

SUMMARY REPORT
843 WEST LAUREL BAY BOULEVARD (FORMERLY 140 WEST LAUREL BAY
BOULEVARD)
LAUREL BAY MILITARY HOUSING AREA
MARINE CORPS AIR STATION BEAUFORT
BEAUFORT, SC

Revision: 0
Prepared for:

Department of the Navy
Naval Facilities Engineering Command, Mid-Atlantic
9324 Virginia Avenue
Norfolk, Virginia 23511-3095

and



Naval Facilities Engineering Command Atlantic
9324 Virginia Avenue
Norfolk, Virginia 23511-3095

JUNE 2021

SUMMARY REPORT
843 WEST LAUREL BAY BOULEVARD (FORMERLY 140 WEST LAUREL BAY
BOULEVARD)
LAUREL BAY MILITARY HOUSING AREA
MARINE CORPS AIR STATION BEAUFORT
BEAUFORT, SC

Revision: 0
Prepared for:

Department of the Navy
Naval Facilities Engineering Command, Mid- Atlantic
9324 Virginia Avenue
Norfolk, Virginia 23511-3095

and



Naval Facilities Engineering Command Atlantic

9324 Virginia Avenue
Norfolk, Virginia 23511-3095

Prepared by:

CDM - AECOM

Multimedia Joint Venture

CDM - AECOM Multimedia Joint Venture
10560 Arrowhead Drive, Suite 500
Fairfax, Virginia 22030

Contract Number: N62470-14-D-9016
CTO WE52
JUNE 2021

Table of Contents

1.0	INTRODUCTION	1
1.1	BACKGROUND INFORMATION.....	1
1.2	UST REMOVAL AND ASSESSMENT PROCESS.....	2
2.0	SAMPLING ACTIVITIES AND RESULTS	3
2.1	UST REMOVAL AND SOIL SAMPLING	3
2.2	SOIL ANALYTICAL RESULTS.....	4
2.3	GROUNDWATER SAMPLING.....	4
2.4	GROUNDWATER ANALYTICAL RESULTS	5
3.0	PROPERTY STATUS.....	5
4.0	REFERENCES	5

Tables

Table 1	Laboratory Analytical Results - Soil
Table 2	Laboratory Analytical Results - Groundwater

Appendices

Appendix A	Multi-Media Selection Process for LBMH
Appendix B	UST Assessment Report
Appendix C	Laboratory Analytical Report - Groundwater
Appendix D	Regulatory Correspondence

List of Acronyms

bgs	below ground surface
BTEX	benzene, toluene, ethylbenzene, and xylenes
CTO	Contract Task Order
COPC	constituents of potential concern
ft	feet
IDIQ	Indefinite Delivery, Indefinite Quantity
IGWA	Initial Groundwater Assessment
JV	Joint Venture
LBMH	Laurel Bay Military Housing
MCAS	Marine Corps Air Station
NAVFAC Mid-Lant	Naval Facilities Engineering Command Mid-Atlantic
NFA	No Further Action
PAH	polynuclear aromatic hydrocarbon
QAPP	Quality Assurance Program Plan
RBSL	risk-based screening level
SCDHEC	South Carolina Department of Health and Environmental Control
Site	LBMH area at MCAS Beaufort, South Carolina
UST	underground storage tank
VISL	vapor intrusion screening level

1.0 INTRODUCTION

The CDM - AECOM Multimedia Joint Venture (JV) was contracted by the Naval Facilities Engineering Command, Mid-Atlantic (NAVFAC Mid-Lant) to provide reporting services for the heating oil underground storage tanks (USTs) located in Laurel Bay Military Housing (LBMH) area at the Marine Corps Air Station (MCAS) Beaufort, South Carolina (Site). This work has been awarded under Contract Task Order (CTO) WE52 of the Indefinite Delivery, Indefinite Quantity (IDIQ) Multimedia Environmental Compliance Contract (Contract No. N62470-14-D-9016).

As of January 2014, the LBMH addresses were re-numbered to comply with the E-911 emergency response addressing system; however, in order to remain consistent with historical sampling and reporting for LBMH area, the residences will continue to be referenced with their original address numbers in sample nomenclature and reporting documents.

This report summarizes the results the environmental investigation activities associated with the storage of home heating oil and the potential release of petroleum constituents at the referenced property. Based on the results of the investigation, a No Further Action (NFA) determination has been made by the South Carolina Department of Health and Environmental Control (SCDHEC) for 843 West Laurel Bay Boulevard (Formerly 140 West Laurel Bay Boulevard). This NFA determination indicates that there are no unacceptable risks to human health or the environment for the petroleum constituents associated with the home heating oil USTs. The following information is included in this report:

- Background information;
- Sampling activities and results; and
- A determination of the property status.

1.1 Background Information

The LBMH area is located approximately 3.5 miles west of MCAS Beaufort. The area is approximately 970 acres in size and serves as an enlisted and officer family housing area. The area is configured with single family and duplex residential structures, and includes recreation, open space, and community facilities. The community includes approximately 1,300 housing units, including legacy Capehart style homes and newer duplex style homes. The housing area

is bordered on the west by salt marshes and the Broad River, and to the north, east and south by uplands. Forested areas lie along the northern and northeastern borders.

Capehart style homes within the LBMH area were formerly heated using heating oil stored in USTs at each residence. There were 1,100 Capehart style housing units in the LBMH area. The newer duplex homes within the LBMH area never utilized heating oil tanks. Heating oil has not been used at Laurel Bay since the mid-1980s. As was the accepted practice at the time, USTs were drained, filled with dirt, capped, and left in place when they were removed from service. Residential USTs are not regulated in the State of South Carolina (i.e., there are no federal or state laws governing installation, management, or removal).

In 2007, MCAS Beaufort began a voluntary program to remove the unregulated, residential USTs and conduct sampling activities to determine if, and to what extent, petroleum constituents may have impacted the surrounding environment. MCAS Beaufort coordinated with SCDHEC to develop removal procedures that were consistent with procedural requirements for regulated USTs. All tank removal activities and follow-on actions are conducted in coordination with SCDHEC. To date, all known USTs have been removed from all residential properties within the LBMH area.

1.2 UST Removal and Assessment Process

During the UST removal process, a soil sample was collected from beneath the UST excavations (approximately 4 to 6 feet [ft] below ground surface [bgs]) and analyzed for a predetermined list of constituents of potential concern (COPCs) associated with the petroleum compounds found in home heating oil. These COPCs, derived from the *Quality Assurance Program Plan (QAPP) for the Underground Storage Tank Management Division, Revision 3.1* (SCDHEC, 2016) and the *Underground Storage Tank Assessment Instructions for Permanent Closure and Change-In-Service*, (SCDHEC, 2018), are as follows:

- benzene, toluene, ethylbenzene, and xylenes (BTEX),
- naphthalene, and
- five select polynuclear aromatic hydrocarbon (PAHs): benzo(a)anthracene, benzo(b)fluoranthene, benzo(k)fluoranthene, chrysene and dibenz(a,h)anthracene.

Soil sample results were submitted by MCAS Beaufort to SCDHEC utilizing SCDHEC's UST Assessment Report form. In accordance with SCDHEC's *QAPP for the UST Management*

Division (SCDHEC, 2016), the soil screening levels consists of SCDHEC risk-based screening levels (RBSLs). It should be noted that the RBSLs for select PAHs were revised in Revision 2.0 of the QAPP (SCDHEC, 2013) and were revised again in Revision 3.0 (SCDHEC, 2015). The screening levels used for evaluation at each site were those levels that were in effect at the time of reporting and review by SCDHEC.

The results of the soil sampling at each former UST location were used to determine if a potential for groundwater contamination exists (i.e., soil results greater than RBSLs) and subsequently to select properties for follow-up initial groundwater assessment (IGWA) sampling. The results of the IGWA sampling (if necessary) are used to determine the presence or absence of the aforementioned COPCs in groundwater and identify whether former UST locations will require additional delineation of COPCs in groundwater. In order to delineate the extent of impact to groundwater, permanent wells are installed and a sampling program is established for those former UST locations where IGWA sampling has indicated the presence of COPCs in excess of the SCDHEC RBSLs for groundwater. Groundwater analytical results are also compared to the site specific groundwater vapor intrusion screening levels (VISLs) to evaluate the potential for vapor intrusion and the necessity for an investigation associated with this media. A multi-media investigation selection process tree, applicable to the LBMH UST investigations, is presented as Appendix A.

2.0 SAMPLING ACTIVITIES AND RESULTS

The following section presents the sampling activities and associated results for 843 West Laurel Bay Boulevard (Formerly 140 West Laurel Bay Boulevard). Details regarding the soil investigation at this site are provided in the *SCDHEC UST Assessment Report – 140 Laurel Bay Boulevard* (MCAS Beaufort, 2009). The UST Assessment Report is provided in Appendix B. Details regarding the IGWA sampling activities at this site are provided in the *Initial Groundwater Investigation Report – July 2013* (Resolution Consultants, 2015). The laboratory report that includes the pertinent IGWA analytical results for this site is presented in Appendix C.

2.1 UST Removal and Soil Sampling

On March 17 2009, two 280 gallon heating oil USTs were removed at 843 West Laurel Bay Boulevard (Formerly 140 West Laurel Bay Boulevard). Tank 1 was removed from the front landscaped bed area adjacent to the driveway. Tank 2 was removed from the front grassed

area adjacent to the driveway. The former UST locations are indicated in Figures 2 and 3 of the UST Assessment Report (Appendix B). The USTs were removed, cleaned, and shipped offsite for recycling. There was no visual evidence (i.e., staining or sheen) of petroleum impact at the time of the UST removal. According to the UST Assessment Report (Appendix B), the depths to the bases of the USTs were 5'11" (Tank 1) and 4'1" (Tank 2) bgs and a single soil sample was collected for each at that depth. The samples were collected from the fill port side of the former USTs to represent a worst case scenario.

Following UST removal, a soil sample was collected from the base of each excavation and shipped to an offsite laboratory for analysis of the petroleum COPCs. Sampling was performed in accordance with applicable South Carolina regulation R.61-92, Part 280 (SCDHEC, 2017) and assessment guidelines.

2.2 Soil Analytical Results

A summary of the laboratory analytical results and SCDHEC RBSLs is presented in Table 1. A copy of the laboratory analytical data report is included in the UST Assessment Report presented in Appendix B. The laboratory analytical data report includes the soil results for the additional PAHs that were analyzed, but do not have associated RBSLs.

The soil sample results were submitted by MCAS Beaufort to SCDHEC utilizing SCDHEC's UST Assessment Report form (Appendix B). The results of the soil sampling at the former UST location were used by MCAS Beaufort, in consultation with SCDHEC, to determine a path forward (i.e., additional sampling or NFA) for the property. The soil results collected from 843 West Laurel Bay Boulevard (Formerly 140 West Laurel Bay Boulevard) were greater than the SCDHEC RBSLs, which indicated further investigation was required. In a letter dated May 18, 2009, SCDHEC requested an IGWA for 843 West Laurel Bay Boulevard (Formerly 140 West Laurel Bay Boulevard) to determine if the groundwater was impacted by petroleum COPCs. SCDHEC's request letter is provided in Appendix D.

2.3 Groundwater Sampling

On July 23, 2013, a temporary monitoring well was installed at 843 West Laurel Bay Boulevard (Formerly 140 West Laurel Bay Boulevard), in accordance with the South Carolina Well Standards and Regulations (R.61-71.H-I, updated June 24, 2016). In order to provide data that can be used to determine whether COPCs are migrating to underlying groundwater, the monitoring well was placed in the same general location as the former heating oil UST.

The former UST locations are indicated in Figures 2 and 3 of the UST Assessment Report (Appendix B). Further details are provided in the *Initial Groundwater Investigation Report – July 2013* (Resolution Consultants, 2015).

The sampling strategy for this phase of the investigation required a one-time sampling event of the temporarily installed monitoring well. Following well installation and development, groundwater samples were collected using low-flow methods and shipped to an offsite laboratory for analysis of the petroleum COPCs. Upon completion of groundwater sampling, the temporary well was abandoned in accordance with the South Carolina Well Standards and Regulations R.61-71 (SCDHEC, 2016). Field forms are provided in the *Initial Groundwater Investigation Report – July 2013* (Resolution Consultants, 2015).

2.4 Groundwater Analytical Results

A summary of the laboratory analytical results and SCDHEC RBSLs is presented in Table 2. A copy of the laboratory analytical data report is included in Appendix C.

The groundwater results collected from 843 West Laurel Bay Boulevard (Formerly 140 West Laurel Bay Boulevard) were less than the SCDHEC RBSLs and the site specific groundwater VISLs (Table 2), which indicated that the groundwater was not impacted by COPCs associated with the former UST at concentrations that present a potential risk to human health and the environment.

3.0 PROPERTY STATUS

Based on the analytical results for groundwater, SCDHEC made the determination that NFA was required for 843 West Laurel Bay Boulevard (Formerly 140 West Laurel Bay Boulevard). This NFA determination was obtained in a letter dated August 6, 2015. SCDHEC's NFA letter is provided in Appendix D.

4.0 REFERENCES

Marine Corps Air Station Beaufort, 2009. *South Carolina Department of Health and Environmental Control (SCDHEC) Underground Storage Tank Assessment Report – 140 Laurel Bay Boulevard, Laurel Bay Military Housing Area*, April 2009.

Resolution Consultants, 2015. *Initial Groundwater Investigation Report – July 2013 for Laurel Bay Military Housing Area, Multiple Properties, Laurel Bay Military Housing Area, Marine Corps Air Station Beaufort, Beaufort, South Carolina*, June 2015.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2013. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 2.0*, April 2013.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2015. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.0*, May 2015.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2016. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.1*, February 2016.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2017. *R.61-92, Part 280, Underground Storage Tank Control Regulations*, March 2017.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2018. *Underground Storage Tank Assessment Instructions for Permanent Closure and Change-In-Service*, March 2018.

South Carolina Department of Health and Environmental Control Bureau of Water, 2016. *R.61-71, Well Standards*, June 2016.

Tables

Table 1
Laboratory Analytical Results - Soil
843 West Laurel Bay Blvd (Formerly 140 West Laurel Bay Blvd)
Laurel Bay Military Housing Area
Marine Corps Air Station Beaufort
Beaufort, South Carolina

Constituent	SCDHEC RBSLs ⁽¹⁾	Results Sample Collected 03/17/09	
		140 Laurel Bay Blvd-1	140 Laurel Bay Blvd-2
Volatile Organic Compounds Analyzed by EPA Method 8260B (mg/kg)			
Benzene	0.003	0.0157	ND
Ethylbenzene	1.15	1.48	4.20
Naphthalene	0.036	14.3	31.1
Toluene	0.627	ND	1.33
Xylenes, Total	13.01	2.24	29.5
Semivolatile Organic Compounds Analyzed by EPA Method 8270D (mg/kg)			
Benzo(a)anthracene	0.66	0.995	ND
Benzo(b)fluoranthene	0.66	0.619	ND
Benzo(k)fluoranthene	0.66	0.528	ND
Chrysene	0.66	1.18	ND
Dibenz(a,h)anthracene	0.66	0.0872	ND

Notes:

⁽¹⁾ South Carolina Risk-Based Screening Levels from the Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 1.0 and 1.1 (SCDHEC, May 2001 and SCDHEC, February 2011) and the Underground Storage Tank Assessment Guidelines (SCDHEC, February 2006).

Bold font indicates the analyte was detected.

Bold font and shading indicates the concentration exceeds the SCDHEC RBSL.

EPA - United States Environmental Protection Agency

mg/kg - milligrams per kilogram

ND - not detected at the reporting limit (or method detection limit if shown on the laboratory report). The soil laboratory report is provided in Appendix B.

RBSL - Risk-Based Screening Level

SCDHEC - South Carolina Department Of Health and Environmental Control

Table 2
Laboratory Analytical Results - Groundwater
843 West Laurel Bay Blvd (Formerly 140 West Laurel Bay Blvd)
Laurel Bay Military Housing Area
Marine Corps Air Station Beaufort
Beaufort, South Carolina

Constituent	SCDHEC RBSLs ⁽¹⁾	Site-Specific Groundwater VISLs (µg/L) ⁽²⁾	Results Sample Collected 07/23/13
Volatile Organic Compounds Analyzed by EPA Method 8260B (µg/L)			
Benzene	5	16.24	ND
Ethylbenzene	700	45.95	ND
Naphthalene	25	29.33	ND
Toluene	1000	105,445	ND
Xylenes, Total	10,000	2,133	ND
Semivolatile Organic Compounds Analyzed by EPA Method 8270D (µg/L)			
Benzo(a)anthracene	10	NA	ND
Benzo(b)fluoranthene	10	NA	ND
Benzo(k)fluoranthene	10	NA	ND
Chrysene	10	NA	ND
Dibenz(a,h)anthracene	10	NA	ND

Notes:

(1) South Carolina Risk-Based Screening Levels from the Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.1 (SCDHEC, February 2016).

(2) Site-specific groundwater VISLs were calculated using the EPA JE Model Spreadsheets (Version 3.1, February 2004) and conservative modeling inputs representative of a small single-story house with an 8 foot ceiling. Site-specific groundwater VISLs were developed based on a target risk level of 1×10^{-6} , a target hazard quotient of 1 (per target organ), and a default residential exposure scenario, assuming exposure for 24 hours/day, 350 days/year, for 26 years. Modeling was performed for a range of depths to groundwater for application as appropriate in different areas of the Laurel Bay Military Housing Area. The most conservative levels are presented for comparison. Refer to Appendix H of the Uniform Federal Policy Sampling Analysis and Sampling Plan for Vapor Media, Revision 4 (Resolution Consultants, April 2017) for additional information.

Bold font indicates the analyte was detected.

Bold font and shading indicates the concentration exceeds the SCDHEC RBSL and/or the Site-Specific Groundwater VISL.

EPA - United States Environmental Protection Agency

JE - Johnson & Ettinger

NA - Not Applicable

ND - not detected at the reporting limit (or method detection limit if shown on the laboratory report). The groundwater laboratory report is provided in Appendix C.

RBSL - Risk-Based Screening Level

SCDHEC - South Carolina Department Of Health and Environmental Control

µg/L - micrograms per liter

VISL - Vapor Intrusion Screening Level

Appendix A
Multi-Media Selection Process for LBMH



Appendix A - Multi-Media Selection Process for LBMH

Appendix B
UST Assessment Report

04189

South Carolina Department of Health and Environmental Control (SCDHEC)
Underground Storage Tank (UST) Assessment Report

Date Received
State Use Only

Submit Completed Form To:
UST Program
SCDHEC
2600 Bull Street
Columbia, South Carolina 29201
Telephone (803) 896-7957

RECEIVED

APR 24 2009

SITE ASSESSMENT,
REMEDICATION &
REVITALIZATION

I. OWNERSHIP OF UST (S)

MCAS Beaufort, Commanding Officer Attn: NREAO (Craig Ehde)		
Owner Name (Corporation, Individual, Public Agency, Other)		
P.O. Box 55001		
Mailing Address		
Beaufort,	South Carolina	29904-5001
City	State	Zip Code
843	228-7317	Craig Ehde
Area Code	Telephone Number	Contact Person

II. SITE IDENTIFICATION AND LOCATION

Permit I.D. #	
Laurel Bay Military Housing Area, Marine Corps Air Station, Beaufort, SC	
Facility Name or Company Site Identifier	
140 Laurel Bay Blvd., Laurel Bay Military Housing Area	
Street Address or State Road (as applicable)	
Beaufort,	Beaufort
City	County

III. INSURANCE INFORMATION

Insurance Statement

The petroleum release reported to DHEC on _____ at Permit ID Number _____ may qualify to receive state monies to pay for appropriate site rehabilitation activities. Before participation is allowed in the State Clean-up fund, written confirmation of the existence or non-existence of an environmental insurance policy is required. **This section must be completed.**

Is there now, or has there ever been an insurance policy or other financial mechanism that covers this UST release? **YES**____ **NO**____ (check one)

If you answered **YES** to the above question, please complete the following information:

My policy provider is: _____
The policy deductible is: _____
The policy limit is: _____

If you have this type of insurance, please include a copy of the policy with this report.

IV. REQUEST FOR SUPERB FUNDING

I **DO** / **DO NOT** wish to participate in the SUPERB Program. (Circle one.)

V. CERTIFICATION (To be signed by the UST owner)

I certify that I have personally examined and am familiar with the information submitted in this and all attached documents; and that based on my inquiry of those individuals responsible for obtaining this information, I believe that the submitted information is true, accurate, and complete.

Name (Type or print.)

Signature

To be completed by Notary Public:

Sworn before me this _____ day of _____, 20____

(Name)

Notary Public for the state of _____
Please affix State seal if you are commissioned outside South Carolina

VI. UST INFORMATION

- A. Product...(ex. Gas, Kerosene).....
- B. Capacity..(ex. 1k, 2k).....
- C. Age.....
- D. Construction Material..(ex. Steel, FRP).....
- E. Month/Year of Last Use.....
- F. Depth (ft.) To Base of Tank.....
- G. Spill Prevention Equipment Y/N.....
- H. Overfill Prevention Equipment Y/N.....
- I. Method of Closure Removed/Filled.....
- J. Date Tanks Removed/Filled.....
- K. Visible Corrosion or Pitting Y/N.....
- L. Visible Holes Y/N.....

140 Laurel Bay Blvd-1		140 Laurel Bay Blvd-2	
Heating oil		Heating oil	
280 gal		280 gal	
Late 1950s		Late 1950s	
Steel		Steel	
Mid 1980s		Mid 1980s	
5'11"		4'1"	
No		No	
No		No	
Removed		Removed	
3/17/09		3/17/09	
Yes		Yes	
Yes		Yes	

M. Method of disposal for any USTs removed from the ground (attach disposal manifests)
 Both tanks were removed from the ground, cleaned and recycled.
 See Attachment "A."

N. Method of disposal for any liquid petroleum, sludges, or wastewaters removed from the USTs (attach disposal manifests)
 Contaminated water from both tanks was pumped from the tanks,
 and disposed of by MCAS.

O. If any corrosion, pitting, or holes were observed, describe the location and extent for each UST
 Corrosion, pitting and holes were found on the entire surface.

VII. PIPING INFORMATION

	140 Laurel Bay Blvd-1		140 Laurel Bay Blvd-2	
A.	Construction Material..(ex. Steel, FRP).....		Steel /Copper	
B.	Distance from UST to Dispenser.....		N/A	
C.	Number of Dispensers.....		N/A	
D.	Type of System Pressure or Suction.....		Suction	
E.	Was Piping Removed from the Ground? Y/N		No*	
F.	Visible Corrosion or Pitting Y/N.....		Yes	
G.	Visible Holes Y/N.....		No	
H.	Age.....		Early 1950s	

- I. If any corrosion, pitting, or holes were observed, describe the location and extent for each piping run.
 Corrosion and pitting were found on the surface of the steel pipe.

*Steel piping was removed. Copper piping was cut & capped at the edge of the excavation.

VIII. BRIEF SITE DESCRIPTION AND HISTORY

The USTs at the residences are constructed of single wall steel and formerly contained fuel oil for heating. These USTs were installed in the late 1950s and last used in the mid 1980s.

IX. SITE CONDITIONS

	Yes	No	Unk
<p>A. Were any petroleum-stained or contaminated soils found in the UST excavation, soil borings, trenches, or monitoring wells?</p> <p>If yes, indicate depth and location on the site map.</p>		X	
<p>B. Were any petroleum odors detected in the excavation, soil borings, trenches, or monitoring wells? Strong odor emitted from both excavations.</p> <p>If yes, indicate location on site map and describe the odor (strong, mild, etc.)</p>	X		
<p>C. Was water present in the UST excavation, soil borings, or trenches?</p> <p>If yes, how far below land surface (indicate location and depth)?</p>		X	
<p>D. Did contaminated soils remain stockpiled on site after closure?</p> <p>If yes, indicate the stockpile location on the site map.</p> <p>Name of DHEC representative authorizing soil removal:</p>		X	
<p>E. Was a petroleum sheen or free product detected on any excavation or boring waters?</p> <p>If yes, indicate location and thickness.</p>		X	

X. SAMPLE INFORMATION

A. SCDHEC Lab Certification Number 96012001

B.

Sample #	Location	Sample Type (Soil/Water)	Soil Type (Sand/Clay)	Depth*	Date/Time of Collection	Collected by	OVA #
140 Bay Blvd-1	Excav at fill end	Soil	Clay	5'11"	3/17/09 1355 hrs	S. Pratt	
140 Bay Blvd-2	Excav at fill end	Soil	Clay	4'1"	3/17/09 1025 hrs	S. Pratt	
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							

* = Depth Below the Surrounding Land Surface

XI. SAMPLING METHODOLOGY

Provide a detailed description of the methods used to collect and store the samples. Also include the preservative used for each sample. Please use the space provided below.

Sampling was performed in accordance with SC DHEC R.61-92 Part 280 and SC DHEC Assessment Guidelines. Sample containers were prepared by the testing laboratory. The grab method was utilized to fill the sample containers leaving as little head space as possible and immediately capped. Soil samples were extracted from area below tank. The samples were marked, logged, and immediately placed in a sample cooler packed with ice to maintain an approximate temperature of 4 degrees Centigrade. Tools were thoroughly cleaned and decontaminated with the seven step decon process after each use. The samples remained in custody of SBG-EEG, Inc. until they were transferred to Test America Incorporated for analysis as documented in the Chain of Custody Record.


XII. RECEPTORS

	Yes	No
<p>A. Are there any lakes, ponds, streams, or wetlands located within 1000 feet of the UST system?</p> <p style="padding-left: 20px;">If yes, indicate type of receptor, distance, and direction on site map.</p>	X	
<p>B. Are there any public, private, or irrigation water supply wells within 1000 feet of the UST system?</p> <p style="padding-left: 20px;">If yes, indicate type of well, distance, and direction on site map.</p>		X
<p>C. Are there any underground structures (e.g., basements) Located within 100 feet of the UST system?</p> <p style="padding-left: 20px;">If yes, indicate type of structure, distance, and direction on site map.</p>		X
<p>D. Are there any underground utilities (e.g., telephone, electricity, gas, water, sewer, storm drain) located within 100 feet of the UST system that could potentially come in contact with the contamination? *Sewer, water, electricity, cable, fiber optic</p> <p style="padding-left: 20px;">If yes, indicate the type of utility, distance, and direction on the site map.</p>	X*	
<p>E. Has contaminated soil been identified at a depth less than 3 feet below land surface in an area that is not capped by asphalt or concrete?</p> <p style="padding-left: 20px;">If yes, indicate the area of contaminated soil on the site map.</p>		X


XIII. SITE MAP

You must supply a scaled site map. It should include all buildings, road names, utilities, tank and dispenser island locations, labeled sample locations, extent of excavation, and any other pertinent information.

(Attach Site Map Here)



140 Laurel Bay Blvd



SBG-EEG, Inc.

Small Business Group, Inc.
10179 Hwy 78
Ladson, SC 29456

Ph. (843) 879-0400


Drawn By: L. DiAsio

Dwg Date: Apr 2009



**FIGURE 1: LOCATION MAP
140 LAUREL BAY BLVD., LAUREL BAY
MCAS BEAUFORT SC**




870' BROAD RIVER




140 LAUREL BAY BLVD.
LAUREL BAY MILITARY HOUSING
MCAS BEAUFORT, SC



POWER
POLE



WASTE WATER



SBG-EEG
10179 HWY 78
LADSON, SC 29456
ph. (843) 879-0400

FIGURE 2 SITE MAP
140 LAUREL BAY BLVD., LAUREL BAY
MCAS BEAUFORT SC
SCALE: GRAPHIC DWG DATE APR 2009




870' BROAD RIVER

140 LAUREL BAY BLVD.



PORCH



FILL END
TANK WAS 45"
BELOW GRADE.

SOIL SAMPLE
140 LAUREL BAY BLVD-1

SIDEWALK

ASPHALT
DRIVEWAY

GRASS

EXCAVATION


280 GALLON
UST

TANK WAS 13"
BELOW GRADE.

SOIL SAMPLE
140 LAUREL BAY BLVD-2

FILL END

GRAPHIC SCALE



SBG-EEG

10179 HWY 78
LADSON, SC 29456

ph. (843) 879-0400

FIGURE 3 UST SAMPLE LOCATIONS
140 LAUREL BAY BLVD., LAUREL BAY
MCAS BEAUFORT SC

SCALE: GRAPHIC

DWG DATE APR 2009



Picture 1: 140 Laurel Bay Blvd site.



Picture 2: UST 140LaurelBayBlvd-1 being removed from the excavation.



Picture 3: UST 140LaurelBayBlvd-2 being removed from the excavation.

XIV. SUMMARY OF ANALYSIS RESULTS

Enter the soil analytical data for each soil boring for all COC in the table below and on the following page.

CoC	140 Laurel Bay Blvd-1		140 Laurel Bay Blvd-2			
Benzene	0.0157 mg/kg		ND			
Toluene	ND		1.33 mg/kg			
Ethylbenzene	1.48 mg/kg		4.20 mg/kg			
Xylenes	2.24 mg/kg		29.5 mg/kg			
Naphthalene	14.3 mg/kg		31.1 mg/kg			
Benzo (a) anthracene	0.995 mg/kg		ND			
Benzo (b) fluoranthene	0.619 mg/kg		ND			
Benzo (k) fluoranthene	0.528 mg/kg		ND			
Chrysene	1.18 mg/kg		ND			
Dibenz (a, h) anthracene	0.0872 mg/kg		ND			
TPH (EPA 3550)						

CoC	SB-9	SB-10	SB-11	SB-12	SB-13	SB-14	SB-15	SB-16
Benzene								
Toluene								
Ethylbenzene								
Xylenes								
Naphthalene								
Benzo (a) anthracene								
Benzo (b) fluoranthene								
Benzo (k) fluoranthene								
Chrysene								
Dibenz (a, h) anthracene								
TPH (EPA 3550)								

SUMMARY OF ANALYSIS RESULTS (cont'd)

Enter the ground water analytical data for each sample for all CoC in the table below. If free product is present, indicate the measured thickness to the nearest 0.01 feet.

CoC	RBSL (µg/l)	W-1	W-2	W -3	W -4
Free Product Thickness	None				
Benzene	5				
Toluene	1,000				
Ethylbenzene	700				
Xylenes	10,000				
Total BTEX	N/A				
MTBE	40				
Naphthalene	25				
Benzo (a) anthracene	10				
Benzo (b) flouranthene	10				
Benzo (k) flouranthene	10				
Chrysene	10				
Dibenz (a, h) anthracene	10				
EDB	.05				
1,2-DCA	5				
Lead	Site specific				

XV. ANALYTICAL RESULTS

You must submit the laboratory report and chain-of-custody form for the samples. These samples must be analyzed by a South Carolina certified laboratory.

(Attach Certified Analytical Results and Chain-of-Custody Here)
(Please see Form #4)

March 31, 2009 5:14:39PM

Client: EEG - Env. Enterprise Group (2449)
10179 Highway 78
Ladson, SC 29456
Attn: Tom McElwee

Work Order: NSC1899
Project Name: Laurel Bay Housing Project
Project Nbr: [none]
P/O Nbr: 08087
Date Received: 03/20/09

SAMPLE IDENTIFICATION	LAB NUMBER	COLLECTION DATE AND TIME
142 Laurel Bay Blvd.	NSC1899-01	03/16/09 09:15
140 Laurel Bay Blvd.-1	NSC1899-02	03/17/09 13:55
140 Laurel Bay Blvd.-2	NSC1899-03	03/17/09 10:25
144 Laurel Bay Blvd.	NSC1899-04	03/18/09 10:30
148 Laurel Bay Blvd.	NSC1899-05	03/19/09 10:20

An executed copy of the chain of custody, the project quality control data, and the sample receipt form are also included as an addendum to this report. If you have any questions relating to this analytical report, please contact your Laboratory Project Manager at 1-800-765-0980. Any opinions, if expressed, are outside the scope of the Laboratory's accreditation.

This material is intended only for the use of the individual(s) or entity to whom it is addressed, and may contain information that is privileged and confidential. If you are not the intended recipient, or the employee or agent responsible for delivering this material to the intended recipient, you are hereby notified that any dissemination, distribution, or copying of this material is strictly prohibited. If you have received this material in error, please notify us immediately at 615-726-0177.

The Chain(s) of Custody, 2 pages, are included and are an integral part of this report.


These results relate only to the items tested. This report shall not be reproduced except in full and with permission of the laboratory.

All solids results are reported in wet weight unless specifically stated.

Estimated uncertainty is available upon request.

This report has been electronically signed.

Report Approved By:



Roxanne Connor

Program Manager - Conventional Accounts

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwec

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

ANALYTICAL REPORT

Analyte	Result	Flag	Units	MRL	Dilution Factor	Analysis Date/Time	Method	Batch
Sample ID: NSC1899-01 (142 Laurel Bay Blvd. - Soil) Sampled: 03/16/09 09:15								
Polyaromatic Hydrocarbons by EPA 8270D								
Acenaphthene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Acenaphthylene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Anthracene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Benzo (a) anthracene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Benzo (a) pyrene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Benzo (b) fluoranthene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Benzo (g,h,i) perylene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Benzo (k) fluoranthene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Chrysene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Dibenz (a,h) anthracene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Fluoranthene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Fluorene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Indeno (1,2,3-cd) pyrene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Naphthalene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Phenanthrene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
Pyrene	ND		mg/kg dry	0.0820	1	03/23/09 22:12	SW846 8270D	9033305
<i>Surr: Terphenyl-d14 (26-128%)</i>	87 %					03/23/09 22:12	SW846 8270D	9033305
<i>Surr: 2-Fluorobiphenyl (19-109%)</i>	74 %					03/23/09 22:12	SW846 8270D	9033305
<i>Surr: Nitrobenzene-d5 (22-104%)</i>	67 %					03/23/09 22:12	SW846 8270D	9033305
General Chemistry Parameters								
% Dry Solids	80.4		%	0.500	1	03/26/09 08:19	SW-846	9033632
Selected Volatile Organic Compounds by EPA Method 8260B								
Benzene	ND		mg/kg dry	0.00204	1	03/25/09 23:19	SW846 8260B	9033095
Ethylbenzene	ND		mg/kg dry	0.00204	1	03/25/09 23:19	SW846 8260B	9033095
Naphthalene	0.00608		mg/kg dry	0.00510	1	03/25/09 23:19	SW846 8260B	9033095
Toluene	ND		mg/kg dry	0.00204	1	03/25/09 23:19	SW846 8260B	9033095
Xylenes, total	ND		mg/kg dry	0.00510	1	03/25/09 23:19	SW846 8260B	9033095
<i>Surr: 1,2-Dichloroethane-d4 (41-150%)</i>	92 %					03/25/09 23:19	SW846 8260B	9033095
<i>Surr: Dibromofluoromethane (55-139%)</i>	104 %					03/25/09 23:19	SW846 8260B	9033095
<i>Surr: Toluene-d8 (57-148%)</i>	115 %					03/25/09 23:19	SW846 8260B	9033095
<i>Surr: 4-Bromofluorobenzene (58-150%)</i>	145 %					03/25/09 23:19	SW846 8260B	9033095

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

ANALYTICAL REPORT

Analyte	Result	Flag	Units	MRL	Dilution Factor	Analysis Date/Time	Method	Batch
Sample ID: NSC1899-02 (140 Laurel Bay Blvd.-1 - Soil) Sampled: 03/17/09 13:55								
Polyaromatic Hydrocarbons by EPA 8270D								
Acenaphthene	ND		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Acenaphthylene	ND		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Anthracene	0.697		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Benzo (a) anthracene	0.995		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Benzo (a) pyrene	0.549		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Benzo (b) fluoranthene	0.619		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Benzo (g,h,i) perylene	0.207		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Benzo (k) fluoranthene	0.528		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Chrysene	1.18		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Dibenz (a,h) anthracene	0.0872		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Fluoranthene	2.11		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Fluorene	ND		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Indeno (1,2,3-cd) pyrene	0.216		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Naphthalene	12.3		mg/kg dry	0.421	5	03/24/09 12:28	SW846 8270D	9033305
Phenanthrene	9.51		mg/kg dry	0.421	5	03/24/09 12:28	SW846 8270D	9033305
Pyrene	2.08		mg/kg dry	0.0842	1	03/23/09 22:35	SW846 8270D	9033305
Surr: Terphenyl-d14 (26-128%)	95 %					03/23/09 22:35	SW846 8270D	9033305
Surr: 2-Fluorobiphenyl (19-109%)	88 %					03/23/09 22:35	SW846 8270D	9033305
Surr: Nitrobenzene-d5 (22-104%)	199 %	ZX				03/23/09 22:35	SW846 8270D	9033305
General Chemistry Parameters								
% Dry Solids	79.0		%	0.500	1	03/26/09 08:19	SW-846	9033632
Selected Volatile Organic Compounds by EPA Method 8260B								
Benzene	0.0157		mg/kg dry	0.00174	1	03/26/09 00:20	SW846 8260B	9033095
Ethylbenzene	1.48		mg/kg dry	0.101	50	03/26/09 17:29	SW846 8260B	9034182
Naphthalene	14.3		mg/kg dry	0.506	100	03/27/09 14:36	SW846 8260B	9034202
Toluene	ND		mg/kg dry	0.00174	1	03/26/09 00:20	SW846 8260B	9033095
Xylenes, total	2.24		mg/kg dry	0.253	50	03/26/09 17:29	SW846 8260B	9034182
Surr: 1,2-Dichloroethane-d4 (41-150%)	89 %					03/26/09 00:20	SW846 8260B	9033095
Surr: 1,2-Dichloroethane-d4 (41-150%)	88 %					03/26/09 17:29	SW846 8260B	9034182
Surr: 1,2-Dichloroethane-d4 (41-150%)	91 %					03/27/09 14:36	SW846 8260B	9034202
Surr: Dibromofluoromethane (55-139%)	91 %					03/26/09 00:20	SW846 8260B	9033095
Surr: Dibromofluoromethane (55-139%)	93 %					03/26/09 17:29	SW846 8260B	9034182
Surr: Dibromofluoromethane (55-139%)	94 %					03/27/09 14:36	SW846 8260B	9034202
Surr: Toluene-d8 (57-148%)	154 %	ZX				03/26/09 00:20	SW846 8260B	9033095
Surr: Toluene-d8 (57-148%)	105 %					03/26/09 17:29	SW846 8260B	9034182
Surr: Toluene-d8 (57-148%)	103 %					03/27/09 14:36	SW846 8260B	9034202
Surr: 4-Bromofluorobenzene (58-150%)	136 %					03/26/09 00:20	SW846 8260B	9033095
Surr: 4-Bromofluorobenzene (58-150%)	108 %					03/26/09 17:29	SW846 8260B	9034182
Surr: 4-Bromofluorobenzene (58-150%)	108 %					03/27/09 14:36	SW846 8260B	9034202

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

ANALYTICAL REPORT

Analyte	Result	Flag	Units	MRL	Dilution Factor	Analysis Date/Time	Method	Batch
Sample ID: NSC1899-03 (140 Laurel Bay Blvd.-2 - Soil) Sampled: 03/17/09 10:25								
Polyaromatic Hydrocarbons by EPA 8270D								
Acenaphthene	ND		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Acenaphthylene	ND		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Anthracene	0.540		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Benzo (a) anthracene	ND		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Benzo (a) pyrene	ND		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Benzo (b) fluoranthene	ND		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Benzo (g,h,i) perylene	ND		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Benzo (k) fluoranthene	ND		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Chrysene	ND		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Dibenz (a,h) anthracene	ND		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Fluoranthene	ND		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Fluorene	2.90		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Indeno (1,2,3-cd) pyrene	ND		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Naphthalene	8.56		mg/kg dry	0.449	5	03/24/09 12:51	SW846 8270D	9033305
Phenanthrene	8.58		mg/kg dry	0.449	5	03/24/09 12:51	SW846 8270D	9033305
Pyrene	0.698		mg/kg dry	0.0898	1	03/23/09 22:58	SW846 8270D	9033305
Surr: Terphenyl-d14 (26-128%)	83 %					03/23/09 22:58	SW846 8270D	9033305
Surr: 2-Fluorobiphenyl (19-109%)	77 %					03/23/09 22:58	SW846 8270D	9033305
Surr: Nitrobenzene-d5 (22-104%)	139 %	ZX				03/23/09 22:58	SW846 8270D	9033305
General Chemistry Parameters								
% Dry Solids	72.4		%	0.500	1	03/26/09 08:19	SW-846	9033632
Selected Volatile Organic Compounds by EPA Method 8260B								
Benzene	ND		mg/kg dry	0.133	50	03/26/09 18:00	SW846 8260B	9034182
Ethylbenzene	4.20		mg/kg dry	0.133	50	03/26/09 18:00	SW846 8260B	9034182
Naphthalene	31.1		mg/kg dry	3.32	500	03/27/09 15:06	SW846 8260B	9034202
Toluene	1.33		mg/kg dry	0.133	50	03/26/09 18:00	SW846 8260B	9034182
Xylenes, total	29.5		mg/kg dry	0.332	50	03/26/09 18:00	SW846 8260B	9034182
Surr: 1,2-Dichloroethane-d4 (41-150%)	89 %					03/26/09 18:00	SW846 8260B	9034182
Surr: 1,2-Dichloroethane-d4 (41-150%)	89 %					03/27/09 15:06	SW846 8260B	9034202
Surr: Dibromofluoromethane (55-139%)	91 %					03/26/09 18:00	SW846 8260B	9034182
Surr: Dibromofluoromethane (55-139%)	96 %					03/27/09 15:06	SW846 8260B	9034202
Surr: Toluene-d8 (57-148%)	108 %					03/26/09 18:00	SW846 8260B	9034182
Surr: Toluene-d8 (57-148%)	102 %					03/27/09 15:06	SW846 8260B	9034202
Surr: 4-Bromofluorobenzene (58-150%)	107 %					03/26/09 18:00	SW846 8260B	9034182
Surr: 4-Bromofluorobenzene (58-150%)	110 %					03/27/09 15:06	SW846 8260B	9034202

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

ANALYTICAL REPORT

Analyte	Result	Flag	Units	MRL	Dilution Factor	Analysis Date/Time	Method	Batch
Sample ID: NSC1899-04 (144 Laurel Bay Blvd. - Soil) Sampled: 03/18/09 10:30								
Polyaromatic Hydrocarbons by EPA 8270D								
Acenaphthene	ND		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Acenaphthylene	ND		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Anthracene	ND		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Benzo (a) anthracene	0.0973		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Benzo (a) pyrene	0.0920		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Benzo (b) fluoranthene	0.170		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Benzo (g,h,i) perylene	ND		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Benzo (k) fluoranthene	0.0994		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Chrysene	0.166		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Dibenz (a,h) anthracene	ND		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Fluoranthene	0.161		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Fluorene	ND		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Indeno (1,2,3-cd) pyrene	ND		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Naphthalene	ND		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Phenanthrene	ND		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
Pyrene	0.228		mg/kg dry	0.0829	1	03/27/09 10:53	SW846 8270D	9033201
<i>Surr: Terphenyl-d14 (26-128%)</i>	69 %					03/27/09 10:53	SW846 8270D	9033201
<i>Surr: 2-Fluorobiphenyl (19-109%)</i>	58 %					03/27/09 10:53	SW846 8270D	9033201
<i>Surr: Nitrobenzene-d5 (22-104%)</i>	53 %					03/27/09 10:53	SW846 8270D	9033201
General Chemistry Parameters								
% Dry Solids	80.6		%	0.500	1	03/26/09 08:19	SW-846	9033632
Selected Volatile Organic Compounds by EPA Method 8260B								
Benzene	ND		mg/kg dry	0.00205	1	03/25/09 23:50	SW846 8260B	9033095
Ethylbenzene	ND		mg/kg dry	0.00205	1	03/25/09 23:50	SW846 8260B	9033095
Naphthalene	ND		mg/kg dry	0.00513	1	03/25/09 23:50	SW846 8260B	9033095
Toluene	ND		mg/kg dry	0.00205	1	03/25/09 23:50	SW846 8260B	9033095
Xylenes, total	ND		mg/kg dry	0.00513	1	03/25/09 23:50	SW846 8260B	9033095
<i>Surr: 1,2-Dichloroethane-d4 (41-150%)</i>	90 %					03/25/09 23:50	SW846 8260B	9033095
<i>Surr: Dibromofluoromethane (55-139%)</i>	97 %					03/25/09 23:50	SW846 8260B	9033095
<i>Surr: Toluene-d8 (57-148%)</i>	108 %					03/25/09 23:50	SW846 8260B	9033095
<i>Surr: 4-Bromofluorobenzene (58-150%)</i>	128 %					03/25/09 23:50	SW846 8260B	9033095

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

ANALYTICAL REPORT

Analyte	Result	Flag	Units	MRL	Dilution Factor	Analysis Date/Time	Method	Batch
Sample ID: NSC1899-05 (148 Laurel Bay Blvd. - Soil) Sampled: 03/19/09 10:20								
Polyaromatic Hydrocarbons by EPA 8270D								
Acenaphthene	0.880		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Acenaphthylene	ND		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Anthracene	ND		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Benzo (a) anthracene	0.697		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Benzo (a) pyrene	0.342		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Benzo (b) fluoranthene	0.421		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Benzo (g,h,i) perylene	0.137		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Benzo (k) fluoranthene	0.300		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Chrysene	0.749		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Dibenz (a,h) anthracene	ND		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Fluoranthene	1.27		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Fluorene	1.80		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Indeno (1,2,3-cd) pyrene	0.130		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Naphthalene	2.02		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Phenanthrene	7.51		mg/kg dry	0.749	10	03/27/09 11:14	SW846 8270D	9033201
Pyrene	2.07		mg/kg dry	0.0749	1	03/27/09 00:08	SW846 8270D	9033201
Surr: Terphenyl-d14 (26-128%)	72 %					03/27/09 00:08	SW846 8270D	9033201
Surr: 2-Fluorobiphenyl (19-109%)	49 %					03/27/09 00:08	SW846 8270D	9033201
Surr: Nitrobenzene-d5 (22-104%)	54 %					03/27/09 00:08	SW846 8270D	9033201
General Chemistry Parameters								
% Dry Solids	88.6		%	0.500	1	03/26/09 08:19	SW-846	9033632
Selected Volatile Organic Compounds by EPA Method 8260B								
Benzene	ND		mg/kg dry	0.00197	1	03/26/09 01:21	SW846 8260B	9033095
Ethylbenzene	0.116		mg/kg dry	0.00197	1	03/26/09 01:21	SW846 8260B	9033095
Naphthalene	4.20		mg/kg dry	0.311	50	03/26/09 18:30	SW846 8260B	9034182
Toluene	ND		mg/kg dry	0.00197	1	03/26/09 01:21	SW846 8260B	9033095
Xylenes, total	0.229		mg/kg dry	0.00492	1	03/26/09 01:21	SW846 8260B	9033095
Surr: 1,2-Dichloroethane-d4 (41-150%)	91 %					03/26/09 01:21	SW846 8260B	9033095
Surr: 1,2-Dichloroethane-d4 (41-150%)	91 %					03/26/09 18:30	SW846 8260B	9034182
Surr: Dibromofluoromethane (55-139%)	101 %					03/26/09 01:21	SW846 8260B	9033095
Surr: Dibromofluoromethane (55-139%)	96 %					03/26/09 18:30	SW846 8260B	9034182
Surr: Toluene-d8 (57-148%)	131 %					03/26/09 01:21	SW846 8260B	9033095
Surr: Toluene-d8 (57-148%)	101 %					03/26/09 18:30	SW846 8260B	9034182
Surr: 4-Bromofluorobenzene (58-150%)	675 %	ZX				03/26/09 01:21	SW846 8260B	9033095
Surr: 4-Bromofluorobenzene (58-150%)	101 %					03/26/09 18:30	SW846 8260B	9034182

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

SAMPLE EXTRACTION DATA

Parameter	Batch	Lab Number	Wt/Vol Extracted	Extracted Vol	Date	Analyst	Extraction Method
Polyaromatic Hydrocarbons by EPA 8270D							
SW846 8270D	9033305	NSC1899-01	30.50	1.00	03/23/09 13:50	TEM	EPA 3550B
SW846 8270D	9033305	NSC1899-02	30.20	1.00	03/23/09 13:50	TEM	EPA 3550B
SW846 8270D	9033305	NSC1899-02RE1	30.20	1.00	03/23/09 13:50	TEM	EPA 3550B
SW846 8270D	9033305	NSC1899-03	30.93	1.00	03/23/09 13:50	TEM	EPA 3550B
SW846 8270D	9033305	NSC1899-03RE1	30.93	1.00	03/23/09 13:50	TEM	EPA 3550B
SW846 8270D	9033201	NSC1899-04	30.08	1.00	03/25/09 08:38	DMG	EPA 3550B
SW846 8270D	9033201	NSC1899-05	30.27	1.00	03/25/09 08:38	DMG	EPA 3550B
SW846 8270D	9033201	NSC1899-05RE1	30.27	1.00	03/25/09 08:38	DMG	EPA 3550B
Selected Volatile Organic Compounds by EPA Method 8260B							
SW846 8260B	9033095	NSC1899-01	6.10	5.00	03/16/09 09:15	JRL	EPA 5035
SW846 8260B	9033095	NSC1899-02	7.27	5.00	03/17/09 13:55	JRL	EPA 5035
SW846 8260B	9034182	NSC1899-02RE1	6.25	5.00	03/17/09 13:55	JRL	EPA 5035
SW846 8260B	9034202	NSC1899-02RE2	6.25	5.00	03/17/09 13:55	JRL	EPA 5035
SW846 8260B	9033095	NSC1899-03	5.53	5.00	03/17/09 10:25	JRL	EPA 5035
SW846 8260B	9034182	NSC1899-03RE1	5.20	5.00	03/17/09 10:25	JRL	EPA 5035
SW846 8260B	9034202	NSC1899-03RE2	5.20	5.00	03/17/09 10:25	JRL	EPA 5035
SW846 8260B	9033095	NSC1899-04	6.05	5.00	03/18/09 10:30	JRL	EPA 5035
SW846 8260B	9033095	NSC1899-05	5.74	5.00	03/19/09 10:20	JRL	EPA 5035
SW846 8260B	9034182	NSC1899-05RE1	4.54	5.00	03/19/09 10:20	JRL	EPA 5035

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

PROJECT QUALITY CONTROL DATA

Blank

Analyte	Blank Value	Q	Units	Q.C. Batch	Lab Number	Analyzed Date/Time
Polyaromatic Hydrocarbons by EPA 8270D						
9033201-BLK1						
Acenaphthene	<0.0310		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Acenaphthylene	<0.0320		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Anthracene	<0.0330		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Benzo (a) anthracene	<0.0380		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Benzo (a) pyrene	<0.0290		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Benzo (b) fluoranthene	<0.0320		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Benzo (g,h,i) perylene	<0.0290		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Benzo (k) fluoranthene	<0.0290		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Chrysene	<0.0390		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Dibenz (a,h) anthracene	<0.0310		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Fluoranthene	<0.0340		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Fluorene	<0.0390		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Indeno (1,2,3-cd) pyrene	<0.0310		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Naphthalene	<0.0410		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Phenanthrene	<0.0340		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Pyrene	<0.0410		mg/kg wet	9033201	9033201-BLK1	03/26/09 21:41
Surrogate: Terphenyl-d14	68%			9033201	9033201-BLK1	03/26/09 21:41
Surrogate: 2-Fluorobiphenyl	62%			9033201	9033201-BLK1	03/26/09 21:41
Surrogate: Nitrobenzene-d5	62%			9033201	9033201-BLK1	03/26/09 21:41
9033305-BLK1						
Acenaphthene	<0.0310		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Acenaphthylene	<0.0320		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Anthracene	<0.0330		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Benzo (a) anthracene	<0.0380		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Benzo (a) pyrene	<0.0290		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Benzo (b) fluoranthene	<0.0320		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Benzo (g,h,i) perylene	<0.0290		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Benzo (k) fluoranthene	<0.0290		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Chrysene	<0.0390		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Dibenz (a,h) anthracene	<0.0310		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Fluoranthene	<0.0340		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Fluorene	<0.0390		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Indeno (1,2,3-cd) pyrene	<0.0310		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Naphthalene	<0.0410		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Phenanthrene	<0.0340		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Pyrene	<0.0410		mg/kg wet	9033305	9033305-BLK1	03/23/09 18:25
Surrogate: Terphenyl-d14	100%			9033305	9033305-BLK1	03/23/09 18:25
Surrogate: 2-Fluorobiphenyl	91%			9033305	9033305-BLK1	03/23/09 18:25
Surrogate: Nitrobenzene-d5	93%			9033305	9033305-BLK1	03/23/09 18:25

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

PROJECT QUALITY CONTROL DATA
Blank - Cont.

Analyte	Blank Value	Q	Units	Q.C. Batch	Lab Number	Analyzed Date/Time
Selected Volatile Organic Compounds by EPA Method 8260B						
9033095-BLK1						
Benzene	<0.000670		mg/kg wet	9033095	9033095-BLK1	03/25/09 20:16
Ethylbenzene	<0.000670		mg/kg wet	9033095	9033095-BLK1	03/25/09 20:16
Naphthalene	<0.00151		mg/kg wet	9033095	9033095-BLK1	03/25/09 20:16
Toluene	<0.000670		mg/kg wet	9033095	9033095-BLK1	03/25/09 20:16
Xylenes, total	<0.00172		mg/kg wet	9033095	9033095-BLK1	03/25/09 20:16
Surrogate: 1,2-Dichloroethane-d4	104%			9033095	9033095-BLK1	03/25/09 20:16
Surrogate: Dibromofluoromethane	95%			9033095	9033095-BLK1	03/25/09 20:16
Surrogate: Toluene-d8	101%			9033095	9033095-BLK1	03/25/09 20:16
Surrogate: 4-Bromofluorobenzene	116%			9033095	9033095-BLK1	03/25/09 20:16
9034182-BLK1						
Benzene	<0.000670		mg/kg wet	9034182	9034182-BLK1	03/26/09 15:11
Ethylbenzene	<0.000670		mg/kg wet	9034182	9034182-BLK1	03/26/09 15:11
Naphthalene	<0.00151		mg/kg wet	9034182	9034182-BLK1	03/26/09 15:11
Toluene	<0.000670		mg/kg wet	9034182	9034182-BLK1	03/26/09 15:11
Xylenes, total	<0.00172		mg/kg wet	9034182	9034182-BLK1	03/26/09 15:11
Surrogate: 1,2-Dichloroethane-d4	95%			9034182	9034182-BLK1	03/26/09 15:11
Surrogate: Dibromofluoromethane	101%			9034182	9034182-BLK1	03/26/09 15:11
Surrogate: Toluene-d8	100%			9034182	9034182-BLK1	03/26/09 15:11
Surrogate: 4-Bromofluorobenzene	112%			9034182	9034182-BLK1	03/26/09 15:11
9034202-BLK1						
Benzene	<0.000670		mg/kg wet	9034202	9034202-BLK1	03/27/09 13:23
Ethylbenzene	<0.000670		mg/kg wet	9034202	9034202-BLK1	03/27/09 13:23
Naphthalene	<0.00151		mg/kg wet	9034202	9034202-BLK1	03/27/09 13:23
Toluene	<0.000670		mg/kg wet	9034202	9034202-BLK1	03/27/09 13:23
Xylenes, total	<0.00172		mg/kg wet	9034202	9034202-BLK1	03/27/09 13:23
Surrogate: 1,2-Dichloroethane-d4	88%			9034202	9034202-BLK1	03/27/09 13:23
Surrogate: Dibromofluoromethane	97%			9034202	9034202-BLK1	03/27/09 13:23
Surrogate: Toluene-d8	98%			9034202	9034202-BLK1	03/27/09 13:23
Surrogate: 4-Bromofluorobenzene	104%			9034202	9034202-BLK1	03/27/09 13:23

Client EEG - Env. Enterprise Group (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NSC1899
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 03/20/09 08:00

PROJECT QUALITY CONTROL DATA
Duplicate

Analyte	Orig. Val.	Duplicate	Q	Units	RPD	Limit	Batch	Sample Duplicated	Analyzed Date/Time
General Chemistry Parameters									
9033632-DUP1									
% Dry Solids	84.3	86.9		%	3	20	9033632	NSC1794-05	03/26/09 08:19

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

PROJECT QUALITY CONTROL DATA
LCS

Analyte	Known Val.	Analyzed Val	Q	Units	% Rec.	Target Range	Batch	Analyzed Date/Time
Polyaromatic Hydrocarbons by EPA 8270D								
9033201-BS1								
Acenaphthene	1.67	1.49		mg/kg wet	89%	52 - 106	9033201	03/26/09 22:02
Acenaphthylene	1.67	1.51		mg/kg wet	91%	53 - 109	9033201	03/26/09 22:02
Anthracene	1.67	1.66		mg/kg wet	100%	54 - 124	9033201	03/26/09 22:02
Benzo (a) anthracene	1.67	1.44		mg/kg wet	87%	53 - 111	9033201	03/26/09 22:02
Benzo (a) pyrene	1.67	1.61		mg/kg wet	97%	52 - 122	9033201	03/26/09 22:02
Benzo (b) fluoranthene	1.67	1.57		mg/kg wet	94%	48 - 115	9033201	03/26/09 22:02
Benzo (g,h,i) perylene	1.67	1.46		mg/kg wet	88%	46 - 114	9033201	03/26/09 22:02
Benzo (k) fluoranthene	1.67	1.46		mg/kg wet	88%	41 - 121	9033201	03/26/09 22:02
Chrysene	1.67	1.44		mg/kg wet	86%	49 - 113	9033201	03/26/09 22:02
Dibenz (a,h) anthracene	1.67	1.49		mg/kg wet	89%	47 - 117	9033201	03/26/09 22:02
Fluoranthene	1.67	1.56		mg/kg wet	94%	52 - 113	9033201	03/26/09 22:02
Fluorene	1.67	1.51		mg/kg wet	91%	54 - 107	9033201	03/26/09 22:02
Indeno (1,2,3-cd) pyrene	1.67	1.50		mg/kg wet	90%	47 - 115	9033201	03/26/09 22:02
Naphthalene	1.67	1.37		mg/kg wet	82%	34 - 107	9033201	03/26/09 22:02
Phenanthrene	1.67	1.47		mg/kg wet	88%	53 - 108	9033201	03/26/09 22:02
Pyrene	1.67	1.47		mg/kg wet	88%	54 - 113	9033201	03/26/09 22:02
Surrogate: Terphenyl-d14	1.67	1.08			65%	26 - 128	9033201	03/26/09 22:02
Surrogate: 2-Fluorobiphenyl	1.67	1.16			69%	19 - 109	9033201	03/26/09 22:02
Surrogate: Nitrobenzene-d5	1.67	1.18			70%	22 - 104	9033201	03/26/09 22:02
9033305-BS1								
Acenaphthene	1.67	1.45		mg/kg wet	87%	52 - 106	9033305	03/23/09 18:47
Acenaphthylene	1.67	1.48		mg/kg wet	89%	53 - 109	9033305	03/23/09 18:47
Anthracene	1.67	1.65		mg/kg wet	99%	54 - 124	9033305	03/23/09 18:47
Benzo (a) anthracene	1.67	1.55		mg/kg wet	93%	53 - 111	9033305	03/23/09 18:47
Benzo (a) pyrene	1.67	1.59		mg/kg wet	96%	52 - 122	9033305	03/23/09 18:47
Benzo (b) fluoranthene	1.67	1.56		mg/kg wet	94%	48 - 115	9033305	03/23/09 18:47
Benzo (g,h,i) perylene	1.67	1.48		mg/kg wet	89%	46 - 114	9033305	03/23/09 18:47
Benzo (k) fluoranthene	1.67	1.53		mg/kg wet	92%	41 - 121	9033305	03/23/09 18:47
Chrysene	1.67	1.53		mg/kg wet	92%	49 - 113	9033305	03/23/09 18:47
Dibenz (a,h) anthracene	1.67	1.53		mg/kg wet	92%	47 - 117	9033305	03/23/09 18:47
Fluoranthene	1.67	1.45		mg/kg wet	87%	52 - 113	9033305	03/23/09 18:47
Fluorene	1.67	1.46		mg/kg wet	88%	54 - 107	9033305	03/23/09 18:47
Indeno (1,2,3-cd) pyrene	1.67	1.54		mg/kg wet	93%	47 - 115	9033305	03/23/09 18:47
Naphthalene	1.67	1.22		mg/kg wet	73%	34 - 107	9033305	03/23/09 18:47
Phenanthrene	1.67	1.50		mg/kg wet	90%	53 - 108	9033305	03/23/09 18:47
Pyrene	1.67	1.66		mg/kg wet	100%	54 - 113	9033305	03/23/09 18:47
Surrogate: Terphenyl-d14	1.67	1.58			95%	26 - 128	9033305	03/23/09 18:47
Surrogate: 2-Fluorobiphenyl	1.67	1.45			87%	19 - 109	9033305	03/23/09 18:47
Surrogate: Nitrobenzene-d5	1.67	1.30			78%	22 - 104	9033305	03/23/09 18:47

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

PROJECT QUALITY CONTROL DATA

LCS - Cont.

Analyte	Known Val.	Analyzed Val	Q	Units	% Rec.	Target Range	Batch	Analyzed Date/Time
Selected Volatile Organic Compounds by EPA Method 8260B								
9033095-BS1								
Benzene	50.0	50.5		ug/kg	101%	76 - 130	9033095	03/25/09 17:42
Ethylbenzene	50.0	53.4		ug/kg	107%	80 - 128	9033095	03/25/09 17:42
Naphthalene	50.0	65.2		ug/kg	130%	63 - 144	9033095	03/25/09 17:42
Toluene	50.0	55.1		ug/kg	110%	80 - 125	9033095	03/25/09 17:42
Xylenes, total	150	160		ug/kg	107%	79 - 130	9033095	03/25/09 17:42
Surrogate: 1,2-Dichloroethane-d4	50.0	49.9			100%	41 - 150	9033095	03/25/09 17:42
Surrogate: Dibromofluoromethane	50.0	48.9			98%	55 - 139	9033095	03/25/09 17:42
Surrogate: Toluene-d8	50.0	51.2			102%	57 - 148	9033095	03/25/09 17:42
Surrogate: 4-Bromofluorobenzene	50.0	53.0			106%	58 - 150	9033095	03/25/09 17:42
9034182-BS1								
Benzene	50.0	51.4		ug/kg	103%	76 - 130	9034182	03/26/09 13:09
Ethylbenzene	50.0	55.2		ug/kg	110%	80 - 128	9034182	03/26/09 13:09
Naphthalene	50.0	60.4		ug/kg	121%	63 - 144	9034182	03/26/09 13:09
Toluene	50.0	56.0		ug/kg	112%	80 - 125	9034182	03/26/09 13:09
Xylenes, total	150	165		ug/kg	110%	79 - 130	9034182	03/26/09 13:09
Surrogate: 1,2-Dichloroethane-d4	50.0	47.9			96%	41 - 150	9034182	03/26/09 13:09
Surrogate: Dibromofluoromethane	50.0	48.3			97%	55 - 139	9034182	03/26/09 13:09
Surrogate: Toluene-d8	50.0	51.2			102%	57 - 148	9034182	03/26/09 13:09
Surrogate: 4-Bromofluorobenzene	50.0	52.4			105%	58 - 150	9034182	03/26/09 13:09
9034202-BS1								
Benzene	50.0	56.4		ug/kg	113%	76 - 130	9034202	03/27/09 11:21
Ethylbenzene	50.0	61.2		ug/kg	122%	80 - 128	9034202	03/27/09 11:21
Naphthalene	50.0	70.1		ug/kg	140%	63 - 144	9034202	03/27/09 11:21
Toluene	50.0	64.6	L1	ug/kg	129%	80 - 125	9034202	03/27/09 11:21
Xylenes, total	150	182		ug/kg	121%	79 - 130	9034202	03/27/09 11:21
Surrogate: 1,2-Dichloroethane-d4	50.0	44.7			89%	41 - 150	9034202	03/27/09 11:21
Surrogate: Dibromofluoromethane	50.0	49.6			99%	55 - 139	9034202	03/27/09 11:21
Surrogate: Toluene-d8	50.0	50.2			100%	57 - 148	9034202	03/27/09 11:21
Surrogate: 4-Bromofluorobenzene	50.0	57.1			114%	58 - 150	9034202	03/27/09 11:21

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

PROJECT QUALITY CONTROL DATA
LCS Dup

Analyte	Orig. Val.	Duplicate	Q	Units	Spike Conc	% Rec.	Target Range	RPD	Limit	Batch	Sample Duplicated	Analyzed Date/Time
Polyaromatic Hydrocarbons by EPA 8270D												
9033305-BSD1												
Acenaphthenc		1.47		mg/kg wet	1.67	88%	52 - 106	2	33	9033305		03/23/09 19:10
Acenaphthylenc		1.48		mg/kg wet	1.67	89%	53 - 109	0.1	38	9033305		03/23/09 19:10
Anthracenc		1.61		mg/kg wet	1.67	96%	54 - 124	3	32	9033305		03/23/09 19:10
Benzo (a) anthracenc		1.52		mg/kg wet	1.67	91%	53 - 111	2	26	9033305		03/23/09 19:10
Benzo (a) pyrenc		1.61		mg/kg wet	1.67	97%	52 - 122	1	31	9033305		03/23/09 19:10
Benzo (b) fluoranthenc		1.59		mg/kg wet	1.67	96%	48 - 115	2	37	9033305		03/23/09 19:10
Benzo (g,h,i) perylene		1.45		mg/kg wet	1.67	87%	46 - 114	2	28	9033305		03/23/09 19:10
Benzo (k) fluoranthenc		1.46		mg/kg wet	1.67	88%	41 - 121	4	35	9033305		03/23/09 19:10
Chrysenc		1.53		mg/kg wet	1.67	92%	49 - 113	0.09	31	9033305		03/23/09 19:10
Dibenz (a,h) anthracenc		1.50		mg/kg wet	1.67	90%	47 - 117	2	32	9033305		03/23/09 19:10
Fluoranthenc		1.42		mg/kg wet	1.67	85%	52 - 113	2	36	9033305		03/23/09 19:10
Fluorenc		1.46		mg/kg wet	1.67	88%	54 - 107	0.4	35	9033305		03/23/09 19:10
Indeno (1,2,3-cd) pyrenc		1.51		mg/kg wet	1.67	91%	47 - 115	2	28	9033305		03/23/09 19:10
Naphthalenc		1.21		mg/kg wet	1.67	73%	34 - 107	1	34	9033305		03/23/09 19:10
Phcnanthrcnc		1.48		mg/kg wet	1.67	89%	53 - 108	1	33	9033305		03/23/09 19:10
Pyrenc		1.65		mg/kg wet	1.67	99%	54 - 113	0.5	36	9033305		03/23/09 19:10
Surrogate: Terphenyl-d14		1.62		mg/kg wet	1.67	97%	26 - 128			9033305		03/23/09 19:10
Surrogate: 2-Fluorobiphenyl		1.53		mg/kg wet	1.67	92%	19 - 109			9033305		03/23/09 19:10
Surrogate: Nitrobenzene-d5		1.33		mg/kg wet	1.67	80%	22 - 104			9033305		03/23/09 19:10
Selected Volatile Organic Compounds by EPA Method 8260B												
9033095-BSD1												
Benzenc		48.6		ug/kg	50.0	97%	76 - 130	4	43	9033095		03/25/09 18:23
Ethylbenzenc		50.5		ug/kg	50.0	101%	80 - 128	6	48	9033095		03/25/09 18:23
Naphthalenc		63.8		ug/kg	50.0	128%	63 - 144	2	50	9033095		03/25/09 18:23
Toluenc		51.4		ug/kg	50.0	103%	80 - 125	7	44	9033095		03/25/09 18:23
Xylenes, total		152		ug/kg	150	101%	79 - 130	5	48	9033095		03/25/09 18:23
Surrogate: 1,2-Dichloroethane-d4		52.6		ug/kg	50.0	105%	41 - 150			9033095		03/25/09 18:23
Surrogate: Dibromofluoromethane		48.8		ug/kg	50.0	98%	55 - 139			9033095		03/25/09 18:23
Surrogate: Toluene-d8		51.0		ug/kg	50.0	102%	57 - 148			9033095		03/25/09 18:23
Surrogate: 4-Bromofluorobenzenc		55.8		ug/kg	50.0	112%	58 - 150			9033095		03/25/09 18:23
9034182-BSD1												
Benzenc		52.4		ug/kg	50.0	105%	76 - 130	2	43	9034182		03/26/09 13:40
Ethylbenzenc		55.5		ug/kg	50.0	111%	80 - 128	0.5	48	9034182		03/26/09 13:40
Naphthalenc		61.9		ug/kg	50.0	124%	63 - 144	2	50	9034182		03/26/09 13:40
Toluenc		57.0		ug/kg	50.0	114%	80 - 125	2	44	9034182		03/26/09 13:40
Xylenes, total		165		ug/kg	150	110%	79 - 130	0.3	48	9034182		03/26/09 13:40
Surrogate: 1,2-Dichloroethane-d4		47.4		ug/kg	50.0	95%	41 - 150			9034182		03/26/09 13:40
Surrogate: Dibromofluoromethane		48.9		ug/kg	50.0	98%	55 - 139			9034182		03/26/09 13:40
Surrogate: Toluene-d8		50.0		ug/kg	50.0	100%	57 - 148			9034182		03/26/09 13:40

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

PROJECT QUALITY CONTROL DATA
LCS Dup - Cont.

Analyte	Orig. Val.	Duplicate	Q	Units	Spike Conc	% Rec.	Target Range	RPD	Limit	Batch	Sample Duplicated	Analyzed Date/Time
Selected Volatile Organic Compounds by EPA Method 8260B												
9034182-BSD1												
<i>Surrogate: 4-Bromofluorobenzene</i>		52.8		ug/kg	50.0	106%	58 - 150			9034182		03/26/09 13:40
9034202-BSD1												
Benzene		58.0		ug/kg	50.0	116%	76 - 130	3	43	9034202		03/27/09 11:51
Ethylbenzene		61.5		ug/kg	50.0	123%	80 - 128	0.5	48	9034202		03/27/09 11:51
Naphthalene		67.0		ug/kg	50.0	134%	63 - 144	5	50	9034202		03/27/09 11:51
Toluene		62.7		ug/kg	50.0	125%	80 - 125	3	44	9034202		03/27/09 11:51
Xylenes, total		181		ug/kg	150	120%	79 - 130	0.5	48	9034202		03/27/09 11:51
<i>Surrogate: 1,2-Dichloroethane-d4</i>		48.1		ug/kg	50.0	96%	41 - 150			9034202		03/27/09 11:51
<i>Surrogate: Dibromofluoromethane</i>		48.7		ug/kg	50.0	97%	55 - 139			9034202		03/27/09 11:51
<i>Surrogate: Toluene-d8</i>		51.2		ug/kg	50.0	102%	57 - 148			9034202		03/27/09 11:51
<i>Surrogate: 4-Bromofluorobenzene</i>		53.8		ug/kg	50.0	108%	58 - 150			9034202		03/27/09 11:51

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

PROJECT QUALITY CONTROL DATA
Matrix Spike

Analyte	Orig. Val.	MS Val	Q	Units	Spike Conc	% Rec.	Target Range	Batch	Sample Spiked	Analyzed Date/Time
Polyaromatic Hydrocarbons by EPA 8270D										
9033201-MS1										
Accnaphthene	ND	1.53		mg/kg wet	1.62	94%	28 - 117	9033201	NSC1962-04	03/26/09 22:23
Acenaphthylene	ND	1.53		mg/kg wet	1.62	94%	33 - 113	9033201	NSC1962-04	03/26/09 22:23
Anthracene	ND	1.65		mg/kg wet	1.62	102%	31 - 131	9033201	NSC1962-04	03/26/09 22:23
Benzo (a) anthracene	ND	1.43		mg/kg wet	1.62	88%	29 - 124	9033201	NSC1962-04	03/26/09 22:23
Benzo (a) pyrene	ND	1.58		mg/kg wet	1.62	97%	30 - 127	9033201	NSC1962-04	03/26/09 22:23
Benzo (b) fluoranthene	ND	1.47		mg/kg wet	1.62	91%	26 - 128	9033201	NSC1962-04	03/26/09 22:23
Benzo (g,h,i) perylene	ND	1.45		mg/kg wet	1.62	89%	21 - 122	9033201	NSC1962-04	03/26/09 22:23
Benzo (k) fluoranthene	ND	1.55		mg/kg wet	1.62	96%	20 - 130	9033201	NSC1962-04	03/26/09 22:23
Chrysene	ND	1.47		mg/kg wet	1.62	91%	30 - 119	9033201	NSC1962-04	03/26/09 22:23
Dibenz (a,h) anthracene	ND	1.47		mg/kg wet	1.62	90%	27 - 122	9033201	NSC1962-04	03/26/09 22:23
Fluoranthene	ND	1.61		mg/kg wet	1.62	99%	23 - 132	9033201	NSC1962-04	03/26/09 22:23
Fluorene	ND	1.52		mg/kg wet	1.62	94%	38 - 110	9033201	NSC1962-04	03/26/09 22:23
Indeno (1,2,3-cd) pyrene	ND	1.50		mg/kg wet	1.62	92%	24 - 122	9033201	NSC1962-04	03/26/09 22:23
Naphthalene	ND	1.36		mg/kg wet	1.62	84%	14 - 117	9033201	NSC1962-04	03/26/09 22:23
Phenanthrene	ND	1.47		mg/kg wet	1.62	91%	21 - 130	9033201	NSC1962-04	03/26/09 22:23
Pyrene	ND	1.51		mg/kg wet	1.62	93%	24 - 133	9033201	NSC1962-04	03/26/09 22:23
Surrogate: Terphenyl-d14		1.06		mg/kg wet	1.62	66%	26 - 128	9033201	NSC1962-04	03/26/09 22:23
Surrogate: 2-Fluorobiphenyl		1.20		mg/kg wet	1.62	74%	19 - 109	9033201	NSC1962-04	03/26/09 22:23
Surrogate: Nitrobenzene-d5		1.17		mg/kg wet	1.62	72%	22 - 104	9033201	NSC1962-04	03/26/09 22:23
9033305-MS1										
Accnaphthene	ND	0.161	M2	mg/kg dry	2.29	7%	28 - 117	9033305	NSC1899-03	03/23/09 19:33
Acenaphthylene	ND	0.936		mg/kg dry	2.29	41%	33 - 113	9033305	NSC1899-03	03/23/09 19:33
Anthracene	0.540	2.10		mg/kg dry	2.29	68%	31 - 131	9033305	NSC1899-03	03/23/09 19:33
Benzo (a) anthracene	ND	2.01		mg/kg dry	2.29	88%	29 - 124	9033305	NSC1899-03	03/23/09 19:33
Benzo (a) pyrene	ND	2.04		mg/kg dry	2.29	89%	30 - 127	9033305	NSC1899-03	03/23/09 19:33
Benzo (b) fluoranthene	ND	2.07		mg/kg dry	2.29	91%	26 - 128	9033305	NSC1899-03	03/23/09 19:33
Benzo (g,h,i) perylene	ND	1.90		mg/kg dry	2.29	83%	21 - 122	9033305	NSC1899-03	03/23/09 19:33
Benzo (k) fluoranthene	ND	1.88		mg/kg dry	2.29	82%	20 - 130	9033305	NSC1899-03	03/23/09 19:33
Chrysene	0.0831	2.05		mg/kg dry	2.29	86%	30 - 119	9033305	NSC1899-03	03/23/09 19:33
Dibenz (a,h) anthracene	ND	1.93		mg/kg dry	2.29	84%	27 - 122	9033305	NSC1899-03	03/23/09 19:33
Fluoranthene	ND	2.38		mg/kg dry	2.29	104%	23 - 132	9033305	NSC1899-03	03/23/09 19:33
Fluorene	2.90	0.464	M2	mg/kg dry	2.29	-106%	38 - 110	9033305	NSC1899-03	03/23/09 19:33
Indeno (1,2,3-cd) pyrene	ND	1.94		mg/kg dry	2.29	85%	24 - 122	9033305	NSC1899-03	03/23/09 19:33
Naphthalene	8.43	11.9	M1	mg/kg dry	2.29	149%	14 - 117	9033305	NSC1899-03	03/23/09 19:33
Phenanthrene	5.98	8.27		mg/kg dry	2.29	100%	21 - 130	9033305	NSC1899-03	03/23/09 19:33
Pyrene	0.698	2.44		mg/kg dry	2.29	76%	24 - 133	9033305	NSC1899-03	03/23/09 19:33

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

PROJECT QUALITY CONTROL DATA
Matrix Spike - Cont.

Analyte	Orig. Val.	MS Val	Q	Units	Spike Conc	% Rec.	Target Range	Batch	Sample Spiked	Analyzed Date/Time
Polyaromatic Hydrocarbons by EPA 8270D										
9033305-MS1										
<i>Surrogate: Terphenyl-d14</i>		2.00		mg/kg dry	2.29	88%	26 - 128	9033305	NSC1899-03	03/23/09 19:33
<i>Surrogate: 2-Fluorobiphenyl</i>		1.88		mg/kg dry	2.29	82%	19 - 109	9033305	NSC1899-03	03/23/09 19:33
<i>Surrogate: Nitrobenzene-d5</i>		3.67	ZX	mg/kg dry	2.29	160%	22 - 104	9033305	NSC1899-03	03/23/09 19:33
Selected Volatile Organic Compounds by EPA Method 8260B										
9034182-MS1										
Benzene	ND	2.86		mg/kg dry	2.82	101%	33 - 146	9034182	NSC1899-05RE	03/26/09 19:01
Ethylbenzene	0.0709	3.14		mg/kg dry	2.82	109%	16 - 160	9034182	NSC1899-05RE	03/26/09 19:01
Naphthalene	4.20	7.03		mg/kg dry	2.82	101%	10 - 151	9034182	NSC1899-05RE	03/26/09 19:01
Toluene	ND	3.08		mg/kg dry	2.82	109%	30 - 145	9034182	NSC1899-05RE	03/26/09 19:01
Xylenes, total	0.163	9.59		mg/kg dry	8.47	111%	16 - 159	9034182	NSC1899-05RE	03/26/09 19:01
<i>Surrogate: 1,2-Dichloroethane-d4</i>		45.7		ug/kg	50.0	91%	41 - 150	9034182	NSC1899-05RE	03/26/09 19:01
<i>Surrogate: Dibromofluoromethane</i>		49.7		ug/kg	50.0	99%	55 - 139	9034182	NSC1899-05RE	03/26/09 19:01
<i>Surrogate: Toluene-d8</i>		49.9		ug/kg	50.0	100%	57 - 148	9034182	NSC1899-05RE	03/26/09 19:01
<i>Surrogate: 4-Bromofluorobenzene</i>		49.2		ug/kg	50.0	98%	58 - 150	9034182	NSC1899-05RE	03/26/09 19:01

Client EEG - Env. Enterprise Group (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NSC1899
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 03/20/09 08:00

PROJECT QUALITY CONTROL DATA

Matrix Spike Dup

Analyte	Orig. Val.	Duplicate	Q	Units	Spike Conc	% Rec.	Target Range	RPD	Limit	Batch	Sample Duplicated	Analyzed Date/Time
Polyaromatic Hydrocarbons by EPA 8270D												
9033201-MSD1												
Acenaphthene	ND	1.48		mg/kg wet	1.63	91%	28 - 117	3	33	9033201	NSC1962-04	03/26/09 22:44
Acenaphthylene	ND	1.52		mg/kg wet	1.63	93%	33 - 113	0.6	38	9033201	NSC1962-04	03/26/09 22:44
Anthracene	ND	1.64		mg/kg wet	1.63	101%	31 - 131	0.8	32	9033201	NSC1962-04	03/26/09 22:44
Benzo (a) anthracene	ND	1.38		mg/kg wet	1.63	85%	29 - 124	3	26	9033201	NSC1962-04	03/26/09 22:44
Benzo (a) pyrene	ND	1.60		mg/kg wet	1.63	98%	30 - 127	1	31	9033201	NSC1962-04	03/26/09 22:44
Benzo (b) fluoranthene	ND	1.27		mg/kg wet	1.63	78%	26 - 128	14	37	9033201	NSC1962-04	03/26/09 22:44
Benzo (g,h,i) perylene	ND	1.44		mg/kg wet	1.63	88%	21 - 122	0.6	28	9033201	NSC1962-04	03/26/09 22:44
Benzo (k) fluoranthene	ND	1.79		mg/kg wet	1.63	110%	20 - 130	14	35	9033201	NSC1962-04	03/26/09 22:44
Chrysene	ND	1.47		mg/kg wet	1.63	90%	30 - 119	0.05	31	9033201	NSC1962-04	03/26/09 22:44
Dibenz (a,h) anthracene	ND	1.46		mg/kg wet	1.63	90%	27 - 122	0.4	32	9033201	NSC1962-04	03/26/09 22:44
Fluoranthene	ND	1.58		mg/kg wet	1.63	97%	23 - 132	2	36	9033201	NSC1962-04	03/26/09 22:44
Fluorene	ND	1.48		mg/kg wet	1.63	91%	38 - 110	3	35	9033201	NSC1962-04	03/26/09 22:44
Indeno (1,2,3-cd) pyrene	ND	1.53		mg/kg wet	1.63	94%	24 - 122	2	28	9033201	NSC1962-04	03/26/09 22:44
Naphthalene	ND	1.43		mg/kg wet	1.63	88%	14 - 117	5	34	9033201	NSC1962-04	03/26/09 22:44
Phenanthrene	ND	1.49		mg/kg wet	1.63	92%	21 - 130	0.9	33	9033201	NSC1962-04	03/26/09 22:44
Pyrene	ND	1.46		mg/kg wet	1.63	90%	24 - 133	3	36	9033201	NSC1962-04	03/26/09 22:44
Surrogate: Terphenyl-d14		1.06		mg/kg wet	1.63	65%	26 - 128			9033201	NSC1962-04	03/26/09 22:44
Surrogate: 2-Fluorobiphenyl		1.16		mg/kg wet	1.63	71%	19 - 109			9033201	NSC1962-04	03/26/09 22:44
Surrogate: Nitrobenzene-d5		1.17		mg/kg wet	1.63	72%	22 - 104			9033201	NSC1962-04	03/26/09 22:44
9033305-MSD1												
Acenaphthene	ND	2.31	R	mg/kg dry	2.25	102%	28 - 117	174	33	9033305	NSC1899-03	03/23/09 19:55
Acenaphthylene	ND	0.903		mg/kg dry	2.25	40%	33 - 113	4	38	9033305	NSC1899-03	03/23/09 19:55
Anthracene	0.540	2.49		mg/kg dry	2.25	86%	31 - 131	17	32	9033305	NSC1899-03	03/23/09 19:55
Benzo (a) anthracene	ND	2.19		mg/kg dry	2.25	97%	29 - 124	9	26	9033305	NSC1899-03	03/23/09 19:55
Benzo (a) pyrene	ND	2.19		mg/kg dry	2.25	97%	30 - 127	7	31	9033305	NSC1899-03	03/23/09 19:55
Benzo (b) fluoranthene	ND	2.33		mg/kg dry	2.25	103%	26 - 128	12	37	9033305	NSC1899-03	03/23/09 19:55
Benzo (g,h,i) perylene	ND	2.02		mg/kg dry	2.25	90%	21 - 122	6	28	9033305	NSC1899-03	03/23/09 19:55
Benzo (k) fluoranthene	ND	1.95		mg/kg dry	2.25	86%	20 - 130	3	35	9033305	NSC1899-03	03/23/09 19:55
Chrysene	0.0831	2.22		mg/kg dry	2.25	95%	30 - 119	8	31	9033305	NSC1899-03	03/23/09 19:55
Dibenz (a,h) anthracene	ND	2.07		mg/kg dry	2.25	92%	27 - 122	7	32	9033305	NSC1899-03	03/23/09 19:55
Fluoranthene	ND	2.42		mg/kg dry	2.25	107%	23 - 132	2	36	9033305	NSC1899-03	03/23/09 19:55
Fluorene	2.90	0.541	M2	mg/kg dry	2.25	-105%	38 - 110	15	35	9033305	NSC1899-03	03/23/09 19:55
Indeno (1,2,3-cd) pyrene	ND	2.08		mg/kg dry	2.25	92%	24 - 122	7	28	9033305	NSC1899-03	03/23/09 19:55
Naphthalene	8.43	9.79		mg/kg dry	2.25	60%	14 - 117	19	34	9033305	NSC1899-03	03/23/09 19:55
Phenanthrene	5.98	7.74		mg/kg dry	2.25	78%	21 - 130	7	33	9033305	NSC1899-03	03/23/09 19:55
Pyrene	0.698	2.73		mg/kg dry	2.25	90%	24 - 133	11	36	9033305	NSC1899-03	03/23/09 19:55
Surrogate: Terphenyl-d14		2.24		mg/kg dry	2.25	99%	26 - 128			9033305	NSC1899-03	03/23/09 19:55
Surrogate: 2-Fluorobiphenyl		2.06		mg/kg dry	2.25	91%	19 - 109			9033305	NSC1899-03	03/23/09 19:55
Surrogate: Nitrobenzene-d5		3.14	ZX	mg/kg dry	2.25	139%	22 - 104			9033305	NSC1899-03	03/23/09 19:55

Client EEG - Env. Enterprise Group (2449)
 10179 Highway 78
 Ladson, SC 29456
 Attn Tom McElwee

Work Order: NSC1899
 Project Name: Laurel Bay Housing Project
 Project Number: [none]
 Received: 03/20/09 08:00

PROJECT QUALITY CONTROL DATA
Matrix Spike Dup - Cont.

Analyte	Orig. Val.	Duplicate	Q	Units	Spike Conc	% Rec.	Target Range	RPD	Limit	Batch	Sample Duplicated	Analyzed Date/Time
Selected Volatile Organic Compounds by EPA Method 8260B												
9034182-MSD1												
Benzene	ND	3.14		mg/kg dry	2.82	111%	33 - 146	10	43	9034182	NSC1899-05RE	03/26/09 19:31
Ethylbenzene	0.0709	3.44		mg/kg dry	2.82	120%	16 - 160	9	48	9034182	NSC1899-05RE	03/26/09 19:31
Naphthalene	4.20	7.14		mg/kg dry	2.82	104%	10 - 151	2	50	9034182	NSC1899-05RE	03/26/09 19:31
Toluene	ND	3.38		mg/kg dry	2.82	120%	30 - 145	9	44	9034182	NSC1899-05RE	03/26/09 19:31
Xylenes, total	0.163	10.6		mg/kg dry	8.47	123%	16 - 159	10	48	9034182	NSC1899-05RE	03/26/09 19:31
<i>Surrogate: 1,2-Dichloroethane-d4</i>		45.1		ug/kg	50.0	90%	41 - 150			9034182	NSC1899-05RE	03/26/09 19:31
<i>Surrogate: Dibromofluoromethane</i>		49.7		ug/kg	50.0	99%	55 - 139			9034182	NSC1899-05RE	03/26/09 19:31
<i>Surrogate: Toluene-d8</i>		49.4		ug/kg	50.0	99%	57 - 148			9034182	NSC1899-05RE	03/26/09 19:31
<i>Surrogate: 4-Bromofluorobenzene</i>		53.3		ug/kg	50.0	107%	58 - 150			9034182	NSC1899-05RE	03/26/09 19:31

Client EEG - Env. Enterprise Group (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NSC1899
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 03/20/09 08:00

CERTIFICATION SUMMARY

TestAmerica Nashville

Method	Matrix	AIHA	Nelac	South Carolina
SW846 8260B	Soil	N/A	X	X
SW846 8270D	Soil			X
SW-846	Soil			

Client EEG - Env. Enterprise Group (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NSC1899
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 03/20/09 08:00

DATA QUALIFIERS AND DEFINITIONS

L1 Laboratory Control Sample and/or Laboratory Control Sample Duplicate recovery was above acceptance limits.
M1 The MS and/or MSD were above the acceptance limits due to sample matrix interference. See Blank Spike (LCS).
M2 The MS and/or MSD were below the acceptance limits due to sample matrix interference. See Blank Spike (LCS).
R The RPD exceeded the method control limit. The individual analyte QA/QC recoveries, however, were within acceptance limits.
ZX Due to sample matrix effects, the surrogate recovery was outside the acceptance limits.
ND Not detected at the reporting limit (or method detection limit if shown)

METHOD MODIFICATION NOTES

ATTACHMENT A

UST Certificate of Disposal

CONTRACTOR

Small Business Group, Inc.
10179 Highway 78
Ladson, SC 29456

TEL (843) 879-0403
FAX (843) 879-0401

TANK ID & LOCATION

UST 140 Laurel Bay Blvd – 1 & 2, 140 Laurel Bay Blvd, Laurel Bay Housing
Area, MCAS Beaufort, S.C.

DISPOSAL LOCATION

Coastal Auto Salvage Co., Inc.
130 Laurel Bay Road
Beaufort, S.C. 29906

TYPE OF TANK

SIZE (GAL)

Steel

280

CLEANING/DISPOSAL METHOD

The tanks and piping were unearthed, cut open, cleaned with a pressure
washer, cut into sections, and recycled.

DISPOSAL CERTIFICATION

I certify that the above tanks, piping and equipment have been properly
cleaned and disposed of.

TO Wilcher , 4/8/09
(Name) (Date)

Appendix C
Laboratory Analytical Report - Groundwater

Volatile Organic Compounds by GC/MS

Client: AECOM - Resolution Consultants	Laboratory ID: OG25027-013
Description: BEALB140TW01WG20130723	Matrix: Aqueous
Date Sampled: 07/23/2013 1350	
Date Received: 07/25/2013	

Run	Prep Method	Analytical Method	Dilution	Analysis Date	Analyst	Prep Date	Batch
1	5030B	8260B	1	08/02/2013 1658	ALL		26393

Parameter	CAS Number	Analytical Method	Result	Q	LOQ	LOD	DL	Units	Run
Benzene	71-43-2	8260B	ND		0.50	0.25	0.027	ug/L	1
Ethylbenzene	100-41-4	8260B	ND		0.50	0.25	0.17	ug/L	1
Naphthalene	91-20-3	8260B	ND		0.50	0.25	0.12	ug/L	1
Toluene	108-88-3	8260B	ND		0.50	0.25	0.17	ug/L	1
Xylenes (total)	1330-20-7	8260B	ND		0.50	0.25	0.17	ug/L	1

Surrogate	Q	Run 1 % Recovery	Acceptance Limits
1,2-Dichloroethane-d4		103	70-120
Toluene-d8		101	85-120
Bromofluorobenzene		110	75-120
Dibromofluoromethane		98	85-115

PQL = Practical quantitation limit B = Detected in the method blank E = Quantitation of compound exceeded the calibration range H = Out of holding time Q = Surrogate failure
 ND = Not detected at or above the MDL J = Estimated result < PQL and ≥ MDL P = The RPD between two GC columns exceeds 40% N = Recovery is out of criteria L = LCS/LCSD failure
 Where applicable, all soil sample analysis are reported on a dry weight basis unless flagged with a "W" S = MS/MSD failure

Semivolatile Organic Compounds by GC/MS

Client: AECOM - Resolution Consultants	Laboratory ID: OG25027-013
Description: BEALB140TW01WG20130723	Matrix: Aqueous
Date Sampled: 07/23/2013 1350	
Date Received: 07/25/2013	

Run	Prep Method	Analytical Method	Dilution	Analysis Date	Analyst	Prep Date	Batch
1	3520C	8270D	1	07/26/2013 1634	RBH	07/25/2013 1509	25843

Parameter	CAS Number	Analytical Method	Result	Q	LOQ	LOD	DL	Units	Run
Benzo(a)anthracene	56-55-3	8270D	ND		0.22	0.11	0.088	ug/L	1
Benzo(b)fluoranthene	205-99-2	8270D	ND		0.22	0.11	0.094	ug/L	1
Benzo(k)fluoranthene	207-08-9	8270D	ND		0.22	0.11	0.099	ug/L	1
Chrysene	218-01-9	8270D	ND		0.22	0.11	0.058	ug/L	1
Dibenzo(a,h)anthracene	53-70-3	8270D	ND		0.22	0.11	0.062	ug/L	1

Surrogate	Q	Run 1 % Recovery	Acceptance Limits
2-Fluorobiphenyl		82	50-110
Nitrobenzene-d5		85	40-110
Terphenyl-d14		81	50-135

PQL = Practical quantitation limit B = Detected in the method blank E = Quantitation of compound exceeded the calibration range H = Out of holding time Q = Surrogate failure
 ND = Not detected at or above the MDL J = Estimated result < PQL and ≥ MDL P = The RPD between two GC columns exceeds 40% N = Recovery is out of criteria L = LCS/LCSD failure
 Where applicable, all soil sample analysis are reported on a dry weight basis unless flagged with a "W" S = MS/MSD failure

Shealy Environmental Services, Inc.
 106 Vantage Point Drive West Columbia, SC 29172 (803) 791-9700 Fax (803) 791-9111 www.shealylab.com

Level 1 Report v2.1

Appendix D
Regulatory Correspondence



C. Earl Hunter, Commissioner

Promoting and protecting the health of the public and the environment.

May 18, 2009

Commanding Officer
ATTN: S-4 NREAO (Craig Ehde)
MCAS
PO Box 55001
Beaufort, SC 29904-5001

Re: MCAS – Laurel Bay Housing –140 Laurel Bay
Site ID # 04189
UST Closure Report received 24 April 2009
Beaufort County

Dear Mr. Ehde:

The purpose of this letter is to verify a release of fuel oil at the referenced residence. According to information received by the Department, the source of the release is from past onsite use of fuel oil USTs. To date, initial activities by the facility have included tank removal and soil sampling. Based on the information contained in the closure report, a potential violation of the South Carolina Pollution Control Act has occurred in that there has been an unauthorized release of petroleum to the environment.

Additional assessment activities are required for this site. Specifically the Department requests that a groundwater sample be collected from this site. Please note, the Department approved a groundwater sampling proposal for Laurel Bay submitted by MCAS under separate cover dated 16 June 2008.

Should you have any questions, please contact me at 803-896-4179 or cookejt@dhec.sc.gov.

Sincerely,

Jan T. Cooke, Hydrogeologist
AST Petroleum Restoration & Site Environmental Investigations Section
Division of Site Assessment, Remediation & Revitalization
Bureau of Land and Waste Management

cc: Region 8 District EQC



Catherine E. Heigel, Director

Promoting and protecting the health of the public and the environment

Division of Waste Management
Bureau of Land and Waste Management

August 6, 2015

Commanding Officer
Attention: NREAO Mr. William A. Drawdy
United State Marine Corps Air Station
Post Office Box 55001
Beaufort, SC 29904-5001

RE: Approval Response to Comments and Concurrence with Final Initial Groundwater Investigation Report-July 2013
Laurel Bay Military Housing Area Multiple Properties
Dated June 2015

Dear Mr. Drawdy,

The South Carolina Department of Health and Environmental Control (the Department) received groundwater data in the above referenced Groundwater Investigation Report for the addresses attached. The regulatory authority for the investigation and cleanup of releases from these tank systems is the South Carolina Pollution Control Act (S.C. Code Ann. §48-1-10 et seq., as amended).

Per the Department's request, groundwater samples were collected from the attached referenced addresses. The Department reviewed the groundwater data and previous investigations and it agrees with the conclusions and recommendations included in the document. To further assess the impact to groundwater, permanent wells should be installed at the 10 stated addresses. For the remaining 25 addresses, there is no indication of contamination on the property and therefore no further investigation is required at this time.

Please note that the Department's decision is based on information provided by the Marine Corps Air Station (MCAS) to date. Any information found to be contradictory to this decision may require additional action. Furthermore, the Department retains the right to request further investigation if deemed necessary.

If you have any questions, please contact me at petruslb@dhec.sc.gov or 803-898-0294.

Sincerely,

Laurel Petrus
RCRA Federal Facilities Section

Attachment: Specific Property Recommendations

Cc: Russell Berry, EQC Region 8 (via email)
Shawn Dolan, Resolution Consultants (via email)
Bryan Beck, NAVFAC MIDATLANTIC (via email)
Craig Ehde (via email)

Attachment to: Petrus to Drawdy
 Subject: Draft Final Initial Groundwater Investigation Report-July 2013
 Specific Property Recommendations
 Dated August 6, 2015

Draft Final Initial Groundwater Investigation Report for (35 addresses/38 tanks)

Permanent Monitoring Well Investigation recommendation (10 addresses/11 tanks)	
119 Banyan	156 Laurel Bay
128 Banyan	1033 Foxglove
132 Banyan	1055 Gardenia
135 Birch	1059 Gardenia
148 Laurel Bay	1168 Jasmine
No Further Action recommendation (25 addresses/27 tanks):	
115 Banyan	386 Acorn
116 Banyan	395 Acorn
120 Banyan	399 Acorn
124 Banyan	1021 Foxglove
125 Banyan	1027 Foxglove
136 Birch	1030 Foxglove
140 Laurel Bay	1032 Foxglove
144 Laurel Bay	1053 Gardenia
152 Laurel Bay	1058 Gardenia
160 Cypress	1061 Gardenia
263 Beech	1166 Jasmine
269 Birch	1169 Jasmine
295 Birch	