

**SUMMARY REPORT  
510 ALBATROSS DRIVE (FORMERLY 1417 ALBATROSS DRIVE)  
LAUREL BAY MILITARY HOUSING AREA  
MARINE CORPS AIR STATION BEAUFORT  
BEAUFORT, SC**

**Revision: 0  
Prepared for:**

**Department of the Navy  
Naval Facilities Engineering Command, Mid-Atlantic  
9324 Virginia Avenue  
Norfolk, Virginia 23511-3095**

**and**



**Naval Facilities Engineering Command Atlantic  
9324 Virginia Avenue  
Norfolk, Virginia 23511-3095**

**JUNE 2021**

**SUMMARY REPORT**  
**510 ALBATROSS DRIVE (FORMERLY 1417 ALBATROSS DRIVE)**  
**LAUREL BAY MILITARY HOUSING AREA**  
**MARINE CORPS AIR STATION BEAUFORT**  
**BEAUFORT, SC**

**Revision: 0**  
**Prepared for:**

**Department of the Navy**  
**Naval Facilities Engineering Command, Mid- Atlantic**  
**9324 Virginia Avenue**  
**Norfolk, Virginia 23511-3095**

**and**



**Naval Facilities Engineering Command Atlantic**

**9324 Virginia Avenue**  
**Norfolk, Virginia 23511-3095**

**Prepared by:**



**CDM - AECOM Multimedia Joint Venture**  
**10560 Arrowhead Drive, Suite 500**  
**Fairfax, Virginia 22030**

**Contract Number: N62470-14-D-9016**  
**CTO WE52**  
**JUNE 2021**

---

## Table of Contents

<b>1.0</b>	<b>INTRODUCTION .....</b>	<b>1</b>
1.1	BACKGROUND INFORMATION.....	1
1.2	UST REMOVAL AND ASSESSMENT PROCESS.....	2
<b>2.0</b>	<b>SAMPLING ACTIVITIES AND RESULTS .....</b>	<b>3</b>
2.1	UST REMOVAL AND SOIL SAMPLING .....	3
2.2	SOIL ANALYTICAL RESULTS.....	4
2.3	GROUNDWATER SAMPLING.....	4
2.4	GROUNDWATER ANALYTICAL RESULTS .....	5
<b>3.0</b>	<b>PROPERTY STATUS.....</b>	<b>5</b>
<b>4.0</b>	<b>REFERENCES .....</b>	<b>5</b>

## Tables

Table 1	Laboratory Analytical Results - Soil
Table 2	Laboratory Analytical Results - Groundwater

## Appendices

Appendix A	Multi-Media Selection Process for LBMH
Appendix B	UST Assessment Report
Appendix C	Laboratory Analytical Report - Groundwater
Appendix D	Regulatory Correspondence

---

### List of Acronyms

bgs	below ground surface
BTEX	benzene, toluene, ethylbenzene, and xylenes
CTO	Contract Task Order
COPC	constituents of potential concern
ft	feet
IDIQ	Indefinite Delivery, Indefinite Quantity
IGWA	Initial Groundwater Assessment
JV	Joint Venture
LBMH	Laurel Bay Military Housing
MCAS	Marine Corps Air Station
NAVFAC Mid-Lant	Naval Facilities Engineering Command Mid-Atlantic
NFA	No Further Action
PAH	polynuclear aromatic hydrocarbon
QAPP	Quality Assurance Program Plan
RBSL	risk-based screening level
SCDHEC	South Carolina Department of Health and Environmental Control
Site	LBMH area at MCAS Beaufort, South Carolina
UST	underground storage tank
VISL	vapor intrusion screening level

## **1.0 INTRODUCTION**

The CDM - AECOM Multimedia Joint Venture (JV) was contracted by the Naval Facilities Engineering Command, Mid-Atlantic (NAVFAC Mid-Lant) to provide reporting services for the heating oil underground storage tanks (USTs) located in Laurel Bay Military Housing (LBMH) area at the Marine Corps Air Station (MCAS) Beaufort, South Carolina (Site). This work has been awarded under Contract Task Order (CTO) WE52 of the Indefinite Delivery, Indefinite Quantity (IDIQ) Multimedia Environmental Compliance Contract (Contract No. N62470-14-D-9016).

As of January 2014, the LBMH addresses were re-numbered to comply with the E-911 emergency response addressing system; however, in order to remain consistent with historical sampling and reporting for LBMH area, the residences will continue to be referenced with their original address numbers in sample nomenclature and reporting documents.

This report summarizes the results the environmental investigation activities associated with the storage of home heating oil and the potential release of petroleum constituents at the referenced property. Based on the results of the investigation, a No Further Action (NFA) determination has been made by the South Carolina Department of Health and Environmental Control (SCDHEC) for 510 Albatross Drive (Formerly 1417 Albatross Drive). This NFA determination indicates that there are no unacceptable risks to human health or the environment for the petroleum constituents associated with the home heating oil USTs. The following information is included in this report:

- Background information;
- Sampling activities and results; and
- A determination of the property status.

### **1.1 Background Information**

The LBMH area is located approximately 3.5 miles west of MCAS Beaufort. The area is approximately 970 acres in size and serves as an enlisted and officer family housing area. The area is configured with single family and duplex residential structures, and includes recreation, open space, and community facilities. The community includes approximately 1,300 housing units, including legacy Capehart style homes and newer duplex style homes. The housing area

is bordered on the west by salt marshes and the Broad River, and to the north, east and south by uplands. Forested areas lie along the northern and northeastern borders.

Capehart style homes within the LBMH area were formerly heated using heating oil stored in USTs at each residence. There were 1,100 Capehart style housing units in the LBMH area. The newer duplex homes within the LBMH area never utilized heating oil tanks. Heating oil has not been used at Laurel Bay since the mid-1980s. As was the accepted practice at the time, USTs were drained, filled with dirt, capped, and left in place when they were removed from service. Residential USTs are not regulated in the State of South Carolina (i.e., there are no federal or state laws governing installation, management, or removal).

In 2007, MCAS Beaufort began a voluntary program to remove the unregulated, residential USTs and conduct sampling activities to determine if, and to what extent, petroleum constituents may have impacted the surrounding environment. MCAS Beaufort coordinated with SCDHEC to develop removal procedures that were consistent with procedural requirements for regulated USTs. All tank removal activities and follow-on actions are conducted in coordination with SCDHEC. To date, all known USTs have been removed from all residential properties within the LBMH area.

## **1.2 UST Removal and Assessment Process**

During the UST removal process, a soil sample was collected from beneath the UST excavations (approximately 4 to 6 feet [ft] below ground surface [bgs]) and analyzed for a predetermined list of constituents of potential concern (COPCs) associated with the petroleum compounds found in home heating oil. These COPCs, derived from the *Quality Assurance Program Plan (QAPP) for the Underground Storage Tank Management Division, Revision 3.1* (SCDHEC, 2016) and the *Underground Storage Tank Assessment Instructions for Permanent Closure and Change-In-Service*, (SCDHEC, 2018), are as follows:

- benzene, toluene, ethylbenzene, and xylenes (BTEX),
- naphthalene, and
- five select polynuclear aromatic hydrocarbon (PAHs): benzo(a)anthracene, benzo(b)fluoranthene, benzo(k)fluoranthene, chrysene and dibenz(a,h)anthracene.

Soil sample results were submitted by MCAS Beaufort to SCDHEC utilizing SCDHEC's UST Assessment Report form. In accordance with SCDHEC's *QAPP for the UST Management*

*Division* (SCDHEC, 2016), the soil screening levels consists of SCDHEC risk-based screening levels (RBSLs). It should be noted that the RBSLs for select PAHs were revised in Revision 2.0 of the QAPP (SCDHEC, 2013) and were revised again in Revision 3.0 (SCDHEC, 2015). The screening levels used for evaluation at each site were those levels that were in effect at the time of reporting and review by SCDHEC.

The results of the soil sampling at each former UST location were used to determine if a potential for groundwater contamination exists (i.e., soil results greater than RBSLs) and subsequently to select properties for follow-up initial groundwater assessment (IGWA) sampling. The results of the IGWA sampling (if necessary) are used to determine the presence or absence of the aforementioned COPCs in groundwater and identify whether former UST locations will require additional delineation of COPCs in groundwater. In order to delineate the extent of impact to groundwater, permanent wells are installed and a sampling program is established for those former UST locations where IGWA sampling has indicated the presence of COPCs in excess of the SCDHEC RBSLs for groundwater. Groundwater analytical results are also compared to the site specific groundwater vapor intrusion screening levels (VISLs) to evaluate the potential for vapor intrusion and the necessity for an investigation associated with this media. A multi-media investigation selection process tree, applicable to the LBMH UST investigations, is presented as Appendix A.

## **2.0 SAMPLING ACTIVITIES AND RESULTS**

The following section presents the sampling activities and associated results for 510 Albatross Drive (Formerly 1417 Albatross Drive). Details regarding the soil investigation at this site are provided in the *SCDHEC UST Assessment Report – 1417 Albatross Drive* (MCAS Beaufort, 2013). The UST Assessment Report is provided in Appendix B. Details regarding the IGWA sampling activities at this site are provided in the *Initial Groundwater Investigation Report – May and June 2015* (Resolution Consultants, 2015). The laboratory report that includes the pertinent IGWA analytical results for this site is presented in Appendix C.

### **2.1 UST Removal and Soil Sampling**

On August 16, 2012, a single 280 gallon heating oil UST was removed from the concrete porch area at 510 Albatross Drive (Formerly 1417 Albatross Drive). The former UST location is indicated on Figures 2 and 3 of the UST Assessment Report (Appendix B). The UST was removed, cleaned, and shipped offsite for recycling. There was no visual evidence (i.e.,

staining or sheen) of petroleum impact at the time of the UST removal. According to the UST Assessment Report (Appendix B), the depth to the base of the UST was 6'3" bgs and a single soil sample was collected from that depth. The sample was collected from the fill port side of the former UST to represent a worst case scenario.

Following UST removal, a soil sample was collected from the base of the excavation and shipped to an offsite laboratory for analysis of the petroleum COPCs. Sampling was performed in accordance with applicable South Carolina regulation R.61-92, Part 280 (SCDHEC, 2017) and assessment guidelines.

## **2.2 Soil Analytical Results**

A summary of the laboratory analytical results and SCDHEC RBSLs is presented in Table 1. A copy of the laboratory analytical data report is included in the UST Assessment Report presented in Appendix B. The laboratory analytical data report includes the soil results for the additional PAHs that were analyzed, but do not have associated RBSLs.

The soil sample results were submitted by MCAS Beaufort to SCDHEC utilizing SCDHEC's UST Assessment Report form (Appendix B). The results of the soil sampling at the former UST location were used by MCAS Beaufort, in consultation with SCDHEC, to determine a path forward (i.e., additional sampling or NFA) for the property. The soil results collected from 510 Albatross Drive (Formerly 1417 Albatross Drive) were greater than the SCDHEC RBSLs, which indicated further investigation was required. In a letter dated April 7, 2015, SCDHEC requested an IGWA for 510 Albatross Drive (Formerly 1417 Albatross Drive) to determine if the groundwater was impacted by petroleum COPCs. SCDHEC's request letter is provided in Appendix D.

## **2.3 Groundwater Sampling**

On June 17, 2015, a temporary monitoring well was installed at 510 Albatross Drive (Formerly 1417 Albatross Drive), in accordance with the South Carolina Well Standards and Regulations (R.61-71.H-I, updated June 24, 2016). In order to provide data that can be used to determine whether COPCs are migrating to underlying groundwater, the monitoring well was placed in the same general location as the former heating oil UST. The former UST location is indicated on Figures 2 and 3 of the UST Assessment Report (Appendix B). Further details are provided in the *Initial Groundwater Investigation Report – May and June 2015* (Resolution Consultants, 2015).



The sampling strategy for this phase of the investigation required a one-time sampling event of the temporarily installed monitoring well. Following well installation and development, groundwater samples were collected using low-flow methods and shipped to an offsite laboratory for analysis of the petroleum COPCs. Upon completion of groundwater sampling, the temporary well was abandoned in accordance with the South Carolina Well Standards and Regulations R.61-71 (SCDHEC, 2016). Field forms are provided in the *Initial Groundwater Investigation Report – May and June 2015* (Resolution Consultants, 2015).

## **2.4 Groundwater Analytical Results**

A summary of the laboratory analytical results and SCDHEC RBSLs is presented in Table 2. A copy of the laboratory analytical data report is included in Appendix C.

The groundwater results collected from 510 Albatross Drive (Formerly 1417 Albatross Drive) were less than the SCDHEC RBSLs and the site specific groundwater VISLs (Table 2), which indicated that the groundwater was not impacted by COPCs associated with the former UST at concentrations that present a potential risk to human health and the environment.

## **3.0 PROPERTY STATUS**

Based on the analytical results for groundwater, SCDHEC made the determination that NFA was required for 510 Albatross Drive (Formerly 1417 Albatross Drive). This NFA determination was obtained in a letter dated February 22, 2016. SCDHEC's NFA letter is provided in Appendix D.

## **4.0 REFERENCES**

Marine Corps Air Station Beaufort, 2013. *South Carolina Department of Health and Environmental Control (SCDHEC) Underground Storage Tank Assessment Report – 1417 Albatross Drive, Laurel Bay Military Housing Area*, February 2013.

Resolution Consultants, 2015. *Initial Groundwater Investigation Report – May and June 2015 for Laurel Bay Military Housing Area, Multiple Properties, Laurel Bay Military Housing Area, Marine Corps Air Station Beaufort, Beaufort, South Carolina*, October 2015.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2013. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 2.0*, April 2013.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2015. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.0*, May 2015.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2016. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.1*, February 2016.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2017. *R.61-92, Part 280, Underground Storage Tank Control Regulations*, March 2017.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2018. *Underground Storage Tank Assessment Instructions for Permanent Closure and Change-In-Service*, March 2018.

South Carolina Department of Health and Environmental Control Bureau of Water, 2016. *R.61-71, Well Standards*, June 2016.

## Tables

**Table 1**  
**Laboratory Analytical Results - Soil**  
**510 Albatross Drive (Formerly 1417 Albatross Drive)**  
**Laurel Bay Military Housing Area**  
**Marine Corps Air Station Beaufort**  
**Beaufort, South Carolina**

Constituent	SCDHEC RBSLs <sup>(1)</sup>	Results Sample Collected 08/16/12
<b>Volatile Organic Compounds Analyzed by EPA Method 8260B (mg/kg)</b>		
Benzene	0.003	ND
Ethylbenzene	1.15	ND
Naphthalene	0.036	ND
Toluene	0.627	ND
Xylenes, Total	13.01	ND
<b>Semivolatile Organic Compounds Analyzed by EPA Method 8270D (mg/kg)</b>		
Benzo(a)anthracene	0.66	ND
Benzo(b)fluoranthene	0.66	ND
Benzo(k)fluoranthene	0.66	ND
Chrysene	0.66	ND
Dibenz(a,h)anthracene	0.66	ND

**Notes:**

<sup>(1)</sup> South Carolina Risk-Based Screening Levels from the Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 2.0 (SCDHEC, April 2013).

Bold font indicates the analyte was detected.

Bold font and shading indicates the concentration exceeds the SCDHEC RBSL.

EPA - United States Environmental Protection Agency

mg/kg - milligrams per kilogram

ND - not detected at the reporting limit (or method detection limit if shown on the laboratory report). The soil laboratory report is provided in Appendix B.

RBSL - Risk-Based Screening Level

SCDHEC - South Carolina Department Of Health and Environmental Control

**Table 2**  
**Laboratory Analytical Results - Groundwater**  
**510 Albatross Drive (Formerly 1417 Albatross Drive)**  
**Laurel Bay Military Housing Area**  
**Marine Corps Air Station Beaufort**  
**Beaufort, South Carolina**

Constituent	SCDHEC RBSLs <sup>(1)</sup>	Site-Specific Groundwater VISLs (µg/L) <sup>(2)</sup>	Results Sample Collected 06/16/15
<b>Volatile Organic Compounds Analyzed by EPA Method 8260B (µg/L)</b>			
Benzene	5	16.24	ND
Ethylbenzene	700	45.95	ND
Naphthalene	25	29.33	ND
Toluene	1000	105,445	ND
Xylenes, Total	10,000	2,133	ND
<b>Semivolatile Organic Compounds Analyzed by EPA Method 8270D (µg/L)</b>			
Benzo(a)anthracene	10	NA	ND
Benzo(b)fluoranthene	10	NA	ND
Benzo(k)fluoranthene	10	NA	ND
Chrysene	10	NA	ND
Dibenz(a,h)anthracene	10	NA	ND

**Notes:**

<sup>(1)</sup> South Carolina Risk-Based Screening Levels from the Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.1 (SCDHEC, February 2016).

<sup>(2)</sup> Site-specific groundwater VISLs were calculated using the EPA JE Model Spreadsheets (Version 3.1, February 2004) and conservative modeling inputs representative of a small single-story house with an 8 foot ceiling. Site-specific groundwater VISLs were developed based on a target risk level of  $1 \times 10^{-6}$ , a target hazard quotient of 1 (per target organ), and a default residential exposure scenario, assuming exposure for 24 hours/day, 350 days/year, for 26 years. Modeling was performed for a range of depths to groundwater for application as appropriate in different areas of the Laurel Bay Military Housing Area. The most conservative levels are presented for comparison. Refer to Appendix H of the Uniform Federal Policy Sampling Analysis and Sampling Plan for Vapor Media, Revision 4 (Resolution Consultants, April 2017) for additional information.

Bold font indicates the analyte was detected.

Bold font and shading indicates the concentration exceeds the SCDHEC RBSL and/or the Site-Specific Groundwater VISL.

EPA - United States Environmental Protection Agency

JE - Johnson & Ettinger

NA - Not Applicable

ND - not detected at the reporting limit (or method detection limit if shown on the laboratory report). The groundwater laboratory report is provided in Appendix C.

RBSL - Risk-Based Screening Level

SCDHEC - South Carolina Department Of Health and Environmental Control

µg/L - micrograms per liter

VISL - Vapor Intrusion Screening Level

**Appendix A**  
**Multi-Media Selection Process for LBMH**



Appendix A - Multi-Media Selection Process for LBMH

**Appendix B**  
**UST Assessment Report**



South Carolina Department of Health and Environmental Control (SCDHEC)  
**Underground Storage Tank (UST) Assessment Report**

Date Received
State Use Only

Submit Completed Form To:  
 UST Program  
 SCDHEC  
 2600 Bull Street  
 Columbia, South Carolina 29201  
 Telephone (803) 896-7957

**I. OWNERSHIP OF UST (S)**

MCAS Beaufort, Commanding Officer Attn: NREAO (Craig Ehde)		
Owner Name (Corporation, Individual, Public Agency, Other)		
P.O. Box 55001		
Mailing Address		
Beaufort,	South Carolina	29904-5001
City	State	Zip Code
843	228-7317	Craig Ehde
Area Code	Telephone Number	Contact Person

**II. SITE IDENTIFICATION AND LOCATION**

Permit I.D. #	
Laurel Bay Military Housing Area, Marine Corps Air Station, Beaufort, SC	
Facility Name or Company Site Identifier	
1417 Albatross Drive, Laurel Bay Military Housing Area	
Street Address or State Road (as applicable)	
Beaufort,	Beaufort
City	County

### III. INSURANCE INFORMATION

#### Insurance Statement

The petroleum release reported to DHEC on \_\_\_\_\_ at Permit ID Number \_\_\_\_\_ may qualify to receive state monies to pay for appropriate site rehabilitation activities. Before participation is allowed in the State Clean-up fund, written confirmation of the existence or non-existence of an environmental insurance policy is required. **This section must be completed.**

Is there now, or has there ever been an insurance policy or other financial mechanism that covers this UST release? YES \_\_\_\_\_ NO \_\_\_\_\_ (check one)

If you answered YES to the above question, please complete the following information:

My policy provider is: \_\_\_\_\_

The policy deductible is: \_\_\_\_\_

The policy limit is: \_\_\_\_\_

If you have this type of insurance, please include a copy of the policy with this report.

### IV. REQUEST FOR SUPERB FUNDING

I DO / DO NOT wish to participate in the SUPERB Program. (Circle one.)

### V. CERTIFICATION (To be signed by the UST owner)

I certify that I have personally examined and am familiar with the information submitted in this and all attached documents; and that based on my inquiry of those individuals responsible for obtaining this information, I believe that the submitted information is true, accurate, and complete.

\_\_\_\_\_  
Name (Type or print.)

\_\_\_\_\_  
Signature

**To be completed by Notary Public:**

Sworn before me this \_\_\_\_\_ day of \_\_\_\_\_, 20 \_\_\_\_\_

\_\_\_\_\_  
(Name)

Notary Public for the state of \_\_\_\_\_  
*Please affix State seal if you are commissioned outside South Carolina*

## VI. UST INFORMATION

- A. Product...(ex. Gas, Kerosene).....
- B. Capacity..(ex. 1k, 2k).....
- C. Age.....
- D. Construction Material..(ex. Steel, FRP).....
- E. Month/Year of Last Use.....
- F. Depth (ft.) To Base of Tank.....
- G. Spill Prevention Equipment Y/N.....
- H. Overfill Prevention Equipment Y/N.....
- I. Method of Closure Removed/Filled.....
- J. Date Tanks Removed/Filled.....
- K. Visible Corrosion or Pitting Y/N.....
- L. Visible Holes Y/N.....

1417 Albatross		
Heating oil		
280 gal		
Late 1950s		
Steel		
Mid 80s		
6'3"		
No		
No		
Removed		
8/16/2012		
Yes		
Yes		

- M. Method of disposal for any USTs removed from the ground (attach disposal manifests)  
UST 1417Albatross was removed from the ground and disposed  
at a Subtitle "D" landfill. See Attachment "A".
- N. Method of disposal for any liquid petroleum, sludges, or wastewaters removed from the USTs (attach disposal manifests)  
UST 1417Albatross was previously filled with sand by others.
- O. If any corrosion, pitting, or holes were observed, describe the location and extent for each UST  
Corrosion, pitting and holes were found throughout the tank.



## XI. SAMPLING METHODOLOGY

Provide a detailed description of the methods used to collect and store the samples. Also include the preservative used for each sample. Please use the space provided below.

Sampling was performed in accordance with SC DHEC R.61-92 Part 280 and SC DHEC Assessment Guidelines. Sample containers were prepared by the testing laboratory. The grab method was utilized to fill the sample containers leaving as little head space as possible and immediately capped. Soil samples were extracted from area below tank. The samples were marked, logged, and immediately placed in a sample cooler packed with ice to maintain an approximate temperature of 4 degrees Centigrade. Tools were thoroughly cleaned and decontaminated with the seven step decon process after each use. The samples remained in custody of SBG-EEG, Inc. until they were transferred to Test America Incorporated for analysis as documented in the Chain of Custody Record.

---

---

---

---

---

---

---

---

---

---

## XII. RECEPTORS

	Yes	No
<p>A. Are there any lakes, ponds, streams, or wetlands located within 1000 feet of the UST system?  <span style="float: right;">*pond &amp; stormwater canal</span></p> <p>If yes, indicate type of receptor, distance, and direction on site map.</p>	*X	
<p>B. Are there any public, private, or irrigation water supply wells within 1000 feet of the UST system?</p> <p>If yes, indicate type of well, distance, and direction on site map.</p>		X
<p>C. Are there any underground structures (e.g., basements) Located within 100 feet of the UST system?</p> <p>If yes, indicate type of structure, distance, and direction on site map.</p>		X
<p>D. Are there any underground utilities (e.g., telephone, electricity, gas, water, sewer, storm drain) located within 100 feet of the UST system that could potentially come in contact with the contamination?  <span style="float: right;">*Sewer, water, electricity cable &amp; fiber optic</span></p> <p>If yes, indicate the type of utility, distance, and direction on the site map.</p>	*X	
<p>E. Has contaminated soil been identified at a depth less than 3 feet below land surface in an area that is not capped by asphalt or concrete?</p> <p>If yes, indicate the area of contaminated soil on the site map.</p>		X


### **XIII. SITE MAP**

**You must supply a scaled site map. It should include all buildings, road names, utilities, tank and dispenser island locations, labeled sample locations, extent of excavation, and any other pertinent information.**

(Attach Site Map Here)



**1417 ALBATROSS**



**SBG-EEG, Inc.**

7301 Rivers Ave., Suite 245  
N. Charleston SC 29406-9643

Ph. (843) 573-7140

Drawn By: L. DiAsio

Dwg Date: Sept 2012


**FIGURE 1: LOCATION MAP**  
**1417 ALBATROSS DRIVE**  
**LAUREL BAY, BEAUFORT SC**





← STORMWATER CANAL ≈ 900'

POND ≈ 750' ↘



**TANK DEPTH BELOW GRADE**  
**1417ALBATROSS = 39"**

***SBG-EEG***



7301 RIVERS AVE., SUITE 245  
N. CHARLESTON SC 29406-9643  
(843) 573-7140

**FIGURE 2 SITE MAP**  
**1417 ALBATROSS DR., LAUREL BAY**  
**MCAS BEAUFORT SC**

SCALE: GRAPHIC

DWG DATE SEPT 2012





\*A PORTION OF THE PATIO WAS REMOVED TO FACILITATE TANK EXTRACTION.

**SBG-EEG**

7301 RIVERS AVE., SUITE 245  
N. CHARLESTON SC 29406-9643  
(843) 573-7140

FIGURE 3 UST SAMPLE LOCATIONS  
1417 ALBATROSS DR., LAUREL BAY  
MCAS BEAUFORT SC

SCALE: GRAPHIC

DWG DATE SEPT 2012



Picture 1: Location of UST 1417Albatross.



Picture 2: UST 1417Albatross excavation.



#### XIV. SUMMARY OF ANALYSIS RESULTS

Enter the soil analytical data for each soil boring for all COC in the table below and on the following page.

<b>CoC</b>	UST 1417Albatross					
<b>Benzene</b>	ND					
<b>Toluene</b>	ND					
<b>Ethylbenzene</b>	ND					
<b>Xylenes</b>	ND					
<b>Naphthalene</b>	ND					
<b>Benzo (a) anthracene</b>	ND					
<b>Benzo (b) fluoranthene</b>	ND					
<b>Benzo (k) fluoranthene</b>	ND					
<b>Chrysene</b>	ND					
<b>Dibenz (a, h) anthracene</b>	ND					
<b>TPH (EPA 3550)</b>						

<b>CoC</b>							
<b>Benzene</b>							
<b>Toluene</b>							
<b>Ethylbenzene</b>							
<b>Xylenes</b>							
<b>Naphthalene</b>							
<b>Benzo (a) anthracene</b>							
<b>Benzo (b) fluoranthene</b>							
<b>Benzo (k) fluoranthene</b>							
<b>Chrysene</b>							
<b>Dibenz (a, h) anthracene</b>							
<b>TPH (EPA 3550)</b>							

### SUMMARY OF ANALYSIS RESULTS (cont'd)

Enter the ground water analytical data for each sample for all CoC in the table below. If free product is present, indicate the measured thickness to the nearest 0.01 feet.

CoC	RBSL (µg/l)	W-1	W-2	W -3	W -4
Free Product Thickness	None				
Benzene	5				
Toluene	1,000				
Ethylbenzene	700				
Xylenes	10,000				
Total BTEX	N/A				
MTBE	40				
Naphthalene	25				
Benzo (a) anthracene	10				
Benzo (b) flouranthene	10				
Benzo (k) flouranthene	10				
Chrysene	10				
Dibenz (a, h) anthracene	10				
EDB	.05				
1,2-DCA	5				
Lead	Site specific				

## **XV. ANALYTICAL RESULTS**

**You must submit the laboratory report and chain-of-custody form for the samples. These samples must be analyzed by a South Carolina certified laboratory.**

(Attach Certified Analytical Results and Chain-of-Custody Here)  
(Please see Form #4)



# TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING

## ANALYTICAL REPORT

TestAmerica Laboratories, Inc.

TestAmerica Nashville

2960 Foster Creighton Drive

Nashville, TN 37204

Tel: (615)726-0177

TestAmerica Job ID: 490-4605-1

Client Project/Site: Laurel Bay Housing Project


For:

Environmental Enterprise Group

10179 Highway 78

Ladson, South Carolina 29456

Attn: Mr. Tom McElwee



Authorized for release by:

8/31/2012 4:18:11 PM

Ken Hayes

Project Manager I

[ken.hayes@testamericainc.com](mailto:ken.hayes@testamericainc.com)

### LINKS

Review your project  
results through

**Total Access**

Have a Question?



**Ask  
The  
Expert**

Visit us at:

[www.testamericainc.com](http://www.testamericainc.com)

*The test results in this report meet all 2003 NELAC and 2009 TNI requirements for accredited parameters, exceptions are noted in this report. This report may not be reproduced except in full, and with written approval from the laboratory. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.*

*This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.*

*Results relate only to the items tested and the sample(s) as received by the laboratory.*

# Table of Contents

Cover Page . . . . .	1
Table of Contents . . . . .	2
Sample Summary . . . . .	3
Case Narrative . . . . .	4
Definitions . . . . .	5
Client Sample Results . . . . .	6
QC Sample Results . . . . .	12
QC Association . . . . .	17
Chronicle . . . . .	19
Method Summary . . . . .	21
Certification Summary . . . . .	22
Chain of Custody . . . . .	23
Receipt Checklists . . . . .	25



## Sample Summary

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
490-4605-1	1167 Jasmine	Solid	08/14/12 10:45	08/21/12 08:15
490-4605-2	1236 Dove - a	Solid	08/14/12 15:15	08/21/12 08:15
490-4605-3	630 Dahlia - a	Solid	08/14/12 15:45	08/21/12 08:15
490-4605-4	771 Althea - a	Solid	08/14/12 16:15	08/21/12 08:15
490-4605-5	1305 Eagle	Solid	08/15/12 15:30	08/21/12 08:15
490-4605-6	1417 Albatross	Solid	08/16/12 15:45	08/21/12 08:15



## Case Narrative

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

**Job ID: 490-4605-1**

**Laboratory: TestAmerica Nashville**

### Narrative

### Job Narrative

490-4605-1

### Comments

No additional comments.

### Receipt

The samples were received on 8/21/2012 8:15 AM; the samples arrived in good condition, properly preserved and, where required, on ice. The temperature of the cooler at receipt was 3.9° C.

### GC/MS VOA

Method(s) 8260B: Insufficient sample volume was available to perform a matrix spike/matrix spike duplicate (MS/MSD) associated with batch 15022. See LCS/LCSD

Method(s) 8260B: Due to sample matrix effect on the internal standard (ISTD), a dilution was required for the following sample(s): 771 Althea - a (490-4605-4).

Method(s) 8260B: Surrogate recovery for the following sample(s) was outside control limits: 1167 Jasmine (490-4605-1). Evidence of matrix interference is present.

Method(s) 8260B: Insufficient sample volume was available to perform a matrix spike/matrix spike duplicate (MS/MSD) associated with batch 15621.

Method(s) 8260B: The method blank for batch 15621 contained Methylene Chloride, Bromodichloromethane, Toluene, and Xylenes above the method detection limit. This target analyte concentration was less than the reporting limit (RL); therefore, re-extraction and/or re-analysis of samples was not performed.

No other analytical or quality issues were noted.

### GC/MS Semi VOA

No analytical or quality issues were noted.

### Organic Prep

No analytical or quality issues were noted.

### VOA Prep

No analytical or quality issues were noted.

## Definitions/Glossary

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

### Qualifiers

#### GC/MS VOA

Qualifier	Qualifier Description
X	Surrogate is outside control limits
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
B	Compound was found in the blank and sample.

#### GC/MS Semi VOA

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

### Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
☆	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CNF	Contains no Free Liquid
DL, RA, RE, IN	Indicates a Dilution, Reanalysis, Re-extraction, or additional Initial metals/anion analysis of the sample
EDL	Estimated Detection Limit
EPA	United States Environmental Protection Agency
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
ND	Not detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RL	Reporting Limit
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)



# Client Sample Results

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

Client Sample ID: 1167 Jasmine

Lab Sample ID: 490-4605-1

Date Collected: 08/14/12 10:45

Matrix: Solid

Date Received: 08/21/12 08:15

Percent Solids: 81.6

## Method: 8260B - Volatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.101	0.0339	mg/Kg	✱	08/22/12 15:09	08/24/12 13:21	1
Ethylbenzene	0.873		0.101	0.0339	mg/Kg	✱	08/22/12 15:09	08/24/12 13:21	1
Naphthalene	0.677		0.306	0.104	mg/Kg	✱	08/22/12 15:18	08/27/12 15:56	1
Toluene	0.102		0.101	0.0375	mg/Kg	✱	08/22/12 15:09	08/24/12 13:21	1
Xylenes, Total	6.20		0.253	0.0339	mg/Kg	✱	08/22/12 15:09	08/24/12 13:21	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	117		70 - 130	08/22/12 15:09	08/24/12 13:21	1
1,2-Dichloroethane-d4 (Surr)	101		70 - 130	08/22/12 15:18	08/27/12 15:56	1
4-Bromofluorobenzene (Surr)	138	X	70 - 130	08/22/12 15:09	08/24/12 13:21	1
4-Bromofluorobenzene (Surr)	98		70 - 130	08/22/12 15:18	08/27/12 15:56	1
Dibromofluoromethane (Surr)	101		70 - 130	08/22/12 15:09	08/24/12 13:21	1
Dibromofluoromethane (Surr)	92		70 - 130	08/22/12 15:18	08/27/12 15:56	1
Toluene-d8 (Surr)	111		70 - 130	08/22/12 15:09	08/24/12 13:21	1
Toluene-d8 (Surr)	100		70 - 130	08/22/12 15:18	08/27/12 15:56	1

## Method: 8270D - Semivolatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.0658	0.00982	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Acenaphthylene	ND		0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Anthracene	0.169		0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Benzo[a]anthracene	0.0378	J	0.0658	0.0147	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Benzo[a]pyrene	ND		0.0658	0.0118	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Benzo[b]fluoranthene	0.0398	J	0.0658	0.0118	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Benzo[g,h,i]perylene	ND		0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Benzo[k]fluoranthene	ND		0.0658	0.0137	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Pyrene	0.155		0.0658	0.0118	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Phenanthrene	1.45		0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Chrysene	0.0454	J	0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Dibenz(a,h)anthracene	ND		0.0658	0.00687	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Fluoranthene	0.122		0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Fluorene	0.581		0.0658	0.0118	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Indeno[1,2,3-cd]pyrene	ND		0.0658	0.00982	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1
Naphthalene	0.738		0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/25/12 21:47	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
2-Fluorobiphenyl (Surr)	68		29 - 120	08/24/12 09:30	08/25/12 21:47	1
Terphenyl-d14 (Surr)	91		13 - 120	08/24/12 09:30	08/25/12 21:47	1
Nitrobenzene-d5 (Surr)	84		27 - 120	08/24/12 09:30	08/25/12 21:47	1

## General Chemistry

Analyte	Result	Qualifier	RL	RL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Solids	82		0.10	0.10	%			08/21/12 15:03	1

# Client Sample Results

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

Client Sample ID: 1236 Dove - a

Date Collected: 08/14/12 15:15

Date Received: 08/21/12 08:15

Lab Sample ID: 490-4605-2

Matrix: Solid

Percent Solids: 93.7

## Method: 8260B - Volatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.105	0.0352	mg/Kg	✱	08/22/12 15:09	08/24/12 13:50	1
Ethylbenzene	ND		0.105	0.0352	mg/Kg	✱	08/22/12 15:09	08/24/12 13:50	1
Naphthalene	ND		0.263	0.0894	mg/Kg	✱	08/22/12 15:09	08/24/12 13:50	1
Toluene	ND		0.105	0.0389	mg/Kg	✱	08/22/12 15:09	08/24/12 13:50	1
Xylenes, Total	ND		0.263	0.0352	mg/Kg	✱	08/22/12 15:09	08/24/12 13:50	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	106		70 - 130	08/22/12 15:09	08/24/12 13:50	1
4-Bromofluorobenzene (Surr)	103		70 - 130	08/22/12 15:09	08/24/12 13:50	1
Dibromofluoromethane (Surr)	94		70 - 130	08/22/12 15:09	08/24/12 13:50	1
Toluene-d8 (Surr)	104		70 - 130	08/22/12 15:09	08/24/12 13:50	1

## Method: 8270D - Semivolatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.0665	0.00992	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Acenaphthylene	ND		0.0665	0.00893	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Anthracene	ND		0.0665	0.00893	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Benzo[a]anthracene	ND		0.0665	0.0149	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Benzo[a]pyrene	ND		0.0665	0.0119	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Benzo[b]fluoranthene	ND		0.0665	0.0119	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Benzo[g,h,i]perylene	ND		0.0665	0.00893	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Benzo[k]fluoranthene	ND		0.0665	0.0139	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Pyrene	ND		0.0665	0.0119	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Phenanthrene	ND		0.0665	0.00893	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Chrysene	ND		0.0665	0.00893	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Dibenz(a,h)anthracene	ND		0.0665	0.00694	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Fluoranthene	ND		0.0665	0.00893	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Fluorene	ND		0.0665	0.0119	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Indeno[1,2,3-cd]pyrene	ND		0.0665	0.00992	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1
Naphthalene	ND		0.0665	0.00893	mg/Kg	✱	08/24/12 09:30	08/25/12 23:05	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
2-Fluorobiphenyl (Surr)	54		29 - 120	08/24/12 09:30	08/25/12 23:05	1
Terphenyl-d14 (Surr)	80		13 - 120	08/24/12 09:30	08/25/12 23:05	1
Nitrobenzene-d5 (Surr)	55		27 - 120	08/24/12 09:30	08/25/12 23:05	1

## General Chemistry

Analyte	Result	Qualifier	RL	RL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Solids	94		0.10	0.10	%			08/21/12 15:03	1



## Client Sample Results

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

**Client Sample ID: 630 Dahlia - a**

**Lab Sample ID: 490-4605-3**

**Date Collected: 08/14/12 15:45**

**Matrix: Solid**

**Date Received: 08/21/12 08:15**

**Percent Solids: 87.4**

### Method: 8260B - Volatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.110	0.0367	mg/Kg	✱	08/22/12 15:09	08/24/12 14:19	1
Ethylbenzene	ND		0.110	0.0367	mg/Kg	✱	08/22/12 15:09	08/24/12 14:19	1
Naphthalene	ND		0.274	0.0931	mg/Kg	✱	08/22/12 15:09	08/24/12 14:19	1
Toluene	ND		0.110	0.0405	mg/Kg	✱	08/22/12 15:09	08/24/12 14:19	1
Xylenes, Total	ND		0.274	0.0367	mg/Kg	✱	08/22/12 15:09	08/24/12 14:19	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	110		70 - 130	08/22/12 15:09	08/24/12 14:19	1
4-Bromofluorobenzene (Surr)	126		70 - 130	08/22/12 15:09	08/24/12 14:19	1
Dibromofluoromethane (Surr)	102		70 - 130	08/22/12 15:09	08/24/12 14:19	1
Toluene-d8 (Surr)	97		70 - 130	08/22/12 15:09	08/24/12 14:19	1

### Method: 8270D - Semivolatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.0667	0.00995	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Acenaphthylene	ND		0.0667	0.00896	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Anthracene	ND		0.0667	0.00896	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Benzo[a]anthracene	ND		0.0667	0.0149	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Benzo[a]pyrene	ND		0.0667	0.0119	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Benzo[b]fluoranthene	ND		0.0667	0.0119	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Benzo[g,h,i]perylene	ND		0.0667	0.00896	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Benzo[k]fluoranthene	ND		0.0667	0.0139	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Pyrene	ND		0.0667	0.0119	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Phenanthrene	ND		0.0667	0.00896	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Chrysene	ND		0.0667	0.00896	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Dibenz(a,h)anthracene	ND		0.0667	0.00697	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Fluoranthene	ND		0.0667	0.00896	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Fluorene	ND		0.0667	0.0119	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Indeno[1,2,3-cd]pyrene	ND		0.0667	0.00995	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1
Naphthalene	ND		0.0667	0.00896	mg/Kg	✱	08/24/12 09:30	08/25/12 23:31	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
2-Fluorobiphenyl (Surr)	62		29 - 120	08/24/12 09:30	08/25/12 23:31	1
Terphenyl-d14 (Surr)	86		13 - 120	08/24/12 09:30	08/25/12 23:31	1
Nitrobenzene-d5 (Surr)	62		27 - 120	08/24/12 09:30	08/25/12 23:31	1

### General Chemistry

Analyte	Result	Qualifier	RL	RL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Solids	87		0.10	0.10	%			08/21/12 15:03	1

# Client Sample Results

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

Client Sample ID: 771 Althea - a

Lab Sample ID: 490-4605-4

Date Collected: 08/14/12 16:15

Matrix: Solid

Date Received: 08/21/12 08:15

Percent Solids: 80.9

## Method: 8260B - Volatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	0.0602	J	0.105	0.0351	mg/Kg	✱	08/22/12 15:09	08/24/12 14:48	1
Ethylbenzene	0.235		0.127	0.0431	mg/Kg	✱	08/22/12 15:18	08/27/12 16:25	1
Naphthalene	8.43		0.317	0.108	mg/Kg	✱	08/22/12 15:18	08/27/12 16:25	1
Toluene	0.575		0.105	0.0388	mg/Kg	✱	08/22/12 15:09	08/24/12 14:48	1
Xylenes, Total	1.13	B	0.317	0.0431	mg/Kg	✱	08/22/12 15:18	08/27/12 16:25	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	114		70 - 130	08/22/12 15:09	08/24/12 14:48	1
1,2-Dichloroethane-d4 (Surr)	99		70 - 130	08/22/12 15:18	08/27/12 16:25	1
4-Bromofluorobenzene (Surr)	0	X	70 - 130	08/22/12 15:09	08/24/12 14:48	1
4-Bromofluorobenzene (Surr)	103		70 - 130	08/22/12 15:18	08/27/12 16:25	1
Dibromofluoromethane (Surr)	106		70 - 130	08/22/12 15:09	08/24/12 14:48	1
Dibromofluoromethane (Surr)	92		70 - 130	08/22/12 15:18	08/27/12 16:25	1
Toluene-d8 (Surr)	162	X	70 - 130	08/22/12 15:09	08/24/12 14:48	1
Toluene-d8 (Surr)	101		70 - 130	08/22/12 15:18	08/27/12 16:25	1

## Method: 8270D - Semivolatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	0.800		0.0657	0.00981	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Acenaphthylene	ND		0.0657	0.00883	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Anthracene	0.341		0.0657	0.00883	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Benzo[a]anthracene	0.221		0.0657	0.0147	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Benzo[a]pyrene	0.0981		0.0657	0.0118	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Benzo[b]fluoranthene	0.195		0.0657	0.0118	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Benzo[g,h,i]perylene	0.0552	J	0.0657	0.00883	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Benzo[k]fluoranthene	0.0744		0.0657	0.0137	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Pyrene	0.626		0.0657	0.0118	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Phenanthrene	4.22		0.131	0.0177	mg/Kg	✱	08/24/12 09:30	08/27/12 16:43	2
Chrysene	0.271		0.0657	0.00883	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Dibenz(a,h)anthracene	0.0432	J	0.0657	0.00687	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Fluoranthene	0.443		0.0657	0.00883	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Fluorene	1.34		0.0657	0.0118	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Indeno[1,2,3-cd]pyrene	0.0575	J	0.0657	0.00981	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1
Naphthalene	0.917		0.0657	0.00883	mg/Kg	✱	08/24/12 09:30	08/25/12 23:57	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
2-Fluorobiphenyl (Surr)	55		29 - 120	08/24/12 09:30	08/25/12 23:57	1
Terphenyl-d14 (Surr)	83		13 - 120	08/24/12 09:30	08/25/12 23:57	1
Nitrobenzene-d5 (Surr)	61		27 - 120	08/24/12 09:30	08/25/12 23:57	1

## General Chemistry

Analyte	Result	Qualifier	RL	RL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Solids	81		0.10	0.10	%			08/21/12 15:03	1



# Client Sample Results

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

Client Sample ID: 1305 Eagle

Lab Sample ID: 490-4605-5

Date Collected: 08/15/12 15:30

Matrix: Solid

Date Received: 08/21/12 08:15

Percent Solids: 97.6

## Method: 8260B - Volatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.108	0.0362	mg/Kg	✱	08/22/12 15:09	08/24/12 15:17	1
Ethylbenzene	ND		0.108	0.0362	mg/Kg	✱	08/22/12 15:09	08/24/12 15:17	1
Naphthalene	0.118	J	0.270	0.0920	mg/Kg	✱	08/22/12 15:09	08/24/12 15:17	1
Toluene	ND		0.108	0.0400	mg/Kg	✱	08/22/12 15:09	08/24/12 15:17	1
Xylenes, Total	ND		0.270	0.0362	mg/Kg	✱	08/22/12 15:09	08/24/12 15:17	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	106		70 - 130	08/22/12 15:09	08/24/12 15:17	1
4-Bromofluorobenzene (Surr)	98		70 - 130	08/22/12 15:09	08/24/12 15:17	1
Dibromofluoromethane (Surr)	95		70 - 130	08/22/12 15:09	08/24/12 15:17	1
Toluene-d8 (Surr)	117		70 - 130	08/22/12 15:09	08/24/12 15:17	1

## Method: 8270D - Semivolatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.0665	0.00993	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Acenaphthylene	ND		0.0665	0.00894	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Anthracene	ND		0.0665	0.00894	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Benzo[a]anthracene	ND		0.0665	0.0149	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Benzo[a]pyrene	ND		0.0665	0.0119	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Benzo[b]fluoranthene	ND		0.0665	0.0119	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Benzo[g,h,i]perylene	ND		0.0665	0.00894	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Benzo[k]fluoranthene	ND		0.0665	0.0139	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Pyrene	ND		0.0665	0.0119	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Phenanthrene	ND		0.0665	0.00894	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Chrysene	ND		0.0665	0.00894	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Dibenz(a,h)anthracene	ND		0.0665	0.00695	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Fluoranthene	ND		0.0665	0.00894	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Fluorene	ND		0.0665	0.0119	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Indeno[1,2,3-cd]pyrene	ND		0.0665	0.00993	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1
Naphthalene	ND		0.0665	0.00894	mg/Kg	✱	08/24/12 09:30	08/26/12 00:22	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
2-Fluorobiphenyl (Surr)	59		29 - 120	08/24/12 09:30	08/26/12 00:22	1
Terphenyl-d14 (Surr)	79		13 - 120	08/24/12 09:30	08/26/12 00:22	1
Nitrobenzene-d5 (Surr)	58		27 - 120	08/24/12 09:30	08/26/12 00:22	1

## General Chemistry

Analyte	Result	Qualifier	RL	RL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Solids	98		0.10	0.10	%			08/21/12 15:03	1

# Client Sample Results

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

Client Sample ID: 1417 Albatross

Lab Sample ID: 490-4605-6

Date Collected: 08/16/12 15:45

Matrix: Solid

Date Received: 08/21/12 08:15

Percent Solids: 81.2

## Method: 8260B - Volatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.102	0.0343	mg/Kg	✱	08/22/12 15:09	08/24/12 15:47	1
Ethylbenzene	ND		0.102	0.0343	mg/Kg	✱	08/22/12 15:09	08/24/12 15:47	1
Naphthalene	ND		0.256	0.0870	mg/Kg	✱	08/22/12 15:09	08/24/12 15:47	1
Toluene	ND		0.102	0.0379	mg/Kg	✱	08/22/12 15:09	08/24/12 15:47	1
Xylenes, Total	ND		0.256	0.0343	mg/Kg	✱	08/22/12 15:09	08/24/12 15:47	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	107		70 - 130	08/22/12 15:09	08/24/12 15:47	1
4-Bromofluorobenzene (Surr)	125		70 - 130	08/22/12 15:09	08/24/12 15:47	1
Dibromofluoromethane (Surr)	89		70 - 130	08/22/12 15:09	08/24/12 15:47	1
Toluene-d8 (Surr)	106		70 - 130	08/22/12 15:09	08/24/12 15:47	1

## Method: 8270D - Semivolatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.0658	0.00982	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Acenaphthylene	ND		0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Anthracene	ND		0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Benzo[a]anthracene	ND		0.0658	0.0147	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Benzo[a]pyrene	ND		0.0658	0.0118	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Benzo[b]fluoranthene	ND		0.0658	0.0118	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Benzo[g,h,i]perylene	ND		0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Benzo[k]fluoranthene	ND		0.0658	0.0137	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Pyrene	ND		0.0658	0.0118	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Phenanthrene	ND		0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Chrysene	ND		0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Dibenz(a,h)anthracene	ND		0.0658	0.00687	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Fluoranthene	ND		0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Fluorene	ND		0.0658	0.0118	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Indeno[1,2,3-cd]pyrene	ND		0.0658	0.00982	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1
Naphthalene	ND		0.0658	0.00884	mg/Kg	✱	08/24/12 09:30	08/26/12 00:48	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
2-Fluorobiphenyl (Surr)	65		29 - 120	08/24/12 09:30	08/26/12 00:48	1
Terphenyl-d14 (Surr)	85		13 - 120	08/24/12 09:30	08/26/12 00:48	1
Nitrobenzene-d5 (Surr)	61		27 - 120	08/24/12 09:30	08/26/12 00:48	1

## General Chemistry

Analyte	Result	Qualifier	RL	RL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Solids	81		0.10	0.10	%			08/21/12 15:03	1



# QC Sample Results

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

## Method: 8260B - Volatile Organic Compounds (GC/MS)

Lab Sample ID: MB 490-15022/6

Matrix: Solid

Analysis Batch: 15022

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB MB		RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
	Result	Qualifier							
Benzene	ND		0.00200	0.000670	mg/Kg			08/24/12 11:53	1
Ethylbenzene	ND		0.00200	0.000670	mg/Kg			08/24/12 11:53	1
Naphthalene	ND		0.00500	0.00170	mg/Kg			08/24/12 11:53	1
Toluene	ND		0.00200	0.000740	mg/Kg			08/24/12 11:53	1
Xylenes, Total	ND		0.00500	0.000670	mg/Kg			08/24/12 11:53	1

Surrogate	MB MB		Limits	Prepared	Analyzed	Dil Fac
	%Recovery	Qualifier				
1,2-Dichloroethane-d4 (Surr)	106		70 - 130		08/24/12 11:53	1
4-Bromofluorobenzene (Surr)	100		70 - 130		08/24/12 11:53	1
Dibromofluoromethane (Surr)	98		70 - 130		08/24/12 11:53	1
Toluene-d8 (Surr)	102		70 - 130		08/24/12 11:53	1

Lab Sample ID: MB 490-15022/7

Matrix: Solid

Analysis Batch: 15022

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB MB		RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
	Result	Qualifier							
Benzene	ND		0.100	0.0335	mg/Kg			08/24/12 12:22	1
Ethylbenzene	ND		0.100	0.0335	mg/Kg			08/24/12 12:22	1
Naphthalene	ND		0.250	0.0850	mg/Kg			08/24/12 12:22	1
Toluene	ND		0.100	0.0370	mg/Kg			08/24/12 12:22	1
Xylenes, Total	ND		0.250	0.0335	mg/Kg			08/24/12 12:22	1

Surrogate	MB MB		Limits	Prepared	Analyzed	Dil Fac
	%Recovery	Qualifier				
1,2-Dichloroethane-d4 (Surr)	108		70 - 130		08/24/12 12:22	1
4-Bromofluorobenzene (Surr)	104		70 - 130		08/24/12 12:22	1
Dibromofluoromethane (Surr)	101		70 - 130		08/24/12 12:22	1
Toluene-d8 (Surr)	99		70 - 130		08/24/12 12:22	1

Lab Sample ID: LCS 490-15022/3

Matrix: Solid

Analysis Batch: 15022

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS LCS		Unit	D	%Rec	%Rec. Limits
		Result	Qualifier				
Benzene	0.0500	0.04735		mg/Kg		95	75 - 127
Ethylbenzene	0.0500	0.05154		mg/Kg		103	80 - 134
Naphthalene	0.0500	0.05063		mg/Kg		101	69 - 150
Toluene	0.0500	0.05479		mg/Kg		110	80 - 132
Xylenes, Total	0.150	0.1512		mg/Kg		101	80 - 137

Surrogate	LCS LCS		Limits
	%Recovery	Qualifier	
1,2-Dichloroethane-d4 (Surr)	101		70 - 130
4-Bromofluorobenzene (Surr)	97		70 - 130
Dibromofluoromethane (Surr)	96		70 - 130
Toluene-d8 (Surr)	108		70 - 130

# QC Sample Results

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

## Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

Lab Sample ID: LCSD 490-15022/4

Matrix: Solid

Analysis Batch: 15022

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Benzene	0.0500	0.04753		mg/Kg		95	75 - 127	0	50
Ethylbenzene	0.0500	0.04869		mg/Kg		97	80 - 134	6	50
Naphthalene	0.0500	0.05278		mg/Kg		106	69 - 150	4	50
Toluene	0.0500	0.04803		mg/Kg		96	80 - 132	13	50
Xylenes, Total	0.150	0.1444		mg/Kg		96	80 - 137	5	50

Surrogate	LCSD %Recovery	LCSD Qualifier	Limits
1,2-Dichloroethane-d4 (Surr)	108		70 - 130
4-Bromofluorobenzene (Surr)	125		70 - 130
Dibromofluoromethane (Surr)	98		70 - 130
Toluene-d8 (Surr)	99		70 - 130

Lab Sample ID: MB 490-15621/6

Matrix: Solid

Analysis Batch: 15621

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.00200	0.000680	mg/Kg			08/27/12 12:30	1
Ethylbenzene	ND		0.00200	0.000680	mg/Kg			08/27/12 12:30	1
Naphthalene	ND		0.00500	0.00170	mg/Kg			08/27/12 12:30	1
Toluene	0.001202	J	0.00200	0.000740	mg/Kg			08/27/12 12:30	1
Xylenes, Total	0.001207	J	0.00500	0.000680	mg/Kg			08/27/12 12:30	1

Surrogate	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	99		70 - 130		08/27/12 12:30	1
4-Bromofluorobenzene (Surr)	104		70 - 130		08/27/12 12:30	1
Dibromofluoromethane (Surr)	94		70 - 130		08/27/12 12:30	1
Toluene-d8 (Surr)	99		70 - 130		08/27/12 12:30	1

Lab Sample ID: MB 490-15621/7

Matrix: Solid

Analysis Batch: 15621

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.100	0.0340	mg/Kg			08/27/12 12:59	1
Ethylbenzene	ND		0.100	0.0340	mg/Kg			08/27/12 12:59	1
Naphthalene	ND		0.250	0.0850	mg/Kg			08/27/12 12:59	1
Toluene	0.05284	J	0.100	0.0370	mg/Kg			08/27/12 12:59	1
Xylenes, Total	0.05238	J	0.250	0.0340	mg/Kg			08/27/12 12:59	1

Surrogate	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	101		70 - 130		08/27/12 12:59	1
4-Bromofluorobenzene (Surr)	105		70 - 130		08/27/12 12:59	1
Dibromofluoromethane (Surr)	94		70 - 130		08/27/12 12:59	1
Toluene-d8 (Surr)	101		70 - 130		08/27/12 12:59	1



## QC Sample Results

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

### Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

Lab Sample ID: LCS 490-15621/3

Matrix: Solid

Analysis Batch: 15621

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS		Unit	D	%Rec	%Rec.	
		Result	Qualifier				Limits	
Benzene	0.0500	0.04607		mg/Kg		92	75 - 127	
Ethylbenzene	0.0500	0.04670		mg/Kg		93	80 - 134	
Naphthalene	0.0500	0.05064		mg/Kg		101	69 - 150	
Toluene	0.0500	0.05422		mg/Kg		108	80 - 132	
Xylenes, Total	0.150	0.1466		mg/Kg		98	80 - 137	

Surrogate	LCS		Limits
	%Recovery	Qualifier	
1,2-Dichloroethane-d4 (Surr)	107		70 - 130
4-Bromofluorobenzene (Surr)	100		70 - 130
Dibromofluoromethane (Surr)	100		70 - 130
Toluene-d8 (Surr)	115		70 - 130

Lab Sample ID: LCSD 490-15621/4

Matrix: Solid

Analysis Batch: 15621

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Analyte	Spike Added	LCSD		Unit	D	%Rec	%Rec.		RPD
		Result	Qualifier				Limits		
Benzene	0.0500	0.04323		mg/Kg		86	75 - 127	6	50
Ethylbenzene	0.0500	0.04667		mg/Kg		93	80 - 134	0	50
Naphthalene	0.0500	0.05099		mg/Kg		102	69 - 150	1	50
Toluene	0.0500	0.04755		mg/Kg		95	80 - 132	13	50
Xylenes, Total	0.150	0.1451		mg/Kg		97	80 - 137	1	50

Surrogate	LCSD		Limits
	%Recovery	Qualifier	
1,2-Dichloroethane-d4 (Surr)	103		70 - 130
4-Bromofluorobenzene (Surr)	100		70 - 130
Dibromofluoromethane (Surr)	98		70 - 130
Toluene-d8 (Surr)	106		70 - 130

### Method: 8270D - Semivolatile Organic Compounds (GC/MS)

Lab Sample ID: MB 490-15031/1-A

Matrix: Solid

Analysis Batch: 15380

Client Sample ID: Method Blank

Prep Type: Total/NA

Prep Batch: 15031

Analyte	MB		RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
	Result	Qualifier							
Acenaphthene	ND		0.0670	0.0100	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Acenaphthylene	ND		0.0670	0.00900	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Anthracene	ND		0.0670	0.00900	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Benzo[a]anthracene	ND		0.0670	0.0150	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Benzo[a]pyrene	ND		0.0670	0.0120	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Benzo[b]fluoranthene	ND		0.0670	0.0120	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Benzo[g,h,i]perylene	ND		0.0670	0.00900	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Benzo[k]fluoranthene	ND		0.0670	0.0140	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Pyrene	ND		0.0670	0.0120	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Phenanthrene	ND		0.0670	0.00900	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Chrysene	ND		0.0670	0.00900	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Dibenz(a,h)anthracene	ND		0.0670	0.00700	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Fluoranthene	ND		0.0670	0.00900	mg/Kg		08/24/12 09:30	08/25/12 20:55	1

## QC Sample Results

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

### Method: 8270D - Semivolatile Organic Compounds (GC/MS) (Continued)

Lab Sample ID: MB 490-15031/1-A

Matrix: Solid

Analysis Batch: 15380

Client Sample ID: Method Blank

Prep Type: Total/NA

Prep Batch: 15031

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Fluorene	ND		0.0670	0.0120	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Indeno[1,2,3-cd]pyrene	ND		0.0670	0.0100	mg/Kg		08/24/12 09:30	08/25/12 20:55	1
Naphthalene	ND		0.0670	0.00900	mg/Kg		08/24/12 09:30	08/25/12 20:55	1

Surrogate	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
2-Fluorobiphenyl (Surr)	78		29 - 120	08/24/12 09:30	08/25/12 20:55	1
Terphenyl-d14 (Surr)	102		13 - 120	08/24/12 09:30	08/25/12 20:55	1
Nitrobenzene-d5 (Surr)	70		27 - 120	08/24/12 09:30	08/25/12 20:55	1

Lab Sample ID: LCS 490-15031/2-A

Matrix: Solid

Analysis Batch: 15380

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Prep Batch: 15031

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Acenaphthylene	1.67	1.504		mg/Kg		90	38 - 120
Anthracene	1.67	1.458		mg/Kg		87	46 - 124
Benzo[a]anthracene	1.67	1.500		mg/Kg		90	45 - 120
Benzo[a]pyrene	1.67	1.613		mg/Kg		97	45 - 120
Benzo[b]fluoranthene	1.67	1.500		mg/Kg		90	42 - 120
Benzo[g,h,i]perylene	1.67	1.415		mg/Kg		85	38 - 120
Benzo[k]fluoranthene	1.67	1.407		mg/Kg		84	42 - 120
Pyrene	1.67	1.576		mg/Kg		95	43 - 120
Phenanthrene	1.67	1.457		mg/Kg		87	45 - 120
Chrysene	1.67	1.461		mg/Kg		88	43 - 120
Dibenz(a,h)anthracene	1.67	1.466		mg/Kg		88	32 - 128
Fluoranthene	1.67	1.438		mg/Kg		86	46 - 120
Fluorene	1.67	1.511		mg/Kg		91	42 - 120
Indeno[1,2,3-cd]pyrene	1.67	1.461		mg/Kg		88	41 - 121
Naphthalene	1.67	1.298		mg/Kg		78	32 - 120

Surrogate	LCS %Recovery	LCS Qualifier	Limits
2-Fluorobiphenyl (Surr)	66		29 - 120
Terphenyl-d14 (Surr)	82		13 - 120
Nitrobenzene-d5 (Surr)	60		27 - 120

Lab Sample ID: 490-4605-1 MS

Matrix: Solid

Analysis Batch: 15380

Client Sample ID: 1167 Jasmine

Prep Type: Total/NA

Prep Batch: 15031

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Acenaphthylene	ND		1.67	1.312		mg/Kg	☼	79	25 - 120
Anthracene	0.169		1.67	1.701		mg/Kg	☼	92	28 - 125
Benzo[a]anthracene	0.0378	J	1.67	1.466		mg/Kg	☼	86	23 - 120
Benzo[a]pyrene	ND		1.67	1.568		mg/Kg	☼	94	15 - 128
Benzo[b]fluoranthene	0.0398	J	1.67	1.538		mg/Kg	☼	90	12 - 133
Benzo[g,h,i]perylene	ND		1.67	1.507		mg/Kg	☼	90	22 - 120
Benzo[k]fluoranthene	ND		1.67	1.434		mg/Kg	☼	86	28 - 120
Pyrene	0.155		1.67	1.490		mg/Kg	☼	80	20 - 123
Phenanthrene	1.45		1.67	2.904		mg/Kg	☼	87	21 - 122



## QC Sample Results

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

### Method: 8270D - Semivolatile Organic Compounds (GC/MS) (Continued)

Lab Sample ID: 490-4605-1 MS

Matrix: Solid

Analysis Batch: 15380

Client Sample ID: 1167 Jasmine

Prep Type: Total/NA

Prep Batch: 15031

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Chrysene	0.0454	J	1.67	1.591		mg/Kg	☼	93	20 - 120
Dibenz(a,h)anthracene	ND		1.67	1.539		mg/Kg	☼	92	12 - 128
Fluoranthene	0.122		1.67	1.570		mg/Kg	☼	87	10 - 143
Fluorene	0.581		1.67	1.931		mg/Kg	☼	81	20 - 120
Indeno[1,2,3-cd]pyrene	ND		1.67	1.505		mg/Kg	☼	90	22 - 121
Naphthalene	0.738		1.67	1.636		mg/Kg	☼	54	10 - 120

Surrogate	MS %Recovery	MS Qualifier	Limits
2-Fluorobiphenyl (Surr)	60		29 - 120
Terphenyl-d14 (Surr)	77		13 - 120
Nitrobenzene-d5 (Surr)	68		27 - 120

Lab Sample ID: 490-4605-1 MSD

Matrix: Solid

Analysis Batch: 15380

Client Sample ID: 1167 Jasmine

Prep Type: Total/NA

Prep Batch: 15031

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Acenaphthylene	ND		1.66	1.609		mg/Kg	☼	97	25 - 120	20	50
Anthracene	0.169		1.66	1.869		mg/Kg	☼	102	28 - 125	9	49
Benzo[a]anthracene	0.0378	J	1.66	1.593		mg/Kg	☼	94	23 - 120	8	50
Benzo[a]pyrene	ND		1.66	1.890		mg/Kg	☼	114	15 - 128	19	50
Benzo[b]fluoranthene	0.0398	J	1.66	1.608		mg/Kg	☼	94	12 - 133	4	50
Benzo[g,h,i]perylene	ND		1.66	1.572		mg/Kg	☼	95	22 - 120	4	50
Benzo[k]fluoranthene	ND		1.66	1.580		mg/Kg	☼	95	28 - 120	10	45
Pyrene	0.155		1.66	1.715		mg/Kg	☼	94	20 - 123	14	50
Phenanthrene	1.45		1.66	3.068		mg/Kg	☼	98	21 - 122	6	50
Chrysene	0.0454	J	1.66	1.596		mg/Kg	☼	93	20 - 120	0	49
Dibenz(a,h)anthracene	ND		1.66	1.660		mg/Kg	☼	100	12 - 128	8	50
Fluoranthene	0.122		1.66	1.690		mg/Kg	☼	94	10 - 143	7	50
Fluorene	0.581		1.66	2.096		mg/Kg	☼	91	20 - 120	8	50
Indeno[1,2,3-cd]pyrene	ND		1.66	1.596		mg/Kg	☼	96	22 - 121	6	50
Naphthalene	0.738		1.66	1.789		mg/Kg	☼	63	10 - 120	9	50

Surrogate	MSD %Recovery	MSD Qualifier	Limits
2-Fluorobiphenyl (Surr)	64		29 - 120
Terphenyl-d14 (Surr)	78		13 - 120
Nitrobenzene-d5 (Surr)	63		27 - 120

### Method: Moisture - Percent Moisture

Lab Sample ID: 490-4605-1 DU

Matrix: Solid

Analysis Batch: 14093

Client Sample ID: 1167 Jasmine

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Percent Solids	82		82		%		0.08	20

## QC Association Summary

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

### GC/MS VOA

#### Prep Batch: 14487

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-4605-1	1167 Jasmine	Total/NA	Solid	5035	
490-4605-2	1236 Dove - a	Total/NA	Solid	5035	
490-4605-3	630 Dahlia - a	Total/NA	Solid	5035	
490-4605-4	771 Althea - a	Total/NA	Solid	5035	
490-4605-5	1305 Eagle	Total/NA	Solid	5035	
490-4605-6	1417 Albatross	Total/NA	Solid	5035	

#### Prep Batch: 14489

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-4605-1	1167 Jasmine	Total/NA	Solid	5035	
490-4605-4	771 Althea - a	Total/NA	Solid	5035	

#### Analysis Batch: 15022

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-4605-1	1167 Jasmine	Total/NA	Solid	8260B	14487
490-4605-2	1236 Dove - a	Total/NA	Solid	8260B	14487
490-4605-3	630 Dahlia - a	Total/NA	Solid	8260B	14487
490-4605-4	771 Althea - a	Total/NA	Solid	8260B	14487
490-4605-5	1305 Eagle	Total/NA	Solid	8260B	14487
490-4605-6	1417 Albatross	Total/NA	Solid	8260B	14487
LCS 490-15022/3	Lab Control Sample	Total/NA	Solid	8260B	
LCSD 490-15022/4	Lab Control Sample Dup	Total/NA	Solid	8260B	
MB 490-15022/6	Method Blank	Total/NA	Solid	8260B	
MB 490-15022/7	Method Blank	Total/NA	Solid	8260B	

#### Analysis Batch: 15621

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-4605-1	1167 Jasmine	Total/NA	Solid	8260B	14489
490-4605-4	771 Althea - a	Total/NA	Solid	8260B	14489
LCS 490-15621/3	Lab Control Sample	Total/NA	Solid	8260B	
LCSD 490-15621/4	Lab Control Sample Dup	Total/NA	Solid	8260B	
MB 490-15621/6	Method Blank	Total/NA	Solid	8260B	
MB 490-15621/7	Method Blank	Total/NA	Solid	8260B	

### GC/MS Semi VOA

#### Prep Batch: 15031

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-4605-1	1167 Jasmine	Total/NA	Solid	3550C	
490-4605-1 MS	1167 Jasmine	Total/NA	Solid	3550C	
490-4605-1 MSD	1167 Jasmine	Total/NA	Solid	3550C	
490-4605-2	1236 Dove - a	Total/NA	Solid	3550C	
490-4605-3	630 Dahlia - a	Total/NA	Solid	3550C	
490-4605-4	771 Althea - a	Total/NA	Solid	3550C	
490-4605-5	1305 Eagle	Total/NA	Solid	3550C	
490-4605-6	1417 Albatross	Total/NA	Solid	3550C	
LCS 490-15031/2-A	Lab Control Sample	Total/NA	Solid	3550C	
MB 490-15031/1-A	Method Blank	Total/NA	Solid	3550C	

#### Analysis Batch: 15380

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-4605-1	1167 Jasmine	Total/NA	Solid	8270D	15031



## QC Association Summary

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

### GC/MS Semi VOA (Continued)

#### Analysis Batch: 15380 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-4605-1 MS	1167 Jasmine	Total/NA	Solid	8270D	15031
490-4605-1 MSD	1167 Jasmine	Total/NA	Solid	8270D	15031
490-4605-2	1236 Dove - a	Total/NA	Solid	8270D	15031
490-4605-3	630 Dahlia - a	Total/NA	Solid	8270D	15031
490-4605-4	771 Althea - a	Total/NA	Solid	8270D	15031
490-4605-5	1305 Eagle	Total/NA	Solid	8270D	15031
490-4605-6	1417 Albatross	Total/NA	Solid	8270D	15031
LCS 490-15031/2-A	Lab Control Sample	Total/NA	Solid	8270D	15031
MB 490-15031/1-A	Method Blank	Total/NA	Solid	8270D	15031

#### Analysis Batch: 15732

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-4605-4	771 Althea - a	Total/NA	Solid	8270D	15031

### General Chemistry

#### Analysis Batch: 14093

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-4605-1	1167 Jasmine	Total/NA	Solid	Moisture	
490-4605-1 DU	1167 Jasmine	Total/NA	Solid	Moisture	
490-4605-2	1236 Dove - a	Total/NA	Solid	Moisture	
490-4605-3	630 Dahlia - a	Total/NA	Solid	Moisture	
490-4605-4	771 Althea - a	Total/NA	Solid	Moisture	
490-4605-5	1305 Eagle	Total/NA	Solid	Moisture	
490-4605-6	1417 Albatross	Total/NA	Solid	Moisture	

# Lab Chronicle

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

**Client Sample ID: 1167 Jasmine**

**Date Collected: 08/14/12 10:45**

**Date Received: 08/21/12 08:15**

**Lab Sample ID: 490-4605-1**

**Matrix: Solid**

**Percent Solids: 81.6**

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	5035			14487	08/22/12 15:09	KK	TAL NSH
Total/NA	Analysis	8260B		1	15022	08/24/12 13:21	KK	TAL NSH
Total/NA	Prep	5035			14489	08/22/12 15:18	KK	TAL NSH
Total/NA	Analysis	8260B		1	15621	08/27/12 15:56	KK	TAL NSH
Total/NA	Prep	3550C			15031	08/24/12 09:30	AK	TAL NSH
Total/NA	Analysis	8270D		1	15380	08/25/12 21:47	JS	TAL NSH
Total/NA	Analysis	Moisture		1	14093	08/21/12 15:03	ML	TAL NSH

**Client Sample ID: 1236 Dove - a**

**Date Collected: 08/14/12 15:15**

**Date Received: 08/21/12 08:15**

**Lab Sample ID: 490-4605-2**

**Matrix: Solid**

**Percent Solids: 93.7**

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	5035			14487	08/22/12 15:09	KK	TAL NSH
Total/NA	Analysis	8260B		1	15022	08/24/12 13:50	KK	TAL NSH
Total/NA	Prep	3550C			15031	08/24/12 09:30	AK	TAL NSH
Total/NA	Analysis	8270D		1	15380	08/25/12 23:05	JS	TAL NSH
Total/NA	Analysis	Moisture		1	14093	08/21/12 15:03	ML	TAL NSH

**Client Sample ID: 630 Dahlia - a**

**Date Collected: 08/14/12 15:45**

**Date Received: 08/21/12 08:15**

**Lab Sample ID: 490-4605-3**

**Matrix: Solid**

**Percent Solids: 87.4**

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	5035			14487	08/22/12 15:09	KK	TAL NSH
Total/NA	Analysis	8260B		1	15022	08/24/12 14:19	KK	TAL NSH
Total/NA	Prep	3550C			15031	08/24/12 09:30	AK	TAL NSH
Total/NA	Analysis	8270D		1	15380	08/25/12 23:31	JS	TAL NSH
Total/NA	Analysis	Moisture		1	14093	08/21/12 15:03	ML	TAL NSH

**Client Sample ID: 771 Althea - a**

**Date Collected: 08/14/12 16:15**

**Date Received: 08/21/12 08:15**

**Lab Sample ID: 490-4605-4**

**Matrix: Solid**

**Percent Solids: 80.9**

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	5035			14487	08/22/12 15:09	KK	TAL NSH
Total/NA	Analysis	8260B		1	15022	08/24/12 14:48	KK	TAL NSH
Total/NA	Prep	5035			14489	08/22/12 15:18	KK	TAL NSH
Total/NA	Analysis	8260B		1	15621	08/27/12 16:25	KK	TAL NSH
Total/NA	Prep	3550C			15031	08/24/12 09:30	AK	TAL NSH
Total/NA	Analysis	8270D		1	15380	08/25/12 23:57	JS	TAL NSH
Total/NA	Analysis	8270D		2	15732	08/27/12 16:43	BS	TAL NSH
Total/NA	Analysis	Moisture		1	14093	08/21/12 15:03	ML	TAL NSH



## Lab Chronicle

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

### Client Sample ID: 1305 Eagle

Date Collected: 08/15/12 15:30

Date Received: 08/21/12 08:15

### Lab Sample ID: 490-4605-5

Matrix: Solid

Percent Solids: 97.6

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	5035			14487	08/22/12 15:09	KK	TAL NSH
Total/NA	Analysis	8260B		1	15022	08/24/12 15:17	KK	TAL NSH
Total/NA	Prep	3550C			15031	08/24/12 09:30	AK	TAL NSH
Total/NA	Analysis	8270D		1	15380	08/26/12 00:22	JS	TAL NSH
Total/NA	Analysis	Moisture		1	14093	08/21/12 15:03	ML	TAL NSH

### Client Sample ID: 1417 Albatross

Date Collected: 08/16/12 15:45

Date Received: 08/21/12 08:15

### Lab Sample ID: 490-4605-6

Matrix: Solid

Percent Solids: 81.2

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	5035			14487	08/22/12 15:09	KK	TAL NSH
Total/NA	Analysis	8260B		1	15022	08/24/12 15:47	KK	TAL NSH
Total/NA	Prep	3550C			15031	08/24/12 09:30	AK	TAL NSH
Total/NA	Analysis	8270D		1	15380	08/26/12 00:48	JS	TAL NSH
Total/NA	Analysis	Moisture		1	14093	08/21/12 15:03	ML	TAL NSH

#### Laboratory References:

TAL NSH = TestAmerica Nashville, 2960 Foster Creighton Drive, Nashville, TN 37204, TEL (615)726-0177

## Method Summary

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

Method	Method Description	Protocol	Laboratory
8260B	Volatile Organic Compounds (GC/MS)	SW846	TAL NSH
8270D	Semivolatile Organic Compounds (GC/MS)	SW846	TAL NSH
Moisture	Percent Moisture	EPA	TAL NSH

### Protocol References:

EPA = US Environmental Protection Agency

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

### Laboratory References:

TAL NSH = TestAmerica Nashville, 2960 Foster Creighton Drive, Nashville, TN 37204, TEL (615)726-0177

## Certification Summary

Client: Environmental Enterprise Group  
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-4605-1

### Laboratory: TestAmerica Nashville

All certifications held by this laboratory are listed. Not all certifications are applicable to this report.

Authority	Program	EPA Region	Certification ID	Expiration Date
	ACIL		393	10-30-12
A2LA	ISO/IEC 17025		0453.07	12-31-13
Alabama	State Program	4	41150	05-31-13
Alaska (UST)	State Program	10	UST-087	07-24-13
Arizona	State Program	9	AZ0473	05-05-13
Arkansas DEQ	State Program	6	88-0737	04-25-13
California	NELAC	9	1168CA	10-31-12
Canadian Assoc Lab Accred (CALA)	Canada		3744	03-08-14
Colorado	State Program	8	N/A	02-28-13
Connecticut	State Program	1	PH-0220	12-31-13
Florida	NELAC	4	E87358	06-30-13
Illinois	NELAC	5	200010	12-09-12
Iowa	State Program	7	131	05-01-14
Kansas	NELAC	7	E-10229	10-31-12
Kentucky	State Program	4	90038	12-31-12
Kentucky (UST)	State Program	4	19	09-15-13
Louisiana	NELAC	6	LA110014	12-31-12
Louisiana	NELAC	6	30613	06-30-13
Maryland	State Program	3	316	03-31-13
Massachusetts	State Program	1	M-TN032	06-30-13
Minnesota	NELAC	5	047-999-345	12-31-12
Mississippi	State Program	4	N/A	06-30-13
Montana (UST)	State Program	8	NA	01-01-15
Nevada	State Program	9	TN00032	09-30-12
New Hampshire	NELAC	1	2963	10-09-12
New Jersey	NELAC	2	TN965	06-30-13
New York	NELAC	2	11342	04-01-13
North Carolina DENR	State Program	4	387	12-31-12
North Dakota	State Program	8	R-146	06-30-13
Ohio VAP	State Program	5	CL0033	01-19-14
Oklahoma	State Program	6	9412	08-31-12
Oregon	NELAC	10	TN200001	04-30-13
Pennsylvania	NELAC	3	68-00585	06-30-13
Rhode Island	State Program	1	LAO00268	12-30-12
South Carolina	State Program	4	84009 (001)	02-28-13
South Carolina	State Program	4	84009 (002)	02-23-14
Tennessee	State Program	4	2008	02-23-14
Texas	NELAC	6	T104704077-09-TX	08-31-13
USDA	Federal		S-48469	11-02-13
Utah	NELAC	8	TAN	06-30-13
Virginia	NELAC	3	460152	06-14-13
Washington	State Program	10	C789	07-19-13
West Virginia DEP	State Program	3	219	02-28-13
Wisconsin	State Program	5	998020430	08-31-13
Wyoming (UST)	A2LA	8	453.07	12-31-13



THE LEADER IN ENVIRONMENTAL TESTING

Phone: 615-726-0177  
Toll Free: 800-765-0980  
Fax: 615-726-3404

To assist us in using the proper analytical methods, is this work being conducted for regulatory purposes?

**Sampler Signature:**

Enforcement Action?	Yes	No
---------------------	-----	----

Project #:

[illegible]

## Login Sample Receipt Checklist

Client: Environmental Enterprise Group

Job Number: 490-4605-1

Login Number: 4605

List Source: TestAmerica Nashville

List Number: 1

Creator: Ford, Easton

Question	Answer	Comment
Radioactivity either was not measured or, if measured, is at or below background	N/A	
The cooler's custody seal, if present, is intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the sample IDs on the containers and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	N/A	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
VOA sample vials do not have headspace or bubble is <6mm (1/4") in diameter.	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	



ATTACHMENT A



# NON-HAZARDOUS MANIFEST

<b>NON-HAZARDOUS MANIFEST</b>		1. Generator's US EPA ID No.		Manifest Doc No.		2. Page 1 of 1	
3. Generator's Mailing Address: MCAS, BEAUFORT LAUREL BAY HOUSING BEAUFORT, SC 29907 4. Generator's Phone 843-228-6461		Generator's Site Address (if different than mailing):		A. Manifest Number <b>WMNA</b> 00316830		B. State Generator's ID	
5. Transporter 1 Company Name EEG, INC.		6. US EPA ID Number		C. State Transporter's ID		D. Transporter's Phone 843-879-0411	
7. Transporter 2 Company Name		8. US EPA ID Number		E. State Transporter's ID		F. Transporter's Phone	
9. Designated Facility Name and Site Address HICKORY HILL LANDFILL 2621 LOW COUNTRY ROAD RIDGELAND, SC 29936		10. US EPA ID Number		G. State Facility ID		H. State Facility Phone 843-987-4643	
GENERATOR	11. Description of Waste Materials		12. Containers		13. Total Quantity	14. Unit Wt./Vol.	I. Misc. Comments
	a. HEATING OIL TANKS FILLED WITH SAND WM Profile # 102655SC		No.	Type			
	b. WM Profile #						
	c. WM Profile #						
	d. WM Profile #						
	J. Additional Descriptions for Materials Listed Above		K. Disposal Location				
			Cell		Level		
			Grid				
	15. Special Handling Instructions and Additional Information LIST FROM: 2) 1417 ALBATROSS- 4) 921 BARRACUDA- 6) 323 ASH- 1) 1305 EAGLE 3) 139 LAUREL BAY- 5) 414 ELDERBERRY.						
	Purchase Order #		EMERGENCY CONTACT / PHONE NO.:				
16. GENERATOR'S CERTIFICATE: I hereby certify that the above-described materials are not hazardous wastes as defined by CFR Part 261 or any applicable state law, have been fully and accurately described, classified and packaged and are in proper condition for transportation according to applicable regulations.							
Printed Name		Signature "On behalf of"			Month	Day	Year
W.C. DUKAKIS					10	1	12
TRANSPORTER	17. Transporter 1 Acknowledgement of Receipt of Materials		Signature		Month	Day	Year
	Printed Name		Signature		Month	Day	Year
18. Transporter 2 Acknowledgement of Receipt of Materials		Signature		Month	Day	Year	
Printed Name		Signature		Month	Day	Year	
James Baldwin		James Baldwin		10	1	12	
FACILITY	19. Certificate of Final Treatment/Disposal I certify, on behalf of the above listed treatment facility, that to the best of my knowledge, the above-described waste was managed in compliance with all applicable laws, regulations, permits and licenses on the dates listed above.						
	20. Facility Owner or Operator: Certification of receipt of non-hazardous materials covered by this manifest.						
Printed Name		Signature			Month	Day	Year
Toni Coffield		Toni Coffield			10	1	12

White- TREATMENT, STORAGE, DISPOSAL FACILITY COPY

Blue- GENERATOR #2 COPY

Yellow- GENERATOR #1 COPY

Pink- FACILITY USE ONLY

Gold- TRANSPORTER #1 COPY

**Appendix C**  
**Laboratory Analytical Report - Groundwater**

# Volatile Organic Compounds by GC/MS

Client: <b>AECOM - Resolution Consultants</b>	Laboratory ID: <b>QF17014-011</b>
Description: <b>BEALB1417TW01WG20150617-a</b>	Matrix: <b>Aqueous</b>
Date Sampled: <b>06/16/2015 1320</b>	
Date Received: <b>06/18/2015</b>	

Run	Prep Method	Analytical Method	Dilution	Analysis Date	Analyst	Prep Date	Batch
1	5030B	8260B	1	06/25/2015 0228	PMM2		78064

Parameter	CAS Number	Analytical Method	Result	Q	LOQ	LOD	DL	Units	Run
Benzene	71-43-2	8260B	0.45	U	5.0	0.45	0.21	ug/L	1
Ethylbenzene	100-41-4	8260B	0.51	U	5.0	0.51	0.21	ug/L	1
Naphthalene	91-20-3	8260B	0.96	U	5.0	0.96	0.14	ug/L	1
Toluene	108-88-3	8260B	0.48	U	5.0	0.48	0.24	ug/L	1
Xylenes (total)	1330-20-7	8260B	0.57	U	5.0	0.57	0.19	ug/L	1

Surrogate	Q	Run 1 % Recovery	Acceptance Limits
Bromofluorobenzene		110	75-120
1,2-Dichloroethane-d4		90	70-120
Toluene-d8		95	85-120
Dibromofluoromethane		87	85-115

PQL = Practical quantitation limit      B = Detected in the method blank      E = Quantitation of compound exceeded the calibration range      H = Out of holding time      Q = Surrogate failure  
 ND = Not detected at or above the MDL      J = Estimated result < PQL and ≥ MDL      P = The RPD between two GC columns exceeds 40%      N = Recovery is out of criteria      L = LCS/LCSD failure  
 Where applicable, all soil sample analysis are reported on a dry weight basis unless flagged with a "W"      S = MS/MSD failure

Shealy Environmental Services, Inc.  
 106 Vantage Point Drive   West Columbia, SC 29172   (803) 791-9700   Fax (803) 791-9111   www.shealylab.com

# Semivolatile Organic Compounds by GC/MS (SIM)

Client: <b>AECOM - Resolution Consultants</b>	Laboratory ID: <b>QF17014-011</b>
Description: <b>BEALB1417TW01WG20150617-a</b>	Matrix: <b>Aqueous</b>
Date Sampled: <b>06/16/2015 1320</b>	
Date Received: <b>06/18/2015</b>	

Run	Prep Method	Analytical Method	Dilution	Analysis Date	Analyst	Prep Date	Batch
1	3520C	8270D (SIM)	1	06/22/2015 1627	RBH	06/19/2015 1430	77693

Parameter	CAS Number	Analytical Method	Result	Q	LOQ	LOD	DL	Units	Run
Benzo(a)anthracene	56-55-3	8270D (SIM)	0.040	U	0.20	0.040	0.019	ug/L	1
Benzo(b)fluoranthene	205-99-2	8270D (SIM)	0.040	U	0.20	0.040	0.019	ug/L	1
Benzo(k)fluoranthene	207-08-9	8270D (SIM)	0.040	U	0.20	0.040	0.024	ug/L	1
Chrysene	218-01-9	8270D (SIM)	0.040	U	0.20	0.040	0.021	ug/L	1
Dibenzo(a,h)anthracene	53-70-3	8270D (SIM)	0.080	U	0.20	0.080	0.040	ug/L	1

Surrogate	Q	Run 1 % Recovery	Acceptance Limits
2-Methylnaphthalene-d10		74	15-139
Fluoranthene-d10		77	23-154

PQL = Practical quantitation limit      B = Detected in the method blank      E = Quantitation of compound exceeded the calibration range      H = Out of holding time      Q = Surrogate failure  
 ND = Not detected at or above the MDL      J = Estimated result < PQL and ≥ MDL      P = The RPD between two GC columns exceeds 40%      N = Recovery is out of criteria      L = LCS/LCSD failure  
 Where applicable, all soil sample analysis are reported on a dry weight basis unless flagged with a "W"      S = MS/MSD failure

Shealy Environmental Services, Inc.  
 106 Vantage Point Drive   West Columbia, SC 29172   (803) 791-9700   Fax (803) 791-9111   www.shealylab.com



## **Appendix D**

### **Regulatory Correspondence**



W. Marshall Taylor Jr., Acting Director

*Promoting and protecting the health of the public and the environment*

April 7, 2015

Commanding Officer  
Attention: NREAO Mr. William A. Drawdy  
United State Marine Corps Air Station  
Post Office Box 55001  
Beaufort, SC 29904-5001

RE: IGWA  
Laurel Bay Underground Storage Tank Assessment Reports for:  
*See attached sheet*

Dear Mr. Drawdy,

The South Carolina Department of Health and Environmental Control (the Department) received the above referenced Underground Storage Tank Assessment Reports for the addresses listed above. The regulatory authority for the investigation and cleanup of releases from these tank systems is the South Carolina Pollution Control Act (S.C. Code Ann. §48-1-10 et seq., as amended).

The Department has reviewed the referenced assessment reports. The submitted analytical results indicate that petroleum constituents are above established Risk-Based Screening Levels and additional investigation is warranted. Specifically, the Department requests that a groundwater sampling proposal be generated to determine if there has been an impact to groundwater at this site.

Please note that the Department's decision is based on information provided by the Marine Corps Air Station (MCAS) to date. Any information found to be contradictory to this decision may require additional action. Furthermore, the Department retains the right to request further investigation if deemed necessary.

If you have any questions, please contact me at [kriegkm@dhec.sc.gov](mailto:kriegkm@dhec.sc.gov) or 803-898-0255.

Sincerely,

Kent Krieg  
Department of Defense Corrective Action Section  
Bureau of Land and Waste Management  
South Carolina Department of Health and Environmental Control

Cc: Russell Berry (via email)  
Craig Ehde (via email)



Catherine B. Templeton, Director

*Promoting and protecting the health of the public and the environment*

**Attachment to:** Krieg to Drawdy  
**Subject:** IGWA  
**Dated** 4/7/2015

**Laurel Bay Underground Storage Tank Assessment Reports for: (18 addresses/19 tanks)**

1186 Bobwhite	1417 Albatross
1194 Cardinal	1420 Dove
1354 Cardinal	1421 Albatross Tank 1
1362 Cardinal	1421 Albatross Tank 2
1364 Cardinal Tank 1	1427 Albatross
1403 Eagle	1429 Albatross
1404 Eagle	1444 Dove Tank 1
1405 Eagle	1453 Cardinal
1408 Eagle	1455 Cardinal
1410 Eagle	



Catherine E. Heigel, Director

*Promoting and protecting the health of the public and the environment*

Division of Waste Management  
Bureau of Land and Waste Management

February 22, 2016

Commanding Officer  
Attention: NREAO Mr. William A. Drawdy  
United State Marine Corps Air Station  
Post Office Box 55001  
Beaufort, SC 29904-5001

RE: Approval and Concurrence with Draft Final Initial Groundwater Investigation Report-May and June 2015  
Laurel Bay Military Housing Area Multiple Properties  
Dated October 2015

Dear Mr. Drawdy,

The South Carolina Department of Health and Environmental Control (the Department) received groundwater data in the above referenced Groundwater Investigation Report for the addresses attached. The regulatory authority for the investigation and cleanup of releases from these tank systems is the South Carolina Pollution Control Act (S.C. Code Ann. §48-1-10 et seq., as amended).

Per the Department's request, groundwater samples were collected from the attached referenced addresses. The Department reviewed the groundwater data and previous investigations and it agrees with the conclusions and recommendations included in the document. To further assess the impact to groundwater, permanent wells should be installed at the 52 stated addresses. For the remaining 91 addresses, there is no indication of contamination on the property and therefore no further investigation is required at this time.

Please note that the Department's decision is based on information provided by the Marine Corps Air Station (MCAS) to date. Any information found to be contradictory to this decision may require additional action. Furthermore, the Department retains the right to request further investigation if deemed necessary.

If you have any questions, please contact me at [petruslb@dhec.sc.gov](mailto:petruslb@dhec.sc.gov) or 803-898-0294.

Sincerely,

Laurel Petrus  
RCRA Federal Facilities Section

*Attachment: Specific Property Recommendations*

Cc: Russell Berry, EQC Region 8 (via email)  
Shawn Dolan, Resolution Consultants (via email)  
Bryan Beck, NAVFAC MIDATLANTIC (via email)  
Craig Ehde (via email)



Attachment to: Petrus to Drawdy  
 Subject: Draft Final Initial Groundwater Investigation Report-May and June 2015  
 Specific Property Recommendations  
 Dated February 22, 2016

**Draft Final Initial Groundwater Investigation Report for (143 addresses)**

**Permanent Monitoring Well Investigation recommendation (52 addresses)**

273 Birch Drive	1192 Bobwhite Drive
325 Ash Street	1194 Bobwhite Drive
326 Ash Street	1272 Albatross Drive
336 Ash Street	1352 Cardinal Lane
343 Ash Street	1356 Cardinal Lane
353 Ash Street	1359 Cardinal Lane
430 Elderberry Drive	1360 Cardinal Lane
440 Elderberry Drive	1362 Cardinal Lane
456 Elderberry Drive	1370 Cardinal Lane
458 Elderberry Drive	1382 Dove Lane
468 Dogwood Drive	1384 Dove lane
518 Laurel Bay Blvd	1385 Dove Lane
635 Dahlia Drive	1389 Dove Lane
638 Dahlia Drive	1392 Dove Lane
640 Dahlia Drive	1393 Dove Lane
647 Dahlia Drive	1407 Eagle Lane
648 Dahlia Drive	1411 Eagle Lane
650 Dahlia Drive	1418 Albatross Drive
652 Dahlia Drive	1420 Albatross Drive
760 Althea Street	1426 Albatross Drive
1102 Iris Lane	1429 Albatross Drive
1132 Iris Lane	1434 Dove Lane
1133 Iris Lane	1436 Dove Lane
1144 Iris Lane	1440 Dove Lane
1148 Iris Lane	1442 Dove Lane
1186 Bobwhite Drive	1444 Dove Lane

**No Further Action recommendation (91 addresses):**

137 Laurel Bay Blvd	771 Althea Street
139 Laurel Bay Blvd	927 Albacore Street
229 Cypress Street	1015 Foxglove Street
261 Beech Street	1046 Gardenia Drive
276 Birch Drive	1062 Gardenia Drive
278 Birch Drive	1070 Heather Street
291 Birch Drive	1072 Heather Street

300 Ash Street	1107 Iris Lane
304 Ash Street	1126 Iris Lane
314 Ash Street	1129 Iris Lane
322 Ash Street	1138 Iris Lane
323 Ash Street	1161 Jasmine Street
324 Ash Street	1167 Jasmine Street
339 Ash Street	1170 Jasmine Street
344 Ash Street	1190 Bobwhite Drive
348 Ash Street	1219 Cardinal Lane
349 Ash Street	1305 Eagle Lane
362 Aspen Street	1353 Cardinal Lane
376 Aspen Street	1354 Cardinal Lane
380 Aspen Street	1357 Cardinal Lane
383 Aspen Street	1361 Cardinal Lane
387 Acorn Drive	1364 Cardinal Lane
392 Acorn Drive	1368 Cardinal Lane
396 Acorn Drive	1377 Dove Lane
433 Elderberry Drive	1381 Dove Lane
439 Elderberry Drive	1391 Dove Lane
442 Elderberry Drive	1403 Eagle Lane
443 Elderberry Drive	1404 Eagle Lane
444 Elderberry Drive	1405 Eagle Lane
445 Elderberry Drive	1406 Eagle Lane
446 Elderberry Drive	1408 Eagle Lane
448 Elderberry Drive	1410 Eagle Lane
449 Elderberry Drive	1412 Eagle Lane
451 Elderberry Drive	1413 Albatross Drive
453 Elderberry Drive	1414 Albatross Drive
464 Dogwood Drive	1417 Albatross Drive
466 Dogwood Drive	1421 Albatross Drive
467 Dogwood Drive	1422 Albatross Drive
469 Dogwood Drive	1425 Albatross Drive
471 Dogwood Drive	1427 Albatross Drive
475 Dogwood Drive	1430 Dove Lane
516 Laurel Bay Blvd	1432 Dove Lane
531 Laurel Bay Blvd	1438 Dove Lane
532 Laurel Bay Blvd	1453 Cardinal Lane
645 Dahlia Drive	1455 Cardinal Lane
763 Althea Street	