

SUMMARY REPORT
650 WEST CARDINAL LANE (FORMERLY 1467 WEST CARDINAL LANE)
LAUREL BAY MILITARY HOUSING AREA
MARINE CORPS AIR STATION BEAUFORT
BEAUFORT, SC

Revision: 0
Prepared for:

Department of the Navy
Naval Facilities Engineering Command, Mid-Atlantic
9324 Virginia Avenue
Norfolk, Virginia 23511-3095

and



Naval Facilities Engineering Command Atlantic
9324 Virginia Avenue
Norfolk, Virginia 23511-3095

JUNE 2021

SUMMARY REPORT
650 WEST CARDINAL LANE (FORMERLY 1467 WEST CARDINAL LANE)
LAUREL BAY MILITARY HOUSING AREA
MARINE CORPS AIR STATION BEAUFORT
BEAUFORT, SC

Revision: 0
Prepared for:

Department of the Navy
Naval Facilities Engineering Command, Mid- Atlantic
9324 Virginia Avenue
Norfolk, Virginia 23511-3095

and



Naval Facilities Engineering Command Atlantic

9324 Virginia Avenue
Norfolk, Virginia 23511-3095

Prepared by:



CDM - AECOM Multimedia Joint Venture
10560 Arrowhead Drive, Suite 500
Fairfax, Virginia 22030

Contract Number: N62470-14-D-9016
CTO WE52
JUNE 2021

Table of Contents

1.0	INTRODUCTION	1
1.1	BACKGROUND INFORMATION.....	1
1.2	UST REMOVAL AND ASSESSMENT PROCESS.....	2
2.0	SAMPLING ACTIVITIES AND RESULTS	3
2.1	UST REMOVAL AND SOIL SAMPLING	3
2.2	SOIL ANALYTICAL RESULTS.....	4
2.3	GROUNDWATER SAMPLING.....	4
2.4	GROUNDWATER ANALYTICAL RESULTS	5
3.0	PROPERTY STATUS.....	5
4.0	REFERENCES	5

Tables

Table 1	Laboratory Analytical Results - Soil
Table 2	Laboratory Analytical Results - Groundwater

Appendices

Appendix A	Multi-Media Selection Process for LBMH
Appendix B	UST Assessment Report
Appendix C	Laboratory Analytical Report - Groundwater
Appendix D	Regulatory Correspondence

List of Acronyms

bgs	below ground surface
BTEX	benzene, toluene, ethylbenzene, and xylenes
CTO	Contract Task Order
COPC	constituents of potential concern
ft	feet
IDIQ	Indefinite Delivery, Indefinite Quantity
IGWA	Initial Groundwater Assessment
JV	Joint Venture
LBMH	Laurel Bay Military Housing
MCAS	Marine Corps Air Station
NAVFAC Mid-Lant	Naval Facilities Engineering Command Mid-Atlantic
NFA	No Further Action
PAH	polynuclear aromatic hydrocarbon
QAPP	Quality Assurance Program Plan
RBSL	risk-based screening level
SCDHEC	South Carolina Department of Health and Environmental Control
Site	LBMH area at MCAS Beaufort, South Carolina
UST	underground storage tank
VISL	vapor intrusion screening level

1.0 INTRODUCTION

The CDM - AECOM Multimedia Joint Venture (JV) was contracted by the Naval Facilities Engineering Command, Mid-Atlantic (NAVFAC Mid-Lant) to provide reporting services for the heating oil underground storage tanks (USTs) located in Laurel Bay Military Housing (LBMH) area at the Marine Corps Air Station (MCAS) Beaufort, South Carolina (Site). This work has been awarded under Contract Task Order (CTO) WE52 of the Indefinite Delivery, Indefinite Quantity (IDIQ) Multimedia Environmental Compliance Contract (Contract No. N62470-14-D-9016).

As of January 2014, the LBMH addresses were re-numbered to comply with the E-911 emergency response addressing system; however, in order to remain consistent with historical sampling and reporting for LBMH area, the residences will continue to be referenced with their original address numbers in sample nomenclature and reporting documents.

This report summarizes the results the environmental investigation activities associated with the storage of home heating oil and the potential release of petroleum constituents at the referenced property. Based on the results of the investigation, a No Further Action (NFA) determination has been made by the South Carolina Department of Health and Environmental Control (SCDHEC) for 650 West Cardinal Lane (Formerly 1467 West Cardinal Lane). This NFA determination indicates that there are no unacceptable risks to human health or the environment for the petroleum constituents associated with the home heating oil USTs. The following information is included in this report:

- Background information;
- Sampling activities and results; and
- A determination of the property status.

1.1 Background Information

The LBMH area is located approximately 3.5 miles west of MCAS Beaufort. The area is approximately 970 acres in size and serves as an enlisted and officer family housing area. The area is configured with single family and duplex residential structures, and includes recreation, open space, and community facilities. The community includes approximately 1,300 housing units, including legacy Capehart style homes and newer duplex style homes. The housing area

is bordered on the west by salt marshes and the Broad River, and to the north, east and south by uplands. Forested areas lie along the northern and northeastern borders.

Capehart style homes within the LBMH area were formerly heated using heating oil stored in USTs at each residence. There were 1,100 Capehart style housing units in the LBMH area. The newer duplex homes within the LBMH area never utilized heating oil tanks. Heating oil has not been used at Laurel Bay since the mid-1980s. As was the accepted practice at the time, USTs were drained, filled with dirt, capped, and left in place when they were removed from service. Residential USTs are not regulated in the State of South Carolina (i.e., there are no federal or state laws governing installation, management, or removal).

In 2007, MCAS Beaufort began a voluntary program to remove the unregulated, residential USTs and conduct sampling activities to determine if, and to what extent, petroleum constituents may have impacted the surrounding environment. MCAS Beaufort coordinated with SCDHEC to develop removal procedures that were consistent with procedural requirements for regulated USTs. All tank removal activities and follow-on actions are conducted in coordination with SCDHEC. To date, all known USTs have been removed from all residential properties within the LBMH area.

1.2 UST Removal and Assessment Process

During the UST removal process, a soil sample was collected from beneath the UST excavations (approximately 4 to 6 feet [ft] below ground surface [bgs]) and analyzed for a predetermined list of constituents of potential concern (COPCs) associated with the petroleum compounds found in home heating oil. These COPCs, derived from the *Quality Assurance Program Plan (QAPP) for the Underground Storage Tank Management Division, Revision 3.1* (SCDHEC, 2016) and the *Underground Storage Tank Assessment Instructions for Permanent Closure and Change-In-Service*, (SCDHEC, 2018), are as follows:

- benzene, toluene, ethylbenzene, and xylenes (BTEX),
- naphthalene, and
- five select polynuclear aromatic hydrocarbon (PAHs): benzo(a)anthracene, benzo(b)fluoranthene, benzo(k)fluoranthene, chrysene and dibenz(a,h)anthracene.

Soil sample results were submitted by MCAS Beaufort to SCDHEC utilizing SCDHEC's UST Assessment Report form. In accordance with SCDHEC's *QAPP for the UST Management*

Division (SCDHEC, 2016), the soil screening levels consists of SCDHEC risk-based screening levels (RBSLs). It should be noted that the RBSLs for select PAHs were revised in Revision 2.0 of the QAPP (SCDHEC, 2013) and were revised again in Revision 3.0 (SCDHEC, 2015). The screening levels used for evaluation at each site were those levels that were in effect at the time of reporting and review by SCDHEC.

The results of the soil sampling at each former UST location were used to determine if a potential for groundwater contamination exists (i.e., soil results greater than RBSLs) and subsequently to select properties for follow-up initial groundwater assessment (IGWA) sampling. The results of the IGWA sampling (if necessary) are used to determine the presence or absence of the aforementioned COPCs in groundwater and identify whether former UST locations will require additional delineation of COPCs in groundwater. In order to delineate the extent of impact to groundwater, permanent wells are installed and a sampling program is established for those former UST locations where IGWA sampling has indicated the presence of COPCs in excess of the SCDHEC RBSLs for groundwater. Groundwater analytical results are also compared to the site specific groundwater vapor intrusion screening levels (VISLs) to evaluate the potential for vapor intrusion and the necessity for an investigation associated with this media. A multi-media investigation selection process tree, applicable to the LBMH UST investigations, is presented as Appendix A.

2.0 SAMPLING ACTIVITIES AND RESULTS

The following section presents the sampling activities and associated results for 650 West Cardinal Lane (Formerly 1467 West Cardinal Lane). Details regarding the soil investigation at this site are provided in the *SCDHEC UST Assessment Report – 1467 Cardinal Lane* (MCAS Beaufort, 2013). The UST Assessment Report is provided in Appendix B. Details regarding the IGWA sampling activities at this site are provided in the *Initial Groundwater Investigation Report – February 2015* (Resolution Consultants, 2015). The laboratory report that includes the pertinent IGWA analytical results for this site is presented in Appendix C.

2.1 UST Removal and Soil Sampling

On September 25, 2012, a single 280 gallon heating oil UST was removed from the rear patio area 650 West Cardinal Lane (Formerly 1467 West Cardinal Lane). The former UST location is indicated on Figures 2 and 3 of the UST Assessment Report (Appendix B). The UST was removed, cleaned, and shipped offsite for recycling. There was no visual evidence (i.e.,

staining or sheen) of petroleum impact at the time of the UST removal. According to the UST Assessment Report (Appendix B), the depth to the base of the UST was 6' bgs and a single soil sample was collected from that depth. The sample was collected from the fill port side of the former UST to represent a worst case scenario.

Following UST removal, a soil sample was collected from the base of the excavation and shipped to an offsite laboratory for analysis of the petroleum COPCs. Sampling was performed in accordance with applicable South Carolina regulation R.61-92, Part 280 (SCDHEC, 2017) and assessment guidelines.

2.2 Soil Analytical Results

A summary of the laboratory analytical results and SCDHEC RBSLs is presented in Table 1. A copy of the laboratory analytical data report is included in the UST Assessment Report presented in Appendix B. The laboratory analytical data report includes the soil results for the additional PAHs that were analyzed, but do not have associated RBSLs.

The soil sample results were submitted by MCAS Beaufort to SCDHEC utilizing SCDHEC's UST Assessment Report form (Appendix B). The results of the soil sampling at the former UST location were used by MCAS Beaufort, in consultation with SCDHEC, to determine a path forward (i.e., additional sampling or NFA) for the property. The soil results collected from 650 West Cardinal Lane (Formerly 1467 West Cardinal Lane) were greater than the SCDHEC RBSLs, which indicated further investigation was required. In a letter dated April 1, 2014, SCDHEC requested an IGWA for 650 West Cardinal Lane (Formerly 1467 West Cardinal Lane) to determine if the groundwater was impacted by petroleum COPCs. SCDHEC's request letter is provided in Appendix D.

2.3 Groundwater Sampling

On February 4, 2015, a temporary monitoring well was installed at 650 West Cardinal Lane (Formerly 1467 West Cardinal Lane), in accordance with the South Carolina Well Standards and Regulations (R.61-71.H-I, updated June 24, 2016). In order to provide data that can be used to determine whether COPCs are migrating to underlying groundwater, the monitoring well was placed in the same general location as the former heating oil UST. The former UST location is indicated on Figures 2 and 3 of the UST Assessment Report (Appendix B). Further details are provided in the *Initial Groundwater Investigation Report – February 2015* (Resolution Consultants, 2015).

The sampling strategy for this phase of the investigation required a one-time sampling event of the temporarily installed monitoring well. Following well installation and development, groundwater samples were collected using low-flow methods and shipped to an offsite laboratory for analysis of the petroleum COPCs. Upon completion of groundwater sampling, the temporary well was abandoned in accordance with the South Carolina Well Standards and Regulations R.61-71 (SCDHEC, 2016). Field forms are provided in the *Initial Groundwater Investigation Report – February 2015* (Resolution Consultants, 2015).

2.4 Groundwater Analytical Results

A summary of the laboratory analytical results and SCDHEC RBSLs is presented in Table 2. A copy of the laboratory analytical data report is included in Appendix C.

The groundwater results collected from 650 West Cardinal Lane (Formerly 1467 West Cardinal Lane) were less than the SCDHEC RBSLs and the site specific groundwater VISLs (Table 2), which indicated that the groundwater was not impacted by COPCs associated with the former UST at concentrations that present a potential risk to human health and the environment.

3.0 PROPERTY STATUS

Based on the analytical results for groundwater, SCDHEC made the determination that NFA was required for 650 West Cardinal Lane (Formerly 1467 West Cardinal Lane). This NFA determination was obtained in a letter dated May 15, 2015. SCDHEC's NFA letter is provided in Appendix D.

4.0 REFERENCES

Marine Corps Air Station Beaufort, 2013. *South Carolina Department of Health and Environmental Control (SCDHEC) Underground Storage Tank Assessment Report – 1467 Cardinal Lane, Laurel Bay Military Housing Area*, April 2013.

Resolution Consultants, 2015. *Initial Groundwater Investigation Report – February 2015 for Laurel Bay Military Housing Area, Multiple Properties, Laurel Bay Military Housing Area, Marine Corps Air Station Beaufort, Beaufort, South Carolina*, April 2015.

- South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2013. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 2.0*, April 2013.
- South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2015. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.0*, May 2015.
- South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2016. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.1*, February 2016.
- South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2017. *R.61-92, Part 280, Underground Storage Tank Control Regulations*, March 2017.
- South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2018. *Underground Storage Tank Assessment Instructions for Permanent Closure and Change-In-Service*, March 2018.
- South Carolina Department of Health and Environmental Control Bureau of Water, 2016. *R.61-71, Well Standards*, June 2016.

Tables

Table 1
Laboratory Analytical Results - Soil
650 West Cardinal Lane (Formerly 1467 West Cardinal Lane)
Laurel Bay Military Housing Area
Marine Corps Air Station Beaufort
Beaufort, South Carolina

Constituent	SCDHEC RBSLs ⁽¹⁾	Results Sample Collected 09/25/12
Volatile Organic Compounds Analyzed by EPA Method 8260B (mg/kg)		
Benzene	0.003	ND
Ethylbenzene	1.15	0.00172
Naphthalene	0.036	0.0116
Toluene	0.627	0.00203
Xylenes, Total	13.01	0.0101
Semivolatile Organic Compounds Analyzed by EPA Method 8270D (mg/kg)		
Benzo(a)anthracene	0.66	ND
Benzo(b)fluoranthene	0.66	ND
Benzo(k)fluoranthene	0.66	ND
Chrysene	0.66	ND
Dibenz(a,h)anthracene	0.66	ND

Notes:

⁽¹⁾ South Carolina Risk-Based Screening Levels from the Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 2.0 (SCDHEC, April 2013).

Bold font indicates the analyte was detected.

Bold font and shading indicates the concentration exceeds the SCDHEC RBSL.

EPA - United States Environmental Protection Agency

mg/kg - milligrams per kilogram

ND - not detected at the reporting limit (or method detection limit if shown on the laboratory report). The soil laboratory report is provided in Appendix B.

RBSL - Risk-Based Screening Level

SCDHEC - South Carolina Department Of Health and Environmental Control

Table 2
Laboratory Analytical Results - Groundwater
650 West Cardinal Lane (Formerly 1467 West Cardinal Lane)
Laurel Bay Military Housing Area
Marine Corps Air Station Beaufort
Beaufort, South Carolina

Constituent	SCDHEC RBSLs ⁽¹⁾	Site-Specific Groundwater VISLs (µg/L) ⁽²⁾	Results Sample Collected 02/05/15
Volatile Organic Compounds Analyzed by EPA Method 8260B (µg/L)			
Benzene	5	16.24	ND
Ethylbenzene	700	45.95	ND
Naphthalene	25	29.33	ND
Toluene	1000	105,445	ND
Xylenes, Total	10,000	2,133	ND
Semivolatile Organic Compounds Analyzed by EPA Method 8270D (µg/L)			
Benzo(a)anthracene	10	NA	ND
Benzo(b)fluoranthene	10	NA	ND
Benzo(k)fluoranthene	10	NA	ND
Chrysene	10	NA	ND
Dibenz(a,h)anthracene	10	NA	ND

Notes:

(1) South Carolina Risk-Based Screening Levels from the Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.1 (SCDHEC, February 2016).

(2) Site-specific groundwater VISLs were calculated using the EPA JE Model Spreadsheets (Version 3.1, February 2004) and conservative modeling inputs representative of a small single-story house with an 8 foot ceiling. Site-specific groundwater VISLs were developed based on a target risk level of 1×10^{-6} , a target hazard quotient of 1 (per target organ), and a default residential exposure scenario, assuming exposure for 24 hours/day, 350 days/year, for 26 years. Modeling was performed for a range of depths to groundwater for application as appropriate in different areas of the Laurel Bay Military Housing Area. The most conservative levels are presented for comparison. Refer to Appendix H of the Uniform Federal Policy Sampling Analysis and Sampling Plan for Vapor Media, Revision 4 (Resolution Consultants, April 2017) for additional information.

Bold font indicates the analyte was detected.

Bold font and shading indicates the concentration exceeds the SCDHEC RBSL and/or the Site-Specific Groundwater VISL.

EPA - United States Environmental Protection Agency

JE - Johnson & Ettinger

NA - Not Applicable

ND - not detected at the reporting limit (or method detection limit if shown on the laboratory report). The groundwater laboratory report is provided in Appendix C.


RBSL - Risk-Based Screening Level

SCDHEC - South Carolina Department Of Health and Environmental Control

µg/L - micrograms per liter

VISL - Vapor Intrusion Screening Level

Appendix A
Multi-Media Selection Process for LBMH



Appendix A - Multi-Media Selection Process for LBMH

Appendix B
UST Assessment Report

Attachment 1

South Carolina Department of Health and Environmental Control (SCDHEC)
Underground Storage Tank (UST) Assessment Report

Date Received
State Use Only

Submit Completed Form To:
UST Program
SCDHEC
2600 Bull Street
Columbia, South Carolina 29201
Telephone (803) 896-7957

I. OWNERSHIP OF UST (S)

MCAS Beaufort, Commanding Officer Attn: NREAO (Craig Ehde)

Owner Name (Corporation, Individual, Public Agency, Other)

P.O. Box 55001

Mailing Address

Beaufort,

South Carolina

29904-5001

City

State

Zip Code

843

228-7317

Craig Ehde

Area Code

Telephone Number

Contact Person

II. SITE IDENTIFICATION AND LOCATION

Permit I.D. #

Laurel Bay Military Housing Area, Marine Corps Air Station, Beaufort, SC
Facility Name or Company Site Identifier

1467 Cardinal Lane, Laurel Bay Military Housing Area

Street Address or State Road (as applicable)

Beaufort,

Beaufort

City

County

Attachment 2

III. INSURANCE INFORMATION

Insurance Statement

The petroleum release reported to DHEC on _____ at Permit ID Number _____ may qualify to receive state monies to pay for appropriate site rehabilitation activities. Before participation is allowed in the State Clean-up fund, written confirmation of the existence or non-existence of an environmental insurance policy is required. **This section must be completed.**

Is there now, or has there ever been an insurance policy or other financial mechanism that covers this UST release? **YES**____ **NO**____ (check one)

If you answered **YES** to the above question, please complete the following information:

My policy provider is: _____

The policy deductible is: _____

The policy limit is: _____

If you have this type of insurance, please include a copy of the policy with this report.

IV. REQUEST FOR SUPERB FUNDING

I **DO** / **DO NOT** wish to participate in the SUPERB Program. (Circle one.)

V. CERTIFICATION (To be signed by the UST owner)

I certify that I have personally examined and am familiar with the information submitted in this and all attached documents; and that based on my inquiry of those individuals responsible for obtaining this information, I believe that the submitted information is true, accurate, and complete.

Name (Type or print.)

Signature

To be completed by Notary Public:

Sworn before me this _____ day of _____, 20____

(Name)

Notary Public for the state of _____
Please affix State seal if you are commissioned outside South Carolina

VI. UST INFORMATION

- A. Product...(ex. Gas, Kerosene).....
- B. Capacity...(ex. 1k, 2k).....
- C. Age.....
- D. Construction Material...(ex. Steel, FRP).....
- E. Month/Year of Last Use.....
- F. Depth (ft.) To Base of Tank.....
- G. Spill Prevention Equipment Y/N.....
- H. Overfill Prevention Equipment Y/N.....
- I. Method of Closure Removed/Filled.....
- J. Date Tanks Removed/Filled.....
- K. Visible Corrosion or Pitting Y/N.....
- L. Visible Holes Y/N.....

1467 Cardinal		
Heating oil		
280 gal		
Late 1950s		
Steel		
Mid 80s		
6'		
No		
No		
Removed		
9/25/2012		
Yes		
Yes		

- M. Method of disposal for any USTs removed from the ground (attach disposal manifests)
UST 1467Cardinal was removed from the ground and disposed
at a Subtitle "D" landfill. See Attachment "A".
- N. Method of disposal for any liquid petroleum, sludges, or wastewaters removed from the USTs (attach disposal manifests)
UST 1467Cardinal was previously filled with sand by others.
- O. If any corrosion, pitting, or holes were observed, describe the location and extent for each UST
Corrosion, pitting and holes were found throughout the tank.

VII. PIPING INFORMATION

- A. Construction Material..(ex. Steel, FRP).....
- B. Distance from UST to Dispenser.....
- C. Number of Dispensers.....
- D. Type of System Pressure or Suction.....
- E. Was Piping Removed from the Ground? Y/N
- F. Visible Corrosion or Pitting Y/N.....
- G. Visible Holes Y/N.....
- H. Age.....

1467 Cardinal		
Steel & Copper		
N/A		
N/A		
Suction		
No		
Yes		
No		
Late 1950s		

- I. If any corrosion, pitting, or holes were observed, describe the location and extent for each piping run.

Corrosion and pitting were found on the surface of the steel vent pipe. Copper supply and return lines were sound.

VIII. BRIEF SITE DESCRIPTION AND HISTORY

The USTs at the residences are constructed of single wall steel and formerly contained fuel oil for heating. These USTs were installed in the late 1950s and last used in the mid 1980s.

IX. SITE CONDITIONS

	Yes	No	Unk
<p>A. Were any petroleum-stained or contaminated soils found in the UST excavation, soil borings, trenches, or monitoring wells?</p> <p>If yes, indicate depth and location on the site map.</p>		X	
<p>B. Were any petroleum odors detected in the excavation, soil borings, trenches, or monitoring wells?</p> <p>If yes, indicate location on site map and describe the odor (strong, mild, etc.)</p>		X	
<p>C. Was water present in the UST excavation, soil borings, or trenches?</p> <p>If yes, how far below land surface (indicate location and depth)?</p>		X	
<p>D. Did contaminated soils remain stockpiled on site after closure?</p> <p>If yes, indicate the stockpile location on the site map.</p> <p>Name of DHEC representative authorizing soil removal:</p>		X	
<p>E. Was a petroleum sheen or free product detected on any excavation or boring waters?</p> <p>If yes, indicate location and thickness.</p>		X	

X. SAMPLE INFORMATION

A. SCDHEC Lab Certification Number 84009

B.

Sample #	Location	Sample Type (Soil/Water)	Soil Type (Sand/Clay)	Depth*	Date/Time of Collection	Collected by	OVA #
1467 Cardinal	Excav at fill end	Soil	Sandy	6'	9/25/12 1500 hrs	P. Shaw	
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							

* = Depth Below the Surrounding Land Surface

XI. SAMPLING METHODOLOGY

Provide a detailed description of the methods used to collect and store the samples. Also include the preservative used for each sample. Please use the space provided below.

Sampling was performed in accordance with SC DHEC R.61-92 Part 280 and SC DHEC Assessment Guidelines. Sample containers were prepared by the testing laboratory. The grab method was utilized to fill the sample containers leaving as little head space as possible and immediately capped. Soil samples were extracted from area below tank. The samples were marked, logged, and immediately placed in a sample cooler packed with ice to maintain an approximate temperature of 4 degrees Centigrade. Tools were thoroughly cleaned and decontaminated with the seven step decon process after each use. The samples remained in custody of SBG-EEG, Inc. until they were transferred to Test America Incorporated for analysis as documented in the Chain of Custody Record.


XII. RECEPTORS

	Yes	No
<p>A. Are there any lakes, ponds, streams, or wetlands located within 1000 feet of the UST system?</p> <p style="text-align: right;">*Broad River & stormwater canal</p> <p>If yes, indicate type of receptor, distance, and direction on site map.</p>	*X	
<p>B. Are there any public, private, or irrigation water supply wells within 1000 feet of the UST system?</p> <p>If yes, indicate type of well, distance, and direction on site map.</p>		X
<p>C. Are there any underground structures (e.g., basements) Located within 100 feet of the UST system?</p> <p>If yes, indicate type of structure, distance, and direction on site map.</p>		X
<p>D. Are there any underground utilities (e.g., telephone, electricity, gas, water, sewer, storm drain) located within 100 feet of the UST system that could potentially come in contact with the contamination?</p> <p style="text-align: right;">*Sewer, water, electricity cable & fiber optic</p> <p>If yes, indicate the type of utility, distance, and direction on the site map.</p>	*X	
<p>E. Has contaminated soil been identified at a depth less than 3 feet below land surface in an area that is not capped by asphalt or concrete?</p> <p>If yes, indicate the area of contaminated soil on the site map.</p>		X

XIII. SITE MAP

You must supply a scaled site map. It should include all buildings, road names, utilities, tank and dispenser island locations, labeled sample locations, extent of excavation, and any other pertinent information.

(Attach Site Map Here)



0 100 200 400 600 800 1,000
Feet

1467 CARDINAL

SBG-EEG, Inc.

7301 Rivers Ave., Suite 245
N. Charleston SC 29406-9643

Ph. (843) 573-7140


Drawn By: L. DiAsio

Dwg Date: Dec 2012

**FIGURE 1: LOCATION MAP
1467 CARDINAL LANE
LAUREL BAY, BEAUFORT SC**

STORMWATER CANAL $\approx 170'$

BROAD R. $\approx 650'$



TANK DEPTH BELOW GRADE
1467CARDINAL = 36"


SBG-EEG

7301 RIVERS AVE., SUITE 245
N. CHARLESTON SC 29406-9643
(843) 573-7140


FIGURE 2 SITE MAP
1467 CARDINAL LANE, LAUREL BAY
MCAS BEAUFORT SC

SCALE: GRAPHIC

DWG DATE DEC 2012



GRAPHIC SCALE



SBG-EEG

7301 RIVERS AVE., SUITE 245
N. CHARLESTON SC 29406-9643
(843) 573-7140


FIGURE 3 UST SAMPLE LOCATIONS
1467 CARDINAL LANE, LAUREL BAY
MCAS BEAUFORT SC

SCALE: GRAPHIC

DWG DATE DEC 2012



Picture 1: Location of UST 1467Cardinal.



Picture 2: UST 1467Cardinal excavation.

XIV. SUMMARY OF ANALYSIS RESULTS

Enter the soil analytical data for each soil boring for all COC in the table below and on the following page.

CoC	UST 1467Cardinal						
Benzene	ND						
Toluene	0.00203 mg/kg						
Ethylbenzene	0.00172 mg/kg						
Xylenes	0.0101 mg/kg						
Naphthalene	0.0116 mg/kg						
Benzo (a) anthracene	ND						
Benzo (b) fluoranthene	ND						
Benzo (k) fluoranthene	ND						
Chrysene	ND						
Dibenz (a, h) anthracene	ND						
TPH (EPA 3550)							

CoC							
Benzene							
Toluene							
Ethylbenzene							
Xylenes							
Naphthalene							
Benzo (a) anthracene							
Benzo (b) fluoranthene							
Benzo (k) fluoranthene							
Chrysene							
Dibenz (a, h) anthracene							
TPH (EPA 3550)							

SUMMARY OF ANALYSIS RESULTS (cont'd)

Enter the ground water analytical data for each sample for all CoC in the table below. If free product is present, indicate the measured thickness to the nearest 0.01 feet.

CoC	RBSL (µg/l)	W-1	W-2	W -3	W -4
Free Product Thickness	None				
Benzene	5				
Toluene	1,000				
Ethylbenzene	700				
Xylenes	10,000				
Total BTEX	N/A				
MTBE	40				
Naphthalene	25				
Benzo (a) anthracene	10				
Benzo (b) flouranthene	10				
Benzo (k) flouranthene	10				
Chrysene	10				
Dibenz (a, h) anthracene	10				
EDB	.05				
1,2-DCA	5				
Lead	Site specific				

XV. ANALYTICAL RESULTS

You must submit the laboratory report and chain-of-custody form for the samples. These samples must be analyzed by a South Carolina certified laboratory.

(Attach Certified Analytical Results and Chain-of-Custody Here)
(Please see Form #4)

TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING

ANALYTICAL REPORT

TestAmerica Laboratories, Inc.

TestAmerica Nashville
2960 Foster Creighton Drive
Nashville, TN 37204
Tel: (615)726-0177


TestAmerica Job ID: 490-8059-1

Client Project/Site: Laurel Bay Housing Project

For:

Environmental Enterprise Group
10179 Highway 78
Ladson, South Carolina 29456

Attn: Mr. Tom McElwee



Authorized for release by:
10/15/2012 4:22:43 PM

Ken Hayes
Project Manager I
ken.hayes@testamericainc.com

LINKS

Review your project
results through

TotalAccess

Have a Question?



Visit us at:

www.testamericainc.com

The test results in this report meet all 2003 NELAC and 2009 TNI requirements for accredited parameters, exceptions are noted in this report. This report may not be reproduced except in full, and with written approval from the laboratory. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

1

2

3

4

5

6

7

8

9

10

11

12

13

Table of Contents

Cover Page	1
Table of Contents	2
Sample Summary	3
Case Narrative	4
Definitions	5
Client Sample Results	6
QC Sample Results	9
QC Association	15
Chronicle	17
Method Summary	18
Certification Summary	19
Chain of Custody	20
Receipt Checklists	22



Sample Summary

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
490-8059-1	1425 Albatross	Solid	09/24/12 15:45	10/02/12 08:30
490-8059-2	1467 Cardinal	Solid	09/25/12 15:00	10/02/12 08:30
490-8059-3	442 Elderberry	Solid	09/26/12 15:30	10/02/12 08:30

1

2

3

4

5

6

7

8

9

10

11

12

13

Case Narrative

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Job ID: 490-8059-1

Laboratory: TestAmerica Nashville

Narrative

Job Narrative 490-8059-1

Comments

No additional comments.

Receipt

The samples were received on 10/2/2012 8:30 AM; the samples arrived in good condition, properly preserved and, where required, on ice. The temperature of the cooler at receipt was 1.3° C.

GC/MS VOA

Method(s) 8260B: Insufficient sample volume was available to perform a matrix spike/matrix spike duplicate (MS/MSD) associated with batch 25524.

Method(s) 8260B: Insufficient sample volume was available to perform a matrix spike/matrix spike duplicate (MS/MSD) associated with batch 26322. See LCS/LCSD

Method(s) 8260B: Surrogate recovery for the following sample(s) was outside control limits: 1425 Albatross (490-8059-1). Evidence of matrix interference is present; therefore, re-extraction and/or re-analysis was not performed.

Method(s) 8260B: Surrogate recovery for the following sample(s) was outside control limits: 442 Elderberry (490-8059-3). Evidence of matrix interference is present.

Method(s) 8260B: Surrogate recovery for the following sample(s) was outside control limits: 442 Elderberry (490-8059-3). Evidence of matrix interference is present; therefore, re-extraction and/or re-analysis was not performed.

Method(s) 8260B: The method blank for preparation batch 26734 contained Toluene above the reporting limit (RL). None of the samples associated with this method blank have positive results reported for this target compound.

Method(s) 8260B: The method blank for batch 26734 contained Xylenes above the method detection limit. This target analyte concentration was less than the reporting limit (RL); therefore, re-extraction and/or re-analysis of samples was not performed.

No other analytical or quality issues were noted.

GC/MS Semi VOA

Method(s) 8270D: The matrix spike / matrix spike duplicate (MS/MSD) percent recoveries and %RPD for batch 25261 were outside control limits. This is attributed to matrix interferences.

No other analytical or quality issues were noted.

Organic Prep

No analytical or quality issues were noted.

VOA Prep

No analytical or quality issues were noted.

Definitions/Glossary

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Qualifiers

GC/MS VOA

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
X	Surrogate is outside control limits
B	Compound was found in the blank and sample.

GC/MS Semi VOA

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
4	MS, MSD: The analyte present in the original sample is 4 times greater than the matrix spike concentration; therefore, control limits are not applicable.
E	Result exceeded calibration range.
F	RPD of the MS and MSD exceeds the control limits
F	MS or MSD exceeds the control limits

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
☼	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CNF	Contains no Free Liquid
DL, RA, RE, IN	Indicates a Dilution, Reanalysis, Re-extraction, or additional Initial metals/anion analysis of the sample
EDL	Estimated Detection Limit
EPA	United States Environmental Protection Agency
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
ND	Not detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RL	Reporting Limit
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)

Client Sample Results

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Client Sample ID: 1425 Albatross

Lab Sample ID: 490-8059-1

Date Collected: 09/24/12 15:45

Matrix: Solid

Date Received: 10/02/12 08:30

Percent Solids: 81.6

Method: 8260B - Volatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	0.00719		0.00195	0.000652	mg/Kg	☒	10/02/12 16:53	10/04/12 17:35	1
Ethylbenzene	0.105		0.00195	0.000652	mg/Kg	☒	10/02/12 16:53	10/04/12 17:35	1
Naphthalene	3.45		0.301	0.102	mg/Kg	☒	10/02/12 16:47	10/08/12 19:25	1
Toluene	0.00184	J	0.00195	0.000721	mg/Kg	☒	10/02/12 16:53	10/04/12 17:35	1
Xylenes, Total	0.341		0.00487	0.000652	mg/Kg	☒	10/02/12 16:53	10/04/12 17:35	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	94		70 - 130	10/02/12 16:53	10/04/12 17:35	1
1,2-Dichloroethane-d4 (Surr)	116		70 - 130	10/02/12 16:47	10/08/12 19:25	1
4-Bromofluorobenzene (Surr)	95		70 - 130	10/02/12 16:53	10/04/12 17:35	1
4-Bromofluorobenzene (Surr)	138	X	70 - 130	10/02/12 16:47	10/08/12 19:25	1
Dibromofluoromethane (Surr)	98		70 - 130	10/02/12 16:53	10/04/12 17:35	1
Dibromofluoromethane (Surr)	145	X	70 - 130	10/02/12 16:47	10/08/12 19:25	1
Toluene-d8 (Surr)	117		70 - 130	10/02/12 16:53	10/04/12 17:35	1
Toluene-d8 (Surr)	70		70 - 130	10/02/12 16:47	10/08/12 19:25	1

Method: 8270D - Semivolatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	0.366		0.0814	0.0122	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Acenaphthylene	0.246		0.0814	0.0109	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Anthracene	0.224		0.0814	0.0109	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Benzo[a]anthracene	ND		0.0814	0.0182	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Benzo[a]pyrene	ND		0.0814	0.0146	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Benzo[b]fluoranthene	ND		0.0814	0.0146	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Benzo[g,h,i]perylene	ND		0.0814	0.0109	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Benzo[k]fluoranthene	ND		0.0814	0.0170	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Pyrene	0.254		0.0814	0.0146	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Phenanthrene	2.45		0.0814	0.0109	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Chrysene	0.0411	J	0.0814	0.0109	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Dibenz[a,h]anthracene	ND		0.0814	0.00851	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Fluoranthene	0.101		0.0814	0.0109	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Fluorene	1.39		0.0814	0.0146	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Indeno[1,2,3-cd]pyrene	ND		0.0814	0.0122	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
Naphthalene	3.52		0.0814	0.0109	mg/Kg	☒	10/03/12 13:12	10/04/12 21:47	1
2-Methylnaphthalene	19.9		0.814	0.194	mg/Kg	☒	10/03/12 13:12	10/06/12 00:39	10
1-Methylnaphthalene	12.0		0.814	0.170	mg/Kg	☒	10/03/12 13:12	10/06/12 00:39	10

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
2-Fluorobiphenyl (Surr)	68		29 - 120	10/03/12 13:12	10/04/12 21:47	1
2-Fluorobiphenyl (Surr)	101		29 - 120	10/03/12 13:12	10/06/12 00:39	10
Terphenyl-d14 (Surr)	95		13 - 120	10/03/12 13:12	10/04/12 21:47	1
Terphenyl-d14 (Surr)	112		13 - 120	10/03/12 13:12	10/06/12 00:39	10
Nitrobenzene-d5 (Surr)	69		27 - 120	10/03/12 13:12	10/04/12 21:47	1
Nitrobenzene-d5 (Surr)	112		27 - 120	10/03/12 13:12	10/06/12 00:39	10

General Chemistry

Analyte	Result	Qualifier	RL	RL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Solids	82		0.10	0.10	%			10/03/12 09:15	1

Client Sample Results

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Client Sample ID: 1467 Cardinal

Lab Sample ID: 490-8059-2

Date Collected: 09/25/12 15:00

Matrix: Solid

Date Received: 10/02/12 08:30

Percent Solids: 82.4

Method: 8260B - Volatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.00196	0.000657	mg/Kg	☒	10/02/12 16:53	10/04/12 18:06	1
Ethylbenzene	0.00172	J	0.00196	0.000657	mg/Kg	☒	10/02/12 16:53	10/04/12 18:06	1
Naphthalene	0.0116		0.00490	0.00167	mg/Kg	☒	10/02/12 16:53	10/04/12 18:06	1
Toluene	0.00203		0.00196	0.000726	mg/Kg	☒	10/02/12 16:53	10/04/12 18:06	1
Xylenes, Total	0.0101		0.00490	0.000657	mg/Kg	☒	10/02/12 16:53	10/04/12 18:06	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	88		70 - 130	10/02/12 16:53	10/04/12 18:06	1
4-Bromofluorobenzene (Surr)	87		70 - 130	10/02/12 16:53	10/04/12 18:06	1
Dibromofluoromethane (Surr)	104		70 - 130	10/02/12 16:53	10/04/12 18:06	1
Toluene-d8 (Surr)	110		70 - 130	10/02/12 16:53	10/04/12 18:06	1

Method: 8270D - Semivolatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.0803	0.0120	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Acenaphthylene	ND		0.0803	0.0108	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Anthracene	ND		0.0803	0.0108	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Benzo[a]anthracene	ND		0.0803	0.0180	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Benzo[a]pyrene	ND		0.0803	0.0144	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Benzo[b]fluoranthene	ND		0.0803	0.0144	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Benzo[g,h,i]perylene	ND		0.0803	0.0108	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Benzo[k]fluoranthene	ND		0.0803	0.0168	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Pyrene	ND		0.0803	0.0144	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Phenanthrene	ND		0.0803	0.0108	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Chrysene	ND		0.0803	0.0108	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Dibenz(a,h)anthracene	ND		0.0803	0.00839	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Fluoranthene	ND		0.0803	0.0108	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Fluorene	ND		0.0803	0.0144	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Indeno[1,2,3-cd]pyrene	ND		0.0803	0.0120	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
Naphthalene	ND		0.0803	0.0108	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
2-Methylnaphthalene	ND		0.0803	0.0192	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1
1-Methylnaphthalene	ND		0.0803	0.0168	mg/Kg	☒	10/03/12 13:12	10/04/12 22:48	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
2-Fluorobiphenyl (Surr)	52		29 - 120	10/03/12 13:12	10/04/12 22:48	1
Terphenyl-d14 (Surr)	70		13 - 120	10/03/12 13:12	10/04/12 22:48	1
Nitrobenzene-d5 (Surr)	52		27 - 120	10/03/12 13:12	10/04/12 22:48	1

General Chemistry

Analyte	Result	Qualifier	RL	RL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Solids	82		0.10	0.10	%			10/03/12 09:15	1

Client Sample Results

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Client Sample ID: 442 Elderberry

Lab Sample ID: 490-8059-3

Date Collected: 09/26/12 15:30

Matrix: Solid

Date Received: 10/02/12 08:30

Percent Solids: 81.1

Method: 8260B - Volatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	0.00587		0.00196	0.000656	mg/Kg	☒	10/02/12 16:53	10/04/12 18:37	1
Ethylbenzene	0.680		0.116	0.0394	mg/Kg	☒	10/02/12 16:47	10/09/12 21:09	1
Naphthalene	4.55		0.290	0.0985	mg/Kg	☒	10/02/12 16:47	10/09/12 21:09	1
Toluene	0.00470		0.00196	0.000724	mg/Kg	☒	10/02/12 16:53	10/04/12 18:37	1
Xylenes, Total	0.490	B	0.290	0.0394	mg/Kg	☒	10/02/12 16:47	10/09/12 21:09	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	96		70 - 130	10/02/12 16:53	10/04/12 18:37	1
1,2-Dichloroethane-d4 (Surr)	99		70 - 130	10/02/12 16:47	10/09/12 21:09	1
4-Bromofluorobenzene (Surr)	378	X	70 - 130	10/02/12 16:53	10/04/12 18:37	1
4-Bromofluorobenzene (Surr)	132	X	70 - 130	10/02/12 16:47	10/09/12 21:09	1
Dibromofluoromethane (Surr)	104		70 - 130	10/02/12 16:53	10/04/12 18:37	1
Dibromofluoromethane (Surr)	100		70 - 130	10/02/12 16:47	10/09/12 21:09	1
Toluene-d8 (Surr)	0.1	X	70 - 130	10/02/12 16:53	10/04/12 18:37	1
Toluene-d8 (Surr)	105		70 - 130	10/02/12 16:47	10/09/12 21:09	1

Method: 8270D - Semivolatile Organic Compounds (GC/MS)

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	0.243		0.0823	0.0123	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Acenaphthylene	0.157		0.0823	0.0111	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Anthracene	0.224		0.0823	0.0111	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Benzo[a]anthracene	0.457		0.0823	0.0184	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Benzo[a]pyrene	0.192		0.0823	0.0147	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Benzo[b]fluoranthene	0.306		0.0823	0.0147	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Benzo[g,h,i]perylene	0.0452	J	0.0823	0.0111	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Benzo[k]fluoranthene	0.287		0.0823	0.0172	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Pyrene	1.00		0.0823	0.0147	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Phenanthrene	1.94		0.0823	0.0111	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Chrysene	0.428		0.0823	0.0111	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Dibenz(a,h)anthracene	ND		0.0823	0.00860	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Fluoranthene	0.924		0.0823	0.0111	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Fluorene	0.735		0.0823	0.0147	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Indeno[1,2,3-cd]pyrene	0.0459	J	0.0823	0.0123	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
Naphthalene	0.455		0.0823	0.0111	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
2-Methylnaphthalene	4.95	E	0.0823	0.0196	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1
1-Methylnaphthalene	3.31		0.0823	0.0172	mg/Kg	☒	10/03/12 13:15	10/04/12 23:08	1

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
2-Fluorobiphenyl (Surr)	75		29 - 120	10/03/12 13:15	10/04/12 23:08	1
Terphenyl-d14 (Surr)	95		13 - 120	10/03/12 13:15	10/04/12 23:08	1
Nitrobenzene-d5 (Surr)	71		27 - 120	10/03/12 13:15	10/04/12 23:08	1

General Chemistry

Analyte	Result	Qualifier	RL	RL	Unit	D	Prepared	Analyzed	Dil Fac
Percent Solids	81		0.10	0.10	%			10/03/12 09:15	1

QC Sample Results

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Method: 8260B - Volatile Organic Compounds (GC/MS)

Lab Sample ID: 400-69151-B-10-D MS

Matrix: Solid

Analysis Batch: 26734

Client Sample ID: Matrix Spike

Prep Type: Total/NA

Prep Batch: 24942

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Benzene	0.00527		0.0603	0.08448		mg/Kg	☒	131	31 - 143
Ethylbenzene	0.00460		0.0603	0.05869		mg/Kg	☒	90	23 - 161
Naphthalene	ND		0.0603	0.01550		mg/Kg	☒	26	10 - 176
Toluene	0.0135		0.0603	0.08036		mg/Kg	☒	111	30 - 155
Xylenes, Total	0.00839		0.181	0.1604		mg/Kg	☒	84	25 - 162

Surrogate	MS %Recovery	MS Qualifier	Limits
1,2-Dichloroethane-d4 (Surr)	102		70 - 130
4-Bromofluorobenzene (Surr)	118		70 - 130
Dibromofluoromethane (Surr)	105		70 - 130
Toluene-d8 (Surr)	111		70 - 130

Lab Sample ID: 400-69151-B-10-E MSD

Matrix: Solid

Analysis Batch: 26734

Client Sample ID: Matrix Spike Duplicate

Prep Type: Total/NA

Prep Batch: 24942

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	Limit
Benzene	0.00527		0.0588	0.07036		mg/Kg	☒	111	31 - 143	18	50
Ethylbenzene	0.00460		0.0588	0.05607		mg/Kg	☒	88	23 - 161	5	50
Naphthalene	ND		0.0588	0.01463		mg/Kg	☒	25	10 - 176	6	50
Toluene	0.0135		0.0588	0.06497		mg/Kg	☒	88	30 - 155	21	50
Xylenes, Total	0.00839		0.176	0.1505		mg/Kg	☒	81	25 - 162	6	50

Surrogate	MSD %Recovery	MSD Qualifier	Limits
1,2-Dichloroethane-d4 (Surr)	99		70 - 130
4-Bromofluorobenzene (Surr)	116		70 - 130
Dibromofluoromethane (Surr)	102		70 - 130
Toluene-d8 (Surr)	104		70 - 130

Lab Sample ID: MB 490-25524/7

Matrix: Solid

Analysis Batch: 25524

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.00200	0.000670	mg/Kg			10/04/12 15:00	1
Ethylbenzene	ND		0.00200	0.000670	mg/Kg			10/04/12 15:00	1
Naphthalene	ND		0.00500	0.00170	mg/Kg			10/04/12 15:00	1
Toluene	ND		0.00200	0.000740	mg/Kg			10/04/12 15:00	1
Xylenes, Total	ND		0.00500	0.000670	mg/Kg			10/04/12 15:00	1

Surrogate	MB %Recovery	MB Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	93		70 - 130		10/04/12 15:00	1
4-Bromofluorobenzene (Surr)	85		70 - 130		10/04/12 15:00	1
Dibromofluoromethane (Surr)	101		70 - 130		10/04/12 15:00	1
Toluene-d8 (Surr)	110		70 - 130		10/04/12 15:00	1

QC Sample Results

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

Lab Sample ID: LCS 490-25524/5

Matrix: Solid

Analysis Batch: 25524

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

	LCS	LCS	
Surrogate	%Recovery	Qualifier	Limits
1,2-Dichloroethane-d4 (Surr)	92		70 - 130
4-Bromofluorobenzene (Surr)	96		70 - 130
Dibromofluoromethane (Surr)	98		70 - 130
Toluene-d8 (Surr)	110		70 - 130

Lab Sample ID: LCSD 490-25524/4

Matrix: Solid

Analysis Batch: 25524

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

	Spike	LCSD	LCSD				%Rec.		RPD
Analyte	Added	Result	Qualifier	Unit	D	%Rec	Limits	RPD	Limit
Benzene	0.0500	0.05305		mg/Kg		106	75 - 127	1	50
Ethylbenzene	0.0500	0.05751		mg/Kg		115	80 - 134	2	50
Naphthalene	0.0500	0.05096		mg/Kg		102	69 - 150	1	50
Toluene	0.0500	0.05551		mg/Kg		111	80 - 132	3	50
Xylenes, Total	0.150	0.1736		mg/Kg		116	80 - 137	2	50

	LCSD	LCSD	
Surrogate	%Recovery	Qualifier	Limits
1,2-Dichloroethane-d4 (Surr)	88		70 - 130
4-Bromofluorobenzene (Surr)	86		70 - 130
Dibromofluoromethane (Surr)	100		70 - 130
Toluene-d8 (Surr)	108		70 - 130

Lab Sample ID: MB 490-26322/11

Matrix: Solid

Analysis Batch: 26322

Client Sample ID: Method Blank

Prep Type: Total/NA

	MB	MB							
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.100	0.0340	mg/Kg			10/08/12 14:26	1
Ethylbenzene	ND		0.100	0.0340	mg/Kg			10/08/12 14:26	1
Naphthalene	ND		0.250	0.0850	mg/Kg			10/08/12 14:26	1
Toluene	ND		0.100	0.0370	mg/Kg			10/08/12 14:26	1
Xylenes, Total	ND		0.250	0.0340	mg/Kg			10/08/12 14:26	1

	MB	MB							
Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac			
1,2-Dichloroethane-d4 (Surr)	94		70 - 130		10/08/12 14:26	1			
4-Bromofluorobenzene (Surr)	102		70 - 130		10/08/12 14:26	1			
Dibromofluoromethane (Surr)	97		70 - 130		10/08/12 14:26	1			
Toluene-d8 (Surr)	102		70 - 130		10/08/12 14:26	1			

Lab Sample ID: LCS 490-26322/7

Matrix: Solid

Analysis Batch: 26322

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

	Spike	LCS	LCS				%Rec.		
Analyte	Added	Result	Qualifier	Unit	D	%Rec	Limits		
Benzene	0.0500	0.04950		mg/Kg		99	75 - 127		
Ethylbenzene	0.0500	0.04981		mg/Kg		100	80 - 134		
Naphthalene	0.0500	0.05225		mg/Kg		104	69 - 150		
Toluene	0.0500	0.05029		mg/Kg		101	80 - 132		
Xylenes, Total	0.150	0.1488		mg/Kg		99	80 - 137		

QC Sample Results

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

Lab Sample ID: LCS 490-26322/7

Matrix: Solid

Analysis Batch: 26322

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

	LCS	LCS	
Surrogate	%Recovery	Qualifier	Limits
1,2-Dichloroethane-d4 (Surr)	98		70 - 130
4-Bromofluorobenzene (Surr)	101		70 - 130
Dibromofluoromethane (Surr)	100		70 - 130
Toluene-d8 (Surr)	101		70 - 130

Lab Sample ID: LCSD 490-26322/8

Matrix: Solid

Analysis Batch: 26322

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

	Spike	LCSD	LCSD				%Rec.		RPD
Analyte	Added	Result	Qualifier	Unit	D	%Rec	Limits	RPD	Limit
Benzene	0.0500	0.05126		mg/Kg		103	75 - 127	3	50
Ethylbenzene	0.0500	0.05307		mg/Kg		106	80 - 134	6	50
Naphthalene	0.0500	0.05480		mg/Kg		110	69 - 150	5	50
Toluene	0.0500	0.05181		mg/Kg		104	80 - 132	3	50
Xylenes, Total	0.150	0.1594		mg/Kg		106	80 - 137	7	50

	LCSD	LCSD	
Surrogate	%Recovery	Qualifier	Limits
1,2-Dichloroethane-d4 (Surr)	98		70 - 130
4-Bromofluorobenzene (Surr)	101		70 - 130
Dibromofluoromethane (Surr)	97		70 - 130
Toluene-d8 (Surr)	97		70 - 130

Lab Sample ID: MB 490-26734/9

Matrix: Solid

Analysis Batch: 26734

Client Sample ID: Method Blank

Prep Type: Total/NA

	MB	MB							
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.100	0.0340	mg/Kg			10/09/12 20:15	1
Ethylbenzene	ND		0.100	0.0340	mg/Kg			10/09/12 20:15	1
Naphthalene	ND		0.250	0.0850	mg/Kg			10/09/12 20:15	1
Toluene	0.1218		0.100	0.0370	mg/Kg			10/09/12 20:15	1
Xylenes, Total	0.1573	J	0.250	0.0340	mg/Kg			10/09/12 20:15	1

	MB	MB				
Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4 (Surr)	102		70 - 130		10/09/12 20:15	1
4-Bromofluorobenzene (Surr)	113		70 - 130		10/09/12 20:15	1
Dibromofluoromethane (Surr)	102		70 - 130		10/09/12 20:15	1
Toluene-d8 (Surr)	106		70 - 130		10/09/12 20:15	1

Lab Sample ID: LCS 490-26734/3

Matrix: Solid

Analysis Batch: 26734

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

		Spike	LCS	LCS				%Rec.
Analyte		Added	Result	Qualifier	Unit	D	%Rec	Limits
Benzene		0.0500	0.05252		mg/Kg		105	75 - 127
Ethylbenzene		0.0500	0.05438		mg/Kg		109	80 - 134
Naphthalene		0.0500	0.05434		mg/Kg		109	69 - 150
Toluene		0.0500	0.05406		mg/Kg		108	80 - 132
Xylenes, Total		0.150	0.1673		mg/Kg		112	80 - 137

QC Sample Results

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Method: 8260B - Volatile Organic Compounds (GC/MS) (Continued)

Lab Sample ID: LCS 490-26734/3

Matrix: Solid

Analysis Batch: 26734

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

	LCS	LCS	
Surrogate	%Recovery	Qualifier	Limits
1,2-Dichloroethane-d4 (Surr)	97		70 - 130
4-Bromofluorobenzene (Surr)	124		70 - 130
Dibromofluoromethane (Surr)	104		70 - 130
Toluene-d8 (Surr)	106		70 - 130

Lab Sample ID: LCSD 490-26734/4

Matrix: Solid

Analysis Batch: 26734

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

	Spike	LCSD	LCSD				%Rec.		RPD
Analyte	Added	Result	Qualifier	Unit	D	%Rec	Limits	RPD	Limit
Benzene	0.0500	0.05574		mg/Kg		111	75 - 127	6	50
Ethylbenzene	0.0500	0.05359		mg/Kg		107	80 - 134	1	50
Naphthalene	0.0500	0.05484		mg/Kg		110	69 - 150	1	50
Toluene	0.0500	0.05656		mg/Kg		113	80 - 132	5	50
Xylenes, Total	0.150	0.1637		mg/Kg		109	80 - 137	2	50

	LCSD	LCSD	
Surrogate	%Recovery	Qualifier	Limits
1,2-Dichloroethane-d4 (Surr)	96		70 - 130
4-Bromofluorobenzene (Surr)	120		70 - 130
Dibromofluoromethane (Surr)	102		70 - 130
Toluene-d8 (Surr)	110		70 - 130

Method: 8270D - Semivolatile Organic Compounds (GC/MS)

Lab Sample ID: MB 490-25261/1-A

Matrix: Solid

Analysis Batch: 25523

Client Sample ID: Method Blank

Prep Type: Total/NA

Prep Batch: 25261

	MB	MB							
Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.0670	0.0100	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Acenaphthylene	ND		0.0670	0.00900	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Anthracene	ND		0.0670	0.00900	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Benzo[a]anthracene	ND		0.0670	0.0150	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Benzo[a]pyrene	ND		0.0670	0.0120	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Benzo[b]fluoranthene	ND		0.0670	0.0120	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Benzo[g,h,i]perylene	ND		0.0670	0.00900	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Benzo[k]fluoranthene	ND		0.0670	0.0140	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Pyrene	ND		0.0670	0.0120	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Phenanthrene	ND		0.0670	0.00900	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Chrysene	ND		0.0670	0.00900	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Dibenz(a,h)anthracene	ND		0.0670	0.00700	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Fluoranthene	ND		0.0670	0.00900	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Fluorene	ND		0.0670	0.0120	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Indeno[1,2,3-cd]pyrene	ND		0.0670	0.0100	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
Naphthalene	ND		0.0670	0.00900	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
2-Methylnaphthalene	ND		0.0670	0.0160	mg/Kg		10/03/12 13:12	10/04/12 21:26	1
1-Methylnaphthalene	ND		0.0670	0.0140	mg/Kg		10/03/12 13:12	10/04/12 21:26	1

QC Sample Results

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Method: 8270D - Semivolatile Organic Compounds (GC/MS) (Continued)

Lab Sample ID: MB 490-25261/1-A

Matrix: Solid

Analysis Batch: 25523

Client Sample ID: Method Blank

Prep Type: Total/NA

Prep Batch: 25261

Surrogate	MB	MB	Limits	Prepared	Analyzed	Dil Fac
2-Fluorobiphenyl (Surr)	64		29 - 120	10/03/12 13:12	10/04/12 21:26	1
Terphenyl-d14 (Surr)	80		13 - 120	10/03/12 13:12	10/04/12 21:26	1
Nitrobenzene-d5 (Surr)	63		27 - 120	10/03/12 13:12	10/04/12 21:26	1

Lab Sample ID: LCS 490-25261/2-A

Matrix: Solid

Analysis Batch: 25523

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Prep Batch: 25261

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Acenaphthylene	1.67	1.485		mg/Kg		89	38 - 120
Anthracene	1.67	1.421		mg/Kg		85	46 - 124
Benzo[a]anthracene	1.67	1.433		mg/Kg		86	45 - 120
Benzo[a]pyrene	1.67	1.539		mg/Kg		92	45 - 120
Benzo[b]fluoranthene	1.67	1.668		mg/Kg		100	42 - 120
Benzo[g,h,i]perylene	1.67	1.159		mg/Kg		70	38 - 120
Benzo[k]fluoranthene	1.67	1.402		mg/Kg		84	42 - 120
Pyrene	1.67	1.410		mg/Kg		85	43 - 120
Phenanthrene	1.67	1.390		mg/Kg		83	45 - 120
Chrysene	1.67	1.349		mg/Kg		81	43 - 120
Dibenz(a,h)anthracene	1.67	1.179		mg/Kg		71	32 - 128
Fluoranthene	1.67	1.452		mg/Kg		87	46 - 120
Fluorene	1.67	1.493		mg/Kg		90	42 - 120
Indeno[1,2,3-cd]pyrene	1.67	1.171		mg/Kg		70	41 - 121
Naphthalene	1.67	1.552		mg/Kg		93	32 - 120
2-Methylnaphthalene	1.67	1.439		mg/Kg		86	28 - 120
1-Methylnaphthalene	1.67	1.394		mg/Kg		84	32 - 120

Surrogate	LCS	LCS	Limits
2-Fluorobiphenyl (Surr)	61		29 - 120
Terphenyl-d14 (Surr)	74		13 - 120
Nitrobenzene-d5 (Surr)	59		27 - 120

Lab Sample ID: 490-8059-1 MS

Matrix: Solid

Analysis Batch: 25523

Client Sample ID: 1425 Albatross

Prep Type: Total/NA

Prep Batch: 25261

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Acenaphthylene	0.246		2.04	1.866		mg/Kg	☒	79	25 - 120
Anthracene	0.224		2.04	1.826		mg/Kg	☒	79	28 - 125
Benzo[a]anthracene	ND		2.04	1.671		mg/Kg	☒	82	23 - 120
Benzo[a]pyrene	ND		2.04	1.824		mg/Kg	☒	89	15 - 128
Benzo[b]fluoranthene	ND		2.04	1.704		mg/Kg	☒	84	12 - 133
Benzo[g,h,i]perylene	ND		2.04	1.561		mg/Kg	☒	77	22 - 120
Benzo[k]fluoranthene	ND		2.04	1.836		mg/Kg	☒	90	28 - 120
Pyrene	0.254		2.04	2.042		mg/Kg	☒	88	20 - 123
Phenanthrene	2.45		2.04	4.004		mg/Kg	☒	76	21 - 122
Chrysene	0.0411	J	2.04	1.525		mg/Kg	☒	73	20 - 120
Dibenz(a,h)anthracene	ND		2.04	1.594		mg/Kg	☒	78	12 - 128
Fluoranthene	0.101		2.04	1.606		mg/Kg	☒	74	10 - 143

QC Sample Results

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Method: 8270D - Semivolatile Organic Compounds (GC/MS) (Continued)

Lab Sample ID: 490-8059-1 MS

Matrix: Solid

Analysis Batch: 25523

Client Sample ID: 1425 Albatross

Prep Type: Total/NA

Prep Batch: 25261

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Fluorene	1.39		2.04	3.159		mg/Kg	☒	87	20 - 120
Indeno[1,2,3-cd]pyrene	ND		2.04	1.605		mg/Kg	☒	79	22 - 121
Naphthalene	3.52		2.04	5.153	E	mg/Kg	☒	80	10 - 120
2-Methylnaphthalene	12.3		2.04	13.23	E 4	mg/Kg	☒	47	13 - 120
1-Methylnaphthalene	8.24		2.04	9.728	E 4	mg/Kg	☒	73	10 - 120

Surrogate	MS %Recovery	MS Qualifier	Limits
2-Fluorobiphenyl (Surr)	58		29 - 120
Terphenyl-d14 (Surr)	70		13 - 120
Nitrobenzene-d5 (Surr)	62		27 - 120

Lab Sample ID: 490-8059-1 MSD

Matrix: Solid

Analysis Batch: 25523

Client Sample ID: 1425 Albatross

Prep Type: Total/NA

Prep Batch: 25261

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Acenaphthylene	0.246		2.01	1.849		mg/Kg	☒	80	25 - 120	1	50
Anthracene	0.224		2.01	1.783		mg/Kg	☒	78	28 - 125	2	49
Benzo[a]anthracene	ND		2.01	1.778		mg/Kg	☒	89	23 - 120	6	50
Benzo[a]pyrene	ND		2.01	1.919		mg/Kg	☒	96	15 - 128	5	50
Benzo[b]fluoranthene	ND		2.01	1.865		mg/Kg	☒	93	12 - 133	9	50
Benzo[g,h,i]perylene	ND		2.01	1.627		mg/Kg	☒	81	22 - 120	4	50
Benzo[k]fluoranthene	ND		2.01	1.957		mg/Kg	☒	97	28 - 120	6	45
Pyrene	0.254		2.01	1.827		mg/Kg	☒	78	20 - 123	11	50
Phenanthrene	2.45		2.01	2.691	F	mg/Kg	☒	12	21 - 122	39	50
Chrysene	0.0411	J	2.01	1.604		mg/Kg	☒	78	20 - 120	5	49
Dibenz[a,h]anthracene	ND		2.01	1.637		mg/Kg	☒	81	12 - 128	3	50
Fluoranthene	0.101		2.01	1.742		mg/Kg	☒	82	10 - 143	8	50
Fluorene	1.39		2.01	2.242		mg/Kg	☒	43	20 - 120	34	50
Indeno[1,2,3-cd]pyrene	ND		2.01	1.652		mg/Kg	☒	82	22 - 121	3	50
Naphthalene	3.52		2.01	2.977	F	mg/Kg	☒	-27	10 - 120	54	50
2-Methylnaphthalene	12.3		2.01	6.660	E 4 F	mg/Kg	☒	-279	13 - 120	66	50
1-Methylnaphthalene	8.24		2.01	4.633	E 4 F	mg/Kg	☒	-180	10 - 120	71	50

Surrogate	MSD %Recovery	MSD Qualifier	Limits
2-Fluorobiphenyl (Surr)	65		29 - 120
Terphenyl-d14 (Surr)	73		13 - 120
Nitrobenzene-d5 (Surr)	65		27 - 120

Method: Moisture - Percent Moisture

Lab Sample ID: 490-8127-C-1 DU

Matrix: Solid

Analysis Batch: 25123

Client Sample ID: Duplicate

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Percent Solids	84		84		%		0.1	20

QC Association Summary

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

GC/MS VOA

Prep Batch: 24942

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
400-69151-B-10-D MS	Matrix Spike	Total/NA	Solid	5035	
400-69151-B-10-E MSD	Matrix Spike Duplicate	Total/NA	Solid	5035	

Prep Batch: 25021

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-8059-1	1425 Albatross	Total/NA	Solid	5035	
490-8059-3	442 Elderberry	Total/NA	Solid	5035	

Prep Batch: 25026

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-8059-1	1425 Albatross	Total/NA	Solid	5035	
490-8059-2	1467 Cardinal	Total/NA	Solid	5035	
490-8059-3	442 Elderberry	Total/NA	Solid	5035	

Analysis Batch: 25524

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-8059-1	1425 Albatross	Total/NA	Solid	8260B	25026
490-8059-2	1467 Cardinal	Total/NA	Solid	8260B	25026
490-8059-3	442 Elderberry	Total/NA	Solid	8260B	25026
LCS 490-25524/5	Lab Control Sample	Total/NA	Solid	8260B	
LCSD 490-25524/4	Lab Control Sample Dup	Total/NA	Solid	8260B	
MB 490-25524/7	Method Blank	Total/NA	Solid	8260B	

Analysis Batch: 26322

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-8059-1	1425 Albatross	Total/NA	Solid	8260B	25021
LCS 490-26322/7	Lab Control Sample	Total/NA	Solid	8260B	
LCSD 490-26322/8	Lab Control Sample Dup	Total/NA	Solid	8260B	
MB 490-26322/11	Method Blank	Total/NA	Solid	8260B	

Analysis Batch: 26734

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
400-69151-B-10-D MS	Matrix Spike	Total/NA	Solid	8260B	24942
400-69151-B-10-E MSD	Matrix Spike Duplicate	Total/NA	Solid	8260B	24942
490-8059-3	442 Elderberry	Total/NA	Solid	8260B	25021
LCS 490-26734/3	Lab Control Sample	Total/NA	Solid	8260B	
LCSD 490-26734/4	Lab Control Sample Dup	Total/NA	Solid	8260B	
MB 490-26734/9	Method Blank	Total/NA	Solid	8260B	

GC/MS Semi VOA

Prep Batch: 25261

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-8059-1	1425 Albatross	Total/NA	Solid	3550C	
490-8059-1 MS	1425 Albatross	Total/NA	Solid	3550C	
490-8059-1 MSD	1425 Albatross	Total/NA	Solid	3550C	
490-8059-2	1467 Cardinal	Total/NA	Solid	3550C	
490-8059-3	442 Elderberry	Total/NA	Solid	3550C	
LCS 490-25261/2-A	Lab Control Sample	Total/NA	Solid	3550C	
MB 490-25261/1-A	Method Blank	Total/NA	Solid	3550C	

QC Association Summary

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

GC/MS Semi VOA (Continued)

Analysis Batch: 25523

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-8059-1	1425 Albatross	Total/NA	Solid	8270D	25261
490-8059-1 MS	1425 Albatross	Total/NA	Solid	8270D	25261
490-8059-1 MSD	1425 Albatross	Total/NA	Solid	8270D	25261
490-8059-2	1467 Cardinal	Total/NA	Solid	8270D	25261
490-8059-3	442 Elderberry	Total/NA	Solid	8270D	25261
LCS 490-25261/2-A	Lab Control Sample	Total/NA	Solid	8270D	25261
MB 490-25261/1-A	Method Blank	Total/NA	Solid	8270D	25261

Analysis Batch: 25878

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-8059-1	1425 Albatross	Total/NA	Solid	8270D	25261

General Chemistry

Analysis Batch: 25123

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
490-8059-1	1425 Albatross	Total/NA	Solid	Moisture	
490-8059-2	1467 Cardinal	Total/NA	Solid	Moisture	
490-8059-3	442 Elderberry	Total/NA	Solid	Moisture	
490-8127-C-1 DU	Duplicate	Total/NA	Solid	Moisture	

Lab Chronicle

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Client Sample ID: 1425 Albatross

Date Collected: 09/24/12 15:45

Date Received: 10/02/12 08:30

Lab Sample ID: 490-8059-1

Matrix: Solid

Percent Solids: 81.6

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	5035			25026	10/02/12 16:53	ML	TAL NSH
Total/NA	Analysis	8260B		1	25524	10/04/12 17:35	FE	TAL NSH
Total/NA	Prep	5035			25021	10/02/12 16:47	ML	TAL NSH
Total/NA	Analysis	8260B		1	26322	10/08/12 19:25	KK	TAL NSH
Total/NA	Prep	3550C			25261	10/03/12 13:12	AK	TAL NSH
Total/NA	Analysis	8270D		1	25523	10/04/12 21:47	WS	TAL NSH
Total/NA	Analysis	8270D		10	25878	10/06/12 00:39	WS	TAL NSH
Total/NA	Analysis	Moisture		1	25123	10/03/12 09:15	RS	TAL NSH

Client Sample ID: 1467 Cardinal

Date Collected: 09/25/12 15:00

Date Received: 10/02/12 08:30

Lab Sample ID: 490-8059-2

Matrix: Solid

Percent Solids: 82.4

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	5035			25026	10/02/12 16:53	ML	TAL NSH
Total/NA	Analysis	8260B		1	25524	10/04/12 18:06	FE	TAL NSH
Total/NA	Prep	3550C			25261	10/03/12 13:12	AK	TAL NSH
Total/NA	Analysis	8270D		1	25523	10/04/12 22:48	WS	TAL NSH
Total/NA	Analysis	Moisture		1	25123	10/03/12 09:15	RS	TAL NSH

Client Sample ID: 442 Elderberry

Date Collected: 09/26/12 15:30

Date Received: 10/02/12 08:30

Lab Sample ID: 490-8059-3

Matrix: Solid

Percent Solids: 81.1

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	5035			25026	10/02/12 16:53	ML	TAL NSH
Total/NA	Analysis	8260B		1	25524	10/04/12 18:37	FE	TAL NSH
Total/NA	Prep	5035			25021	10/02/12 16:47	ML	TAL NSH
Total/NA	Analysis	8260B		1	26734	10/09/12 21:09	FE	TAL NSH
Total/NA	Prep	3550C			25261	10/03/12 13:15	AK	TAL NSH
Total/NA	Analysis	8270D		1	25523	10/04/12 23:08	WS	TAL NSH
Total/NA	Analysis	Moisture		1	25123	10/03/12 09:15	RS	TAL NSH

Laboratory References:

TAL NSH = TestAmerica Nashville, 2960 Foster Creighton Drive, Nashville, TN 37204, TEL (615)726-0177

Method Summary

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Method	Method Description	Protocol	Laboratory
8260B	Volatile Organic Compounds (GC/MS)	SW846	TAL NSH
8270D	Semivolatile Organic Compounds (GC/MS)	SW846	TAL NSH
Moisture	Percent Moisture	EPA	TAL NSH

Protocol References:

EPA = US Environmental Protection Agency

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

TAL NSH = TestAmerica Nashville, 2960 Foster Creighton Drive, Nashville, TN 37204, TEL (615)726-0177

Certification Summary

Client: Environmental Enterprise Group
Project/Site: Laurel Bay Housing Project

TestAmerica Job ID: 490-8059-1

Laboratory: TestAmerica Nashville

All certifications held by this laboratory are listed. Not all certifications are applicable to this report.

Authority	Program	EPA Region	Certification ID	Expiration Date
	ACIL		393	10-30-12
A2LA	ISO/IEC 17025		0453.07	12-31-13
Alabama	State Program	4	41150	05-31-13
Alaska (UST)	State Program	10	UST-087	07-24-13
Arizona	State Program	9	AZ0473	05-05-13
Arkansas DEQ	State Program	6	88-0737	04-25-13
California	NELAC	9	1168CA	10-31-12
Canadian Assoc Lab Accred (CALA)	Canada		3744	03-08-14
Colorado	State Program	8	N/A	02-28-13
Connecticut	State Program	1	PH-0220	12-31-13
Florida	NELAC	4	E87358	06-30-13
Illinois	NELAC	5	200010	12-09-12
Iowa	State Program	7	131	05-01-14
Kansas	NELAC	7	E-10229	10-31-12
Kentucky	State Program	4	90038	12-31-12
Kentucky (UST)	State Program	4	19	09-15-13
Louisiana	NELAC	6	LA110014	12-31-12
Louisiana	NELAC	6	30613	06-30-13
Maryland	State Program	3	316	03-31-13
Massachusetts	State Program	1	M-TN032	06-30-13
Minnesota	NELAC	5	047-999-345	12-31-12
Mississippi	State Program	4	N/A	06-30-13
Montana (UST)	State Program	8	NA	01-01-15
Nevada	State Program	9	TN00032	07-31-13
New Hampshire	NELAC	1	2963	10-09-13
New Jersey	NELAC	2	TN965	06-30-13
New York	NELAC	2	11342	04-01-13
North Carolina DENR	State Program	4	387	12-31-12
North Dakota	State Program	8	R-146	06-30-13
Ohio VAP	State Program	5	CL0033	01-19-14
Oklahoma	State Program	6	9412	08-31-13
Oregon	NELAC	10	TN200001	04-30-13
Pennsylvania	NELAC	3	68-00585	06-30-13
Rhode Island	State Program	1	LAO00268	12-30-12
South Carolina	State Program	4	84009 (001)	02-28-13
South Carolina	State Program	4	84009 (002)	02-23-14
Tennessee	State Program	4	2008	02-23-14
Texas	NELAC	6	T104704077-09-TX	08-31-13
USDA	Federal		S-48469	11-02-13
Utah	NELAC	8	TAN	06-30-13
Virginia	NELAC	3	460152	06-14-13
Washington	State Program	10	C789	07-19-13
West Virginia DEP	State Program	3	219	02-28-13
Wisconsin	State Program	5	998020430	08-31-13
Wyoming (UST)	A2LA	8	453.07	12-31-13



COOLER RECEIPT FORM



490-8059 Chain of

Cooler Received/Opened On 10/02/2012 @ 0830

1. Tracking # 8768 (last 4 digits, FedEx)

Courier: FedEx IR Gun ID 17610176

2. Temperature of rep. sample or temp blank when opened: 1.3 Degrees Celsius

3. If Item #2 temperature is 0°C or less, was the representative sample or temp blank frozen? YES NO NA

4. Were custody seals on outside of cooler? YES...NO...NA

If yes, how many and where:

1 Front + Back

5. Were the seals intact, signed, and dated correctly? YES...NO...NA

6. Were custody papers inside cooler? YES...NO...NA

I certify that I opened the cooler and answered questions 1-6 (Initial) JH

7. Were custody seals on containers: YES NO and Intact YES...NO...NA

Were these signed and dated correctly?

YES...NO...NA

8. Packing mat'l used? Bubblewrap Plastic bag Peanuts Vermiculite Foam Insert Paper Other None

9. Cooling process: Ice Ice-pack Ice (direct contact) Dry ice Other None

10. Did all containers arrive in good condition (unbroken)? YES...NO...NA

11. Were all container labels complete (#, date, signed, pres., etc)? YES...NO...NA

12. Did all container labels and tags agree with custody papers? YES...NO...NA

13a. Were VOA vials received? YES...NO...NA

b. Was there any observable headspace present in any VOA vial?

YES...NO...NA - 8/15

14. Was there a Trip Blank in this cooler? YES...NO...NA If multiple coolers, sequence # 1/1

I certify that I unloaded the cooler and answered questions 7-14 (Initial) EF

15a. On pres'd bottles, did pH test strips suggest preservation reached the correct pH level? YES...NO...NA

b. Did the bottle labels indicate that the correct preservatives were used

YES...NO...NA

16. Was residual chlorine present?

YES...NO...NA

I certify that I checked for chlorine and pH as per SOP and answered questions 15-16 (Initial) EF

17. Were custody papers properly filled out (ink, signed, etc)? YES...NO...NA

18. Did you sign the custody papers in the appropriate place? YES...NO...NA

19. Were correct containers used for the analysis requested? YES...NO...NA

20. Was sufficient amount of sample sent in each container? YES...NO...NA

I certify that I entered this project into LIMS and answered questions 17-20 (Initial) EF

I certify that I attached a label with the unique LIMS number to each container (Initial) EF

21. Were there Non-Conformance issues at login? YES...NO Was a PIPE generated? YES...NO...

10/15/2012

Login Sample Receipt Checklist

Client: Environmental Enterprise Group

Job Number: 490-8059-1

Login Number: 8059

List Source: TestAmerica Nashville

List Number: 1

Creator: Ford, Easton

Question	Answer	Comment
Radioactivity wasn't checked or is \leq background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	N/A	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

ATTACHMENT A



NON-HAZARDOUS MANIFEST

NON-HAZARDOUS MANIFEST		1. Generator's US EPA ID No.		Manifest Doc No.		2. Page 1 of 1		
3. Generator's Mailing Address: MCAS, BEAUFORT LAUREL BAY HOUSING BEAUFORT, SC 29907		4. Generator's Phone 843-228-6461		Generator's Site Address (If different than mailing):		A. Manifest Number WMNA 00316828		
5. Transporter 1 Company Name EEG, INC.		6. US EPA ID Number		C. State Transporter's ID		D. Transporter's Phone 843-879-0411		
7. Transporter 2 Company Name		8. US EPA ID Number		E. State Transporter's ID		F. Transporter's Phone		
9. Designated Facility Name and Site Address HICKORY HILL LANDFILL 2621 LOW COUNTRY ROAD RIDGELAND, SC 29936		10. US EPA ID Number		G. State Facility ID		H. State Facility Phone 843-987-4643		
11. Description of Waste Materials		12. Containers		13. Total Quantity	14. Unit Wt./Vol.	I. Misc. Comments		
		No.	Type					
a. HEATING OIL TANKS FILLED WITH SAND WM Profile # 102655SC								
b. WM Profile #								
c. WM Profile #								
d. WM Profile #								
J. Additional Descriptions for Materials Listed Above		K. Disposal Location						
		Cell		Level				
		Grid						
15. Special Handling Instructions and Additional Information UST'S FROM: 1) 1415 ALBANY 2) 1355 CARDINAL 3) 1425 CARDINAL 4) 1467 CARDINAL 5) 442 ELDERBERRY								
Purchase Order #		EMERGENCY CONTACT / PHONE NO.:						
16. GENERATOR'S CERTIFICATE: I hereby certify that the above-described materials are not hazardous wastes as defined by CFR Part 261 or any applicable state law, have been fully and accurately described, classified and packaged and are in proper condition for transportation according to applicable regulations.								
Printed Name		Signature "On behalf of"				Month	Day	Year
17. Transporter 1 Acknowledgement of Receipt of Materials		Printed Name PRATHAN				Signature [Signature] Month 10 Day 1 Year 12		
18. Transporter 2 Acknowledgement of Receipt of Materials		Printed Name JAMES BALDWIN				Signature [Signature] Month 10 Day 1 Year 12		
19. Certificate of Final Treatment/Disposal I certify, on behalf of the above listed treatment facility, that to the best of my knowledge, the above-described waste was managed in compliance with all applicable laws, regulations, permits and licenses on the dates listed above.								
20. Facility Owner or Operator: Certification of receipt of non-hazardous materials covered by this manifest.								
Printed Name		Signature				Month	Day	Year
Toni Coyle		Toni Coyle				10	1	12

White- TREATMENT, STORAGE, DISPOSAL FACILITY COPY

Blue- GENERATOR #2 COPY

Yellow- GENERATOR #1 COPY

Pink- FACILITY USE ONLY

Gold- TRANSPORTER #1 COPY

Appendix C
Laboratory Analytical Report - Groundwater

Volatile Organic Compounds by GC/MS

Client: AECOM - Resolution Consultants	Laboratory ID: QB06006-015
Description: BEALB1467TW01WG20150205	Matrix: Aqueous
Date Sampled: 02/05/2015 1500	
Date Received: 02/06/2015	

Run	Prep Method	Analytical Method	Dilution	Analysis Date	Analyst	Prep Date	Batch
1	5030B	8260B	1	02/12/2015 1555	EH1		67618

Parameter	CAS Number	Analytical Method	Result	Q	LOQ	LOD	DL	Units	Run
Benzene	71-43-2	8260B	0.40	U	1.0	0.40	0.13	ug/L	1
Ethylbenzene	100-41-4	8260B	0.50	U	1.0	0.50	0.33	ug/L	1
Naphthalene	91-20-3	8260B	0.20	U	1.0	0.20	0.40	ug/L	1
Toluene	108-88-3	8260B	0.50	U	1.0	0.50	0.33	ug/L	1
Xylenes (total)	1330-20-7	8260B	0.40	U	1.0	0.40	0.33	ug/L	1

Surrogate	Q	Run 1 % Recovery	Acceptance Limits
1,2-Dichloroethane-d4		93	70-120
Bromofluorobenzene		99	75-120
Toluene-d8		97	85-120
Dibromofluoromethane		97	85-115

PQL = Practical quantitation limit B = Detected in the method blank E = Quantitation of compound exceeded the calibration range H = Out of holding time Q = Surrogate failure
 ND = Not detected at or above the MDL J = Estimated result < PQL and ≥ MDL P = The RPD between two GC columns exceeds 40% N = Recovery is out of criteria L = LCS/LCSD failure
 Where applicable, all soil sample analysis are reported on a dry weight basis unless flagged with a "W" S = MS/MSD failure

Shealy Environmental Services, Inc.
 106 Vantage Point Drive West Columbia, SC 29172 (803) 791-9700 Fax (803) 791-9111 www.shealylab.com

Level 1 Report v2.1

Semivolatile Organic Compounds by GC/MS (SIM)

Client: AECOM - Resolution Consultants	Laboratory ID: QB06006-015
Description: BEALB1467TW01WG20150205	Matrix: Aqueous
Date Sampled: 02/05/2015 1500	
Date Received: 02/06/2015	

Run	Prep Method	Analytical Method	Dilution	Analysis Date	Analyst	Prep Date	Batch
2	3520C	8270D (SIM)	50	02/19/2015 1623	RBH	02/10/2015 1512	67395

Parameter	CAS Number	Analytical Method	Result	Q	LOQ	LOD	DL	Units	Run
Benzo(a)anthracene	56-55-3	8270D (SIM)	2.0	U	10	2.0	0.95	ug/L	2
Benzo(b)fluoranthene	205-99-2	8270D (SIM)	2.0	U	10	2.0	0.95	ug/L	2
Benzo(k)fluoranthene	207-08-9	8270D (SIM)	2.0	U	10	2.0	1.2	ug/L	2
Chrysene	218-01-9	8270D (SIM)	2.0	U	10	2.0	1.1	ug/L	2
Dibenzo(a,h)anthracene	53-70-3	8270D (SIM)	4.0	U	10	4.0	2.0	ug/L	2

Surrogate	Q	Run 2 % Recovery	Acceptance Limits
2-Methylnaphthalene-d10		67	15-139
Fluoranthene-d10		52	23-154

PQL = Practical quantitation limit B = Detected in the method blank E = Quantitation of compound exceeded the calibration range H = Out of holding time Q = Surrogate failure
 ND = Not detected at or above the MDL J = Estimated result < PQL and ≥ MDL P = The RPD between two GC columns exceeds 40% N = Recovery is out of criteria L = LCS/LCSD failure
 Where applicable, all soil sample analysis are reported on a dry weight basis unless flagged with a "W" S = MS/MSD failure

Appendix D

Regulatory Correspondence

April 1, 2014

Commanding Officer
Attention: NREAO Mr. William A. Drawdy
United State Marine Corps Air Station
Post Office Box 55001
Beaufort, SC 29904-5001

RE: IGWA
Laurel Bay Underground Storage Tank Assessment Reports for:
See attached sheet

Dear Mr. Drawdy,


The South Carolina Department of Health and Environmental Control (the Department) received the above referenced Underground Storage Tank Assessment Reports for the addresses listed above. The regulatory authority for the investigation and cleanup of releases from these tank systems is the South Carolina Pollution Control Act (S.C. Code Ann. §48-1-10 et seq., as amended).

The Department has reviewed the referenced assessment reports. The submitted analytical results indicate that petroleum constituents are above established Risk-Based Screening Levels and additional investigation is warranted. Specifically, the Department requests that a groundwater sampling proposal be generated to determine if there has been an impact to groundwater at this site.

Please note that the Department's decision is based on information provided by the Marine Corps Air Station (MCAS) to date. Any information found to be contradictory to this decision may require additional action. Furthermore, the Department retains the right to request further investigation if deemed necessary.

If you have any questions, please contact me at kriegkm@gmail.com or 803-898-0255.

Sincerely,



Kent Krieg
Department of Defense Corrective Action Section
Bureau of Land and Waste Management
South Carolina Department of Health and Environmental Control

Cc: Russell Berry (via email)
Craig Ehde (via email)

Attachment to: Krieg to Drawdy
Subject: IGWA
Dated 4/1/2014

Laurel Bay Underground Storage Tank Assessment Reports for: (25 addresses/26 tanks)

1187 Bobwhite	1456 Cardinal
1431 Dove	1457 Cardinal
1433 Dove	1461 Cardinal
1435 Dove Tank #1	1465 Cardinal
1435 Dove Tank #2	1467 Cardinal
1437 Dove	1469 Cardinal
1439 Dove	1470 Cardinal
1441 Dove	1471 Cardinal
1447 Dove	1473 Cardinal
1449 Dove	1477 Cardinal
1451 Dove	1478 Cardinal
1452 Cardinal	1479 Cardinal
1454 Cardinal	1485 Cardinal



May 5, 2015

W. Marshall Taylor Jr., Acting Director

Promoting and protecting the health of the public and the environment

Commanding Officer
Attention: NREAO Mr. William A. Drawdy
United State Marine Corps Air Station
Post Office Box 55001
Beaufort, SC 29904-5001

RE: Correction - Recommendation Concurrence
Draft Final Initial Groundwater Investigation Report
Dated April 2015

Dear Mr. Drawdy,

The South Carolina Department of Health and Environmental Control (the Department) received groundwater data in the above referenced Groundwater Investigation Report for the addresses attached. The regulatory authority for the investigation and cleanup of releases from these tank systems is the South Carolina Pollution Control Act (S.C. Code Ann. §48-1-10 et seq., as amended).

Per the Department's request, groundwater samples were collected from the attached referenced addresses. The Department reviewed the groundwater data and previous investigations and it agrees with the conclusions and recommendations included in the document. To further assess the impact to groundwater, permanent wells should be installed at the 3 stated addresses. For the remaining 23 addresses, there is no indication of contamination on the property and therefore no further investigation is required at this time. *Note the correction to the attachment, properly referencing 1431 Dove and 1435 Dove Tank 1 and Tank 2 in the Permanent Monitoring Well Investigation recommendation section.*

Please note that the Department's decision is based on information provided by the Marine Corps Air Station (MCAS) to date. Any information found to be contradictory to this decision may require additional action. Furthermore, the Department retains the right to request further investigation if deemed necessary.

If you have any questions, please contact me at kriegkm@dhec.sc.gov or 803-898-0255.

Sincerely,

Kent Krieg
Department of Defense Corrective Action Section
Bureau of Land and Waste Management
South Carolina Department of Health and Environmental Control

Attachment: Specific Property Recommendations

Cc: Russell Berry (via email)
Craig Ehde (via email)
Bryan Beck (via email)



W. Marshall Taylor Jr., Acting Director

Promoting and protecting the health of the public and the environment

Attachment to: Krieg to Drawdy
Subject: Draft Final Initial Groundwater Investigation Report - April 2015
Specific Property Recommendations
Dated 5/5/2015

Draft Final Initial Groundwater Investigation Report for: (26 addresses/28 tanks)

Permanent Monitoring Well Investigation recommendation (3 addresses/4 tanks):	
1431 Dove	1435 Dove Tank 2
1435 Dove Tank 1	1452 Cardinal
No Further Action recommendation (23 addresses/24 tanks):	
1187 Bobwhite	1463 Cardinal
1433 Dove	1465 Cardinal
1437 Dove	1467 Cardinal
1439 Dove	1469 Cardinal
1441 Dove	1470 Cardinal
1447 Dove	1473 Cardinal
1449 Dove	1471 Cardinal
1451 Dove	1477 Cardinal
1454 Cardinal	1478 Cardinal
1456 Cardinal	1479 Cardinal Tank 1
1457 Cardinal	1479 Cardinal Tank 2
1461 Cardinal	1485 Cardinal