

**SUMMARY REPORT  
291 ASH STREET (FORMERLY 328 ASH STREET)  
LAUREL BAY MILITARY HOUSING AREA  
MARINE CORPS AIR STATION BEAUFORT  
BEAUFORT, SC**

**Revision: 0  
Prepared for:**

**Department of the Navy  
Naval Facilities Engineering Command, Mid-Atlantic  
9324 Virginia Avenue  
Norfolk, Virginia 23511-3095**

**and**



**Naval Facilities Engineering Command Atlantic  
9324 Virginia Avenue  
Norfolk, Virginia 23511-3095**

**JUNE 2021**

**SUMMARY REPORT  
291 ASH STREET (FORMERLY 328 ASH STREET)  
LAUREL BAY MILITARY HOUSING AREA  
MARINE CORPS AIR STATION BEAUFORT  
BEAUFORT, SC**

**Revision: 0  
Prepared for:**

**Department of the Navy  
Naval Facilities Engineering Command, Mid- Atlantic  
9324 Virginia Avenue  
Norfolk, Virginia 23511-3095**

**and**



**Naval Facilities Engineering Command Atlantic**

**9324 Virginia Avenue  
Norfolk, Virginia 23511-3095**

**Prepared by:**

**CDM - AECOM**  
**Multimedia Joint Venture**

**CDM - AECOM Multimedia Joint Venture  
10560 Arrowhead Drive, Suite 500  
Fairfax, Virginia 22030**

**Contract Number: N62470-14-D-9016  
CTO WE52  
JUNE 2021**

---

## Table of Contents

<b>1.0</b>	<b>INTRODUCTION .....</b>	<b>1</b>
1.1	BACKGROUND INFORMATION.....	1
1.2	UST REMOVAL AND ASSESSMENT PROCESS.....	2
<b>2.0</b>	<b>SAMPLING ACTIVITIES AND RESULTS .....</b>	<b>3</b>
2.1	UST REMOVAL AND SOIL SAMPLING .....	3
2.2	SOIL ANALYTICAL RESULTS.....	4
2.3	GROUNDWATER SAMPLING.....	4
2.4	GROUNDWATER ANALYTICAL RESULTS .....	5
<b>3.0</b>	<b>PROPERTY STATUS.....</b>	<b>5</b>
<b>4.0</b>	<b>REFERENCES .....</b>	<b>5</b>

## Tables

Table 1	Laboratory Analytical Results - Soil
Table 2	Laboratory Analytical Results - Groundwater

## Appendices

Appendix A	Multi-Media Selection Process for LBMH
Appendix B	UST Assessment Report
Appendix C	Laboratory Analytical Report - Groundwater
Appendix D	Regulatory Correspondence

---

### List of Acronyms

bgs	below ground surface
BTEX	benzene, toluene, ethylbenzene, and xylenes
CTO	Contract Task Order
COPC	constituents of potential concern
ft	feet
IDIQ	Indefinite Delivery, Indefinite Quantity
IGWA	Initial Groundwater Assessment
JV	Joint Venture
LBMH	Laurel Bay Military Housing
MCAS	Marine Corps Air Station
NAVFAC Mid-Lant	Naval Facilities Engineering Command Mid-Atlantic
NFA	No Further Action
PAH	polynuclear aromatic hydrocarbon
QAPP	Quality Assurance Program Plan
RBSL	risk-based screening level
SCDHEC	South Carolina Department of Health and Environmental Control
Site	LBMH area at MCAS Beaufort, South Carolina
UST	underground storage tank
VISL	vapor intrusion screening level

## **1.0 INTRODUCTION**

The CDM - AECOM Multimedia Joint Venture (JV) was contracted by the Naval Facilities Engineering Command, Mid-Atlantic (NAVFAC Mid-Lant) to provide reporting services for the heating oil underground storage tanks (USTs) located in Laurel Bay Military Housing (LBMH) area at the Marine Corps Air Station (MCAS) Beaufort, South Carolina (Site). This work has been awarded under Contract Task Order (CTO) WE52 of the Indefinite Delivery, Indefinite Quantity (IDIQ) Multimedia Environmental Compliance Contract (Contract No. N62470-14-D-9016).

As of January 2014, the LBMH addresses were re-numbered to comply with the E-911 emergency response addressing system; however, in order to remain consistent with historical sampling and reporting for LBMH area, the residences will continue to be referenced with their original address numbers in sample nomenclature and reporting documents.

This report summarizes the results the environmental investigation activities associated with the storage of home heating oil and the potential release of petroleum constituents at the referenced property. Based on the results of the investigation, a No Further Action (NFA) determination has been made by the South Carolina Department of Health and Environmental Control (SCDHEC) for 291 Ash Street (Formerly 328 Ash Street). This NFA determination indicates that there are no unacceptable risks to human health or the environment for the petroleum constituents associated with the home heating oil USTs. The following information is included in this report:

- Background information;
- Sampling activities and results; and
- A determination of the property status.

### **1.1 Background Information**

The LBMH area is located approximately 3.5 miles west of MCAS Beaufort. The area is approximately 970 acres in size and serves as an enlisted and officer family housing area. The area is configured with single family and duplex residential structures, and includes recreation, open space, and community facilities. The community includes approximately 1,300 housing units, including legacy Capehart style homes and newer duplex style homes. The housing area

is bordered on the west by salt marshes and the Broad River, and to the north, east and south by uplands. Forested areas lie along the northern and northeastern borders.

Capehart style homes within the LBMH area were formerly heated using heating oil stored in USTs at each residence. There were 1,100 Capehart style housing units in the LBMH area. The newer duplex homes within the LBMH area never utilized heating oil tanks. Heating oil has not been used at Laurel Bay since the mid-1980s. As was the accepted practice at the time, USTs were drained, filled with dirt, capped, and left in place when they were removed from service. Residential USTs are not regulated in the State of South Carolina (i.e., there are no federal or state laws governing installation, management, or removal).

In 2007, MCAS Beaufort began a voluntary program to remove the unregulated, residential USTs and conduct sampling activities to determine if, and to what extent, petroleum constituents may have impacted the surrounding environment. MCAS Beaufort coordinated with SCDHEC to develop removal procedures that were consistent with procedural requirements for regulated USTs. All tank removal activities and follow-on actions are conducted in coordination with SCDHEC. To date, all known USTs have been removed from all residential properties within the LBMH area.

## **1.2 UST Removal and Assessment Process**

During the UST removal process, a soil sample was collected from beneath the UST excavations (approximately 4 to 6 feet [ft] below ground surface [bgs]) and analyzed for a predetermined list of constituents of potential concern (COPCs) associated with the petroleum compounds found in home heating oil. These COPCs, derived from the *Quality Assurance Program Plan (QAPP) for the Underground Storage Tank Management Division, Revision 3.1* (SCDHEC, 2016) and the *Underground Storage Tank Assessment Instructions for Permanent Closure and Change-In-Service*, (SCDHEC, 2018), are as follows:

- benzene, toluene, ethylbenzene, and xylenes (BTEX),
- naphthalene, and
- five select polynuclear aromatic hydrocarbon (PAHs): benzo(a)anthracene, benzo(b)fluoranthene, benzo(k)fluoranthene, chrysene and dibenz(a,h)anthracene.

Soil sample results were submitted by MCAS Beaufort to SCDHEC utilizing SCDHEC's UST Assessment Report form. In accordance with SCDHEC's *QAPP for the UST Management*

*Division* (SCDHEC, 2016), the soil screening levels consists of SCDHEC risk-based screening levels (RBSLs). It should be noted that the RBSLs for select PAHs were revised in Revision 2.0 of the QAPP (SCDHEC, 2013) and were revised again in Revision 3.0 (SCDHEC, 2015). The screening levels used for evaluation at each site were those levels that were in effect at the time of reporting and review by SCDHEC.

The results of the soil sampling at each former UST location were used to determine if a potential for groundwater contamination exists (i.e., soil results greater than RBSLs) and subsequently to select properties for follow-up initial groundwater assessment (IGWA) sampling. The results of the IGWA sampling (if necessary) are used to determine the presence or absence of the aforementioned COPCs in groundwater and identify whether former UST locations will require additional delineation of COPCs in groundwater. In order to delineate the extent of impact to groundwater, permanent wells are installed and a sampling program is established for those former UST locations where IGWA sampling has indicated the presence of COPCs in excess of the SCDHEC RBSLs for groundwater. Groundwater analytical results are also compared to the site specific groundwater vapor intrusion screening levels (VISLs) to evaluate the potential for vapor intrusion and the necessity for an investigation associated with this media. A multi-media investigation selection process tree, applicable to the LBMH UST investigations, is presented as Appendix A.

## **2.0 SAMPLING ACTIVITIES AND RESULTS**

The following section presents the sampling activities and associated results for 291 Ash Street (Formerly 328 Ash Street). Details regarding the soil investigation at this site are provided in the *SCDHEC UST Assessment Report – 328 Ash Street* (MCAS Beaufort, 2012). The UST Assessment Report is provided in Appendix B. Details regarding the IGWA sampling activities at this site are provided in the *Initial Groundwater Investigation Report – February and March 2017* (Resolution Consultants, 2017). The laboratory report that includes the pertinent IGWA analytical results for this site is presented in Appendix C.

### **2.1 UST Removal and Soil Sampling**

On November 29, 2011, two 280 gallon heating oil USTs were removed at 291 Ash Street (Formerly 328 Ash Street). Tank 1 was removed from the front landscaped bed area adjacent to the driveway. Tank 2 was removed from underneath the front concrete walk adjacent to the driveway. The former UST locations are indicated in Figures 2 and 3 of the UST Assessment

Report (Appendix B). The USTs were removed, cleaned, and shipped offsite for recycling. There was no visual evidence (i.e., staining or sheen) of petroleum impact at the time of the UST removal. According to the UST Assessment Report (Appendix B), the depths to the bases of the USTs were 5'6" (Tank 1) and 4'0" (Tank 2) bgs and a single soil sample was collected for each at that depth. The samples were collected from the fill port side of the former USTs to represent a worst case scenario.

Following UST removal, a soil sample was collected from the base of each excavation and shipped to an offsite laboratory for analysis of the petroleum COPCs. Sampling was performed in accordance with applicable South Carolina regulation R.61-92, Part 280 (SCDHEC, 2017) and assessment guidelines.

## **2.2 Soil Analytical Results**

A summary of the laboratory analytical results and SCDHEC RBSLs is presented in Table 1. A copy of the laboratory analytical data report is included in the UST Assessment Report presented in Appendix B. The laboratory analytical data report includes the soil results for the additional PAHs that were analyzed, but do not have associated RBSLs.

The soil sample results were submitted by MCAS Beaufort to SCDHEC utilizing SCDHEC's UST Assessment Report form (Appendix B). The results of the soil sampling at the former UST locations (Tanks 1 and 2) were used by MCAS Beaufort, in consultation with SCDHEC, to determine a path forward (i.e., additional sampling or NFA) for the property. The soil results collected from 91 Ash Street (Formerly 328 Ash Street) during the removal of Tank 1 were less than the SCDHEC RBSLs, which indicated the subsurface was not impacted by COPCs associated with the former UST at concentrations that presented a potential risk to human health and the environment. The soil results collected from 291 Ash Street (Formerly 328 Ash Street) during the removal of Tank 2 were greater than the SCDHEC RBSLs, which indicated further investigation was required. In a letter dated August 24, 2016, SCDHEC requested an IGWA be conducted at the former UST location (Tank 2) at 291 Ash Street (Formerly 328 Ash Street) to determine if the groundwater was impacted by petroleum COPCs. SCDHEC's request letter is provided in Appendix D.

## **2.3 Groundwater Sampling**

On March 1, 2017, a temporary monitoring well was installed at 291 Ash Street (Formerly 328 Ash Street), in accordance with the South Carolina Well Standards and Regulations (R.61-71.H-



I, updated June 24, 2016). In order to provide data that can be used to determine whether COPCs are migrating to underlying groundwater, the monitoring well was placed in the same general location as the former heating oil UST (Tank 2). The former UST locations are indicated in Figures 2 and 3 of the UST Assessment Report (Appendix B). Further details are provided in the *Initial Groundwater Investigation Report – February and March 2017* (Resolution Consultants, 2017).

The sampling strategy for this phase of the investigation required a one-time sampling event of the temporarily installed monitoring well. Following well installation and development, groundwater samples were collected using low-flow methods and shipped to an offsite laboratory for analysis of the petroleum COPCs. Upon completion of groundwater sampling, the temporary well was abandoned in accordance with the South Carolina Well Standards and Regulations R.61-71 (SCDHEC, 2016). Field forms are provided in the *Initial Groundwater Investigation Report – February and March 2017* (Resolution Consultants, 2017).

## **2.4 Groundwater Analytical Results**

A summary of the laboratory analytical results and SCDHEC RBSLs is presented in Table 2. A copy of the laboratory analytical data report is included in Appendix C.

The groundwater results collected from 291 Ash Street (Formerly 328 Ash Street) were less than the SCDHEC RBSLs and the site specific groundwater VISLs (Table 2), which indicated that the groundwater was not impacted by COPCs associated with the former UST at concentrations that present a potential risk to human health and the environment.

## **3.0 PROPERTY STATUS**

Based on the analytical results for groundwater, SCDHEC made the determination that NFA was required for 291 Ash Street (Formerly 328 Ash Street). This NFA determination was obtained in a letter dated July 27, 2017. SCDHEC's NFA letter is provided in Appendix D.

## **4.0 REFERENCES**

Marine Corps Air Station Beaufort, 2012. *South Carolina Department of Health and Environmental Control (SCDHEC) Underground Storage Tank Assessment Report – 328 Ash Street, Laurel Bay Military Housing Area*, February 2012.

Resolution Consultants, 2017. *Initial Groundwater Investigation Report – February and March 2017 for Laurel Bay Military Housing Area, Multiple Properties, Laurel Bay Military Housing Area, Marine Corps Air Station Beaufort, Beaufort, South Carolina*, June 2017.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2013. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 2.0*, April 2013.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2015. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.0*, May 2015.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2016. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.1*, February 2016.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2017. *R.61-92, Part 280, Underground Storage Tank Control Regulations*, March 2017.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2018. *Underground Storage Tank Assessment Instructions for Permanent Closure and Change-In-Service*, March 2018.

South Carolina Department of Health and Environmental Control Bureau of Water, 2016. *R.61-71, Well Standards*, June 2016.

## Tables

**Table 1**  
**Laboratory Analytical Results - Soil**  
**291 Ash Street (Formerly 328 Ash Street)**  
**Laurel Bay Military Housing Area**  
**Marine Corps Air Station Beaufort**  
**Beaufort, South Carolina**

Constituent	SCDHEC RBSLs <sup>(1)</sup>	Results Samples Collected 11/29/11	
		328 Ash-1	328 Ash-2
Volatile Organic Compounds Analyzed by EPA Method 8260B (mg/kg)			
Benzene	0.003	ND	ND
Ethylbenzene	1.15	ND	0.00119
Naphthalene	0.036	ND	0.0429
Toluene	0.627	ND	ND
Xylenes, Total	13.01	ND	ND
Semivolatile Organic Compounds Analyzed by EPA Method 8270D (mg/kg)			
Benzo(a)anthracene	0.66	0.123	ND
Benzo(b)fluoranthene	0.66	ND	ND
Benzo(k)fluoranthene	0.66	ND	ND
Chrysene	0.66	0.101	ND
Dibenz(a,h)anthracene	0.66	ND	ND

**Notes:**

<sup>(1)</sup> South Carolina Risk-Based Screening Levels from the Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.0 and 3.1 (SCDHEC, May 2015 and SCDHEC, February 2016) and the Underground Storage Tank Assessment Guidelines (SCDHEC, February 2006).

Bold font indicates the analyte was detected.

Bold font and shading indicates the concentration exceeds the SCDHEC RBSL.

EPA - United States Environmental Protection Agency

mg/kg - milligrams per kilogram

ND - not detected at the reporting limit (or method detection limit if shown on the laboratory report). The soil laboratory report is provided in Appendix B.

RBSL - Risk-Based Screening Level

SCDHEC - South Carolina Department Of Health and Environmental Control

**Table 2**  
**Laboratory Analytical Results - Groundwater**  
**291 Ash Street (Formerly 328 Ash Street)**  
**Laurel Bay Military Housing Area**  
**Marine Corps Air Station Beaufort**  
**Beaufort, South Carolina**

Constituent	SCDHEC RBSLs <sup>(1)</sup>	Site-Specific Groundwater VISLs (µg/L) <sup>(2)</sup>	Results Sample Collected 03/02/17
<b>Volatile Organic Compounds Analyzed by EPA Method 8260B (µg/L)</b>			
Benzene	5	16.24	ND
Ethylbenzene	700	45.95	ND
Naphthalene	25	29.33	<b>2.6</b>
Toluene	1000	105,445	ND
Xylenes, Total	10,000	2,133	ND
<b>Semivolatile Organic Compounds Analyzed by EPA Method 8270D (µg/L)</b>			
Benzo(a)anthracene	10	NA	ND
Benzo(b)fluoranthene	10	NA	ND
Benzo(k)fluoranthene	10	NA	ND
Chrysene	10	NA	ND
Dibenz(a,h)anthracene	10	NA	ND

**Notes:**

<sup>(1)</sup> South Carolina Risk-Based Screening Levels from the Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.1 (SCDHEC, February 2016).

<sup>(2)</sup> Site-specific groundwater VISLs were calculated using the EPA JE Model Spreadsheets (Version 3.1, February 2004) and conservative modeling inputs representative of a small single-story house with an 8 foot ceiling. Site-specific groundwater VISLs were developed based on a target risk level of  $1 \times 10^{-6}$ , a target hazard quotient of 1 (per target organ), and a default residential exposure scenario, assuming exposure for 24 hours/day, 350 days/year, for 26 years. Modeling was performed for a range of depths to groundwater for application as appropriate in different areas of the Laurel Bay Military Housing Area. The most conservative levels are presented for comparison. Refer to Appendix H of the Uniform Federal Policy Sampling Analysis and Sampling Plan for Vapor Media, Revision 4 (Resolution Consultants, April 2017) for additional information.

Bold font indicates the analyte was detected.

Bold font and shading indicates the concentration exceeds the SCDHEC RBSL and/or the Site-Specific Groundwater VISL.

EPA - United States Environmental Protection Agency

JE - Johnson & Ettinger

NA - Not Applicable

ND - not detected at the reporting limit (or method detection limit if shown on the laboratory report). The groundwater laboratory report is provided in Appendix C.

RBSL - Risk-Based Screening Level

SCDHEC - South Carolina Department Of Health and Environmental Control

µg/L - micrograms per liter

VISL - Vapor Intrusion Screening Level

**Appendix A**  
**Multi-Media Selection Process for LBMH**



Appendix A - Multi-Media Selection Process for LBMH

**Appendix B**  
**UST Assessment Report**



rec'd 2/16/12

Attachment 1

South Carolina Department of Health and Environmental Control (SCDHEC)  
**Underground Storage Tank (UST) Assessment Report**

Date Received

State Use Only

Submit Completed Form To:  
UST Program  
SCDHEC  
2600 Bull Street  
Columbia, South Carolina 29201  
Telephone (803) 896-7957

**I. OWNERSHIP OF UST (S)**

MCAS Beaufort, Commanding Officer Attn: NREAO (Craig Ehde)		
Owner Name (Corporation, Individual, Public Agency, Other)		
P.O. Box 55001		
Mailing Address		
Beaufort,	South Carolina	29904-5001
City	State	Zip Code
843	228-7317	Craig Ehde
Area Code	Telephone Number	Contact Person

**II. SITE IDENTIFICATION AND LOCATION**

Permit I.D. #	
Laurel Bay Military Housing Area, Marine Corps Air Station, Beaufort, SC	
Facility Name or Company Site Identifier	
328 Ash Street, Laurel Bay Military Housing Area	
Street Address or State Road (as applicable)	
Beaufort,	Beaufort
City	County

Attachment 2

### III. INSURANCE INFORMATION

#### Insurance Statement

The petroleum release reported to DHEC on \_\_\_\_\_ at Permit ID Number \_\_\_\_\_ may qualify to receive state monies to pay for appropriate site rehabilitation activities. Before participation is allowed in the State Clean-up fund, written confirmation of the existence or non-existence of an environmental insurance policy is required. **This section must be completed.**

Is there now, or has there ever been an insurance policy or other financial mechanism that covers this UST release? **YES** \_\_\_\_ **NO** \_\_\_\_ (check one)

If you answered **YES** to the above question, please complete the following information:

My policy provider is: \_\_\_\_\_  
The policy deductible is: \_\_\_\_\_  
The policy limit is: \_\_\_\_\_

If you have this type of insurance, please include a copy of the policy with this report.

### IV. REQUEST FOR SUPERB FUNDING

I **DO** / **DO NOT** wish to participate in the SUPERB Program. (Circle one.)

### V. CERTIFICATION (To be signed by the UST owner)

**I certify that I have personally examined and am familiar with the information submitted in this and all attached documents; and that based on my inquiry of those individuals responsible for obtaining this information, I believe that the submitted information is true, accurate, and complete.**

\_\_\_\_\_  
Name (Type or print.)

\_\_\_\_\_  
Signature

#### To be completed by Notary Public:

Sworn before me this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_

\_\_\_\_\_  
(Name)

Notary Public for the state of \_\_\_\_\_.  
*Please affix State seal if you are commissioned outside South Carolina*

## VI. UST INFORMATION

- A. Product...(ex. Gas, Kerosene).....
- B. Capacity..(ex. 1k, 2k).....
- C. Age.....
- D. Construction Material..(ex. Steel, FRP).....
- E. Month/Year of Last Use.....
- F. Depth (ft.) To Base of Tank.....
- G. Spill Prevention Equipment Y/N.....
- H. Overfill Prevention Equipment Y/N.....
- I. Method of Closure Removed/Filled.....
- J. Date Tanks Removed/Filled.....
- K. Visible Corrosion or Pitting Y/N.....
- L. Visible Holes Y/N.....

328Ash-1	328Ash-2	
Heating oil	Heating oil	
280 gal	280 gal	
Late 1950s	Late 1950s	
Steel	Steel	
Mid 80s	Mid 80s	
5'6"	4'	
No	No	
No	No	
Removed	Removed	
11/29/2011	11/29/2011	
Yes	Yes	
Yes	Yes	

- M. Method of disposal for any USTs removed from the ground (attach disposal manifests)  
UST 328Ash-1 was removed from the ground, cleaned and recycled.  
UST 328Ash-2 was removed from the ground, and disposed  
at a Subtitle "D" landfill. See Attachment "A".
- N. Method of disposal for any liquid petroleum, sludges, or wastewaters removed from the USTs (attach disposal manifests)  
Contaminated water was pumped from UST 328Ash-1 and disposed by MCAS.  
UST 328Ash-2 was previously filled with sand by others.
- O. If any corrosion, pitting, or holes were observed, describe the location and extent for each UST  
Corrosion, pitting and holes were found in both tanks.

## VII. PIPING INFORMATION

A. Construction Material..(ex. Steel, FRP).....

B. Distance from UST to Dispenser.....

C. Number of Dispensers.....

D. Type of System Pressure or Suction.....

E. Was Piping Removed from the Ground? Y/N

F. Visible Corrosion or Pitting Y/N.....

G. Visible Holes Y/N.....

H. Age.....

I. If any corrosion, pitting, or holes were observed, describe the location and extent for each piping run.

Steel vent piping for both tanks were corroded and pitted. All  
copper supply and return piping were sound.

328Ash-1	328Ash-2	
Steel & Copper	Steel & Copper	
N/A	N/A	
N/A	N/A	
Suction	Suction	
No	No	
Yes	Yes	
No	No	
Late 1950s	Late 1950s	

## VIII. BRIEF SITE DESCRIPTION AND HISTORY

The USTs at the residences are constructed of single wall steel and formerly contained fuel oil for heating. These USTs were installed in the late 1950s and last used in the mid 1980s.

## IX. SITE CONDITIONS

	Yes	No	Unk
<p>A. Were any petroleum-stained or contaminated soils found in the UST excavation, soil borings, trenches, or monitoring wells?</p> <p>If yes, indicate depth and location on the site map.</p>		X	
<p>B. Were any petroleum odors detected in the excavation, soil borings, trenches, or monitoring wells?</p> <p>If yes, indicate location on site map and describe the odor (strong, mild, etc.)</p>		X	
<p>C. Was water present in the UST excavation, soil borings, or trenches?</p> <p style="padding-left: 40px;">*Small amount of water in 328Ash-1 excavation came from a fresh water line temporarily separated for tank removal.</p> <p>If yes, how far below land surface (indicate location and depth)?</p>		*X	
<p>D. Did contaminated soils remain stockpiled on site after closure?</p> <p>If yes, indicate the stockpile location on the site map.</p> <p>Name of DHEC representative authorizing soil removal:</p>		X	
<p>E. Was a petroleum sheen or free product detected on any excavation or boring waters?</p> <p>If yes, indicate location and thickness.</p>		X	

## X. SAMPLE INFORMATION

A. SCDHEC Lab Certification Number 84009

B.

Sample #	Location	Sample Type (Soil/Water)	Soil Type (Sand/Clay)	Depth*	Date/Time of Collection	Collected by	OVA #
328Ash-1	Excav at fill end	Soil	Sandy	5'6"	11/29/11 1345 hrs	P. Shaw	
328Ash-2	Excav at fill end	Soil	Sandy	4'	11/29/11 1445 hrs	P. Shaw	
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							

\* = Depth Below the Surrounding Land Surface

## **XI. SAMPLING METHODOLOGY**

Provide a detailed description of the methods used to collect and store the samples. Also include the preservative used for each sample. Please use the space provided below.

Sampling was performed in accordance with SC DHEC R.61-92 Part 280 and SC DHEC Assessment Guidelines. Sample containers were prepared by the testing laboratory. The grab method was utilized to fill the sample containers leaving as little head space as possible and immediately capped. Soil samples were extracted from area below tank. The samples were marked, logged, and immediately placed in a sample cooler packed with ice to maintain an approximate temperature of 4 degrees Centigrade. Tools were thoroughly cleaned and decontaminated with the seven step decon process after each use. The samples remained in custody of SBG-EEG, Inc. until they were transferred to Test America Incorporated for analysis as documented in the Chain of Custody Record.

---

---

---

---

---

---

---

---

---

---

## XII. RECEPTORS


	Yes	No
<p>A. Are there any lakes, ponds, streams, or wetlands located within 1000 feet of the UST system?</p> <p style="text-align: right;">*Stormwater canal ~225'</p> <p>If yes, indicate type of receptor, distance, and direction on site map.</p>	*X	
<p>B. Are there any public, private, or irrigation water supply wells within 1000 feet of the UST system?</p> <p>If yes, indicate type of well, distance, and direction on site map.</p>		X
<p>C. Are there any underground structures (e.g., basements) Located within 100 feet of the UST system?</p> <p>If yes, indicate type of structure, distance, and direction on site map.</p>		X
<p>D. Are there any underground utilities (e.g., telephone, electricity, gas, water, sewer, storm drain) located within 100 feet of the UST system that could potentially come in contact with the contamination?</p> <p style="text-align: right;">*Sewer, water, electricity, cable &amp; fiber optic</p> <p>If yes, indicate the type of utility, distance, and direction on the site map.</p>	*X	
<p>E. Has contaminated soil been identified at a depth less than 3 feet below land surface in an area that is not capped by asphalt or concrete?</p> <p>If yes, indicate the area of contaminated soil on the site map.</p>		X




### **XIII. SITE MAP**

**You must supply a scaled site map. It should include all buildings, road names, utilities, tank and dispenser island locations, labeled sample locations, extent of excavation, and any other pertinent information.**

(Attach Site Map Here)



**328 ASH**



**SBG-EEG, Inc.**

7301 Rivers Ave., Suite 245  
N. Charleston SC 29406-9643

Ph. (843) 573-7140

Drawn By: L. DiAsio

Dwg Date: DEC 2011

**FIGURE 1: LOCATION MAP**  
**328 ASH STREET**  
**LAUREL BAY, BEAUFORT SC**



STORMWATER DRAINAGE  
CANAL  $\approx$  225'

328 ASH STREET  
LAUREL BAY MILITARY HOUSING  
MCAS BEAUFORT, SC

CONCRETE PORCH

CONCRETE WALK


UST 328ASH-1,  
280 GAL.

ASPHALT  
DRIVEWAY

UST 328ASH-2,  
280 GAL.

WATER LINE

GRAPHIC SCALE



**SBG-EEG**


7301 RIVERS AVE., SUITE 245  
N. CHARLESTON SC 29406-9643  
(843) 573-7140

FIGURE 2 SITE MAP  
328 ASH ST., LAUREL BAY  
MCAS BEAUFORT SC


SCALE: GRAPHIC

DWG DATE DEC 2011

328 ASH STREET



\*A PORTION OF THE CONCRETE SIDEWALK WAS REMOVED TO FACILITATE TANK EXTRACTION.



TANK DEPTH BELOW GRADE

328-1 = 30"

328-2 = 12"

**SBG-EEG**

7301 RIVERS AVE., SUITE 245  
N. CHARLESTON SC 29406-9643  
(843) 573-7140

FIGURE 3 UST SAMPLE LOCATIONS  
328 ASH ST., LAUREL BAY  
MCAS BEAUFORT SC

SCALE: GRAPHIC

DWG DATE DEC 2011





Picture 1: Location of tanks at 328 Ash Street.



Picture 2: Excavation of UST 328Ash-1.





Picture 3: UST 328 Ash-2 excavation.



Picture 4: Excavation of UST 328-2.

#### XIV. SUMMARY OF ANALYSIS RESULTS

Enter the soil analytical data for each soil boring for all COC in the table below and on the following page.

CoC	UST	328Ash-1		328Ash-2			
Benzene		ND		ND			
Toluene		ND		ND			
Ethylbenzene		ND		0.00119 mg/kg			
Xylenes		ND		ND			
Naphthalene		ND		0.0429 mg/kg			
Benzo (a) anthracene		0.123 mg/kg		ND			
Benzo (b) fluoranthene		ND		ND			
Benzo (k) fluoranthene		ND		ND			
Chrysene		0.101 mg/kg		ND			
Dibenz (a, h) anthracene		ND		ND			
TPH (EPA 3550)							

CoC								
Benzene								
Toluene								
Ethylbenzene								
Xylenes								
Naphthalene								
Benzo (a) anthracene								
Benzo (b) fluoranthene								
Benzo (k) fluoranthene								
Chrysene								
Dibenz (a, h) anthracene								
TPH (EPA 3550)								

### SUMMARY OF ANALYSIS RESULTS (cont'd)

Enter the ground water analytical data for each sample for all CoC in the table below. If free product is present, indicate the measured thickness to the nearest 0.01 feet.

CoC	RBSL (µg/l)	W-1	W-2	W -3	W -4
Free Product Thickness	None				
Benzene	5				
Toluene	1,000				
Ethylbenzene	700				
Xylenes	10,000				
Total BTEX	N/A				
MTBE	40				
Naphthalene	25				
Benzo (a) anthracene	10				
Benzo (b) flouranthene	10				
Benzo (k) flouranthene	10				
Chrysene	10				
Dibenz (a, h) anthracene	10				
EDB	.05				
1,2-DCA	5				
Lead	Site specific				



## **XV. ANALYTICAL RESULTS**

**You must submit the laboratory report and chain-of-custody form for the samples. These samples must be analyzed by a South Carolina certified laboratory.**

(Attach Certified Analytical Results and Chain-of-Custody Here)  
(Please see Form #4)

# TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING

## ANALYTICAL REPORT

TestAmerica Laboratories, Inc.

TestAmerica Nashville  
2960 Foster Creighton Road  
Nashville, TN 37204  
Tel: 800-765-0980

TestAmerica Job ID: NVL0585

Client Project/Site: [none]

Client Project Description: Laurel Bay Housing Project

For:

EEG - Small Business Group, Inc. (2449)  
10179 Highway 78  
Ladson, SC 29456

Attn: Tom McElwee

*Roxanne L. Connor*

Authorized for release by:

12/16/2011 3:52:14 PM

Roxanne Connor

Program Manager - Conventional Accounts

[roxanne.connor@testamericainc.com](mailto:roxanne.connor@testamericainc.com)

Designee for

Ken A. Hayes

Senior Project Manager

[ken.hayes@testamericainc.com](mailto:ken.hayes@testamericainc.com)

### LINKS

Review your project  
results through

TotalAccess

Have a Question?



Visit us at:

[www.testamericainc.com](http://www.testamericainc.com)

*This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.*

*Results relate only to the items tested and the sample(s) as received by the laboratory.*



# Table of Contents

Cover Page . . . . . 1

Table of Contents . . . . . 2

Sample Summary . . . . . 3

Definitions . . . . . 4

Client Sample Results . . . . . 5

QC Sample Results . . . . . 8

QC Association . . . . . 16

Chronicle . . . . . 18

Method Summary . . . . . 19

Certification Summary . . . . . 20

Chain of Custody . . . . . 21

## Sample Summary

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
NVL0585-01	328 Ash-1	Soil	11/29/11 13:45	12/05/11 08:30
NVL0585-02	328 Ash-2	Soil	11/29/11 14:45	12/05/11 08:30
NVL0585-03	370 Aspen	Soil	12/01/11 12:00	12/05/11 08:30

## Definitions/Glossary

Client: EEG - Small Business Group, Inc. (2449)

TestAmerica Job ID: NVL0585

Project/Site: [none]

### Qualifiers

#### GCMS Volatiles

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.
ZX	Due to sample matrix effects, the surrogate recovery was outside the acceptance limits.
RL1	Reporting limit raised due to sample matrix effects.

#### GCMS Semivolatiles

Qualifier	Qualifier Description
J	Result is less than the RL but greater than or equal to the MDL and the concentration is an approximate value.

### Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
☐	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CNF	Contains no Free Liquid
DL, RA, RE, IN	Indicates a Dilution, Reanalysis, Re-extraction, or additional Initial metals/anion analysis of the sample
EDL	Estimated Detection Limit
EPA	United States Environmental Protection Agency
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
ND	Not detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
RL	Reporting Limit
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)



# Client Sample Results

Client: EEG - Small Business Group, Inc. (2449)

TestAmerica Job ID: NVL0585

Project/Site: [none]

Client Sample ID: 328 Ash-1

Lab Sample ID: NVL0585-01

Date Collected: 11/29/11 13:45

Matrix: Soil

Date Received: 12/05/11 08:30

Percent Solids: 85.3

5

## Method: SW846 8260B - Volatile Organic Compounds by EPA Method 8260B - RE1

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.00186	0.00102	mg/kg dry	☒	11/29/11 13:45	12/12/11 17:00	1.00
Ethylbenzene	ND		0.00186	0.00102	mg/kg dry	☒	11/29/11 13:45	12/12/11 17:00	1.00
Naphthalene	ND		0.00465	0.00233	mg/kg dry	☒	11/29/11 13:45	12/12/11 17:00	1.00
Toluene	ND		0.00186	0.00102	mg/kg dry	☒	11/29/11 13:45	12/12/11 17:00	1.00
Xylenes, total	ND		0.00465	0.00233	mg/kg dry	☒	11/29/11 13:45	12/12/11 17:00	1.00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4	100		70 - 130	11/29/11 13:45	12/12/11 17:00	1.00
Dibromofluoromethane	99		70 - 130	11/29/11 13:45	12/12/11 17:00	1.00
Toluene-d8	96		70 - 130	11/29/11 13:45	12/12/11 17:00	1.00
4-Bromofluorobenzene	114		70 - 130	11/29/11 13:45	12/12/11 17:00	1.00

## Method: SW846 8270D - Polyaromatic Hydrocarbons by EPA 8270D

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Acenaphthylene	ND		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Anthracene	0.0445	J	0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Benzo (a) anthracene	0.123		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Benzo (a) pyrene	ND		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Benzo (b) fluoranthene	ND		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Benzo (g,h,i) perylene	ND		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Benzo (k) fluoranthene	ND		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Chrysene	0.101		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Dibenz (a,h) anthracene	ND		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Fluoranthene	0.381		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Fluorene	0.0495	J	0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Indeno (1,2,3-cd) pyrene	ND		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Naphthalene	ND		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Phenanthrene	0.277		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
Pyrene	0.287		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
1-Methylnaphthalene	0.0815		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00
2-Methylnaphthalene	ND		0.0784	0.0398	mg/kg dry	☒	12/09/11 10:02	12/10/11 18:32	1.00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Terphenyl-d14	93		18 - 120	12/09/11 10:02	12/10/11 18:32	1.00
2-Fluorobiphenyl	77		14 - 120	12/09/11 10:02	12/10/11 18:32	1.00
Nitrobenzene-d5	87		17 - 120	12/09/11 10:02	12/10/11 18:32	1.00

## Method: SW-846 - General Chemistry Parameters

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
% Dry Solids	85.3		0.500	0.500	%		12/08/11 10:43	12/09/11 09:10	1.00

# Client Sample Results

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

Client Sample ID: 328 Ash-2

Date Collected: 11/29/11 14:45

Date Received: 12/05/11 08:30

Lab Sample ID: NVL0585-02

Matrix: Soil

Percent Solids: 84

5

## Method: SW846 8260B - Volatile Organic Compounds by EPA Method 8260B

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.00182	0.00100	mg/kg dry	☼	11/29/11 14:45	12/09/11 19:36	1.00
Ethylbenzene	0.00119	J	0.00182	0.00100	mg/kg dry	☼	11/29/11 14:45	12/09/11 19:36	1.00
Naphthalene	0.0429		0.00455	0.00228	mg/kg dry	☼	11/29/11 14:45	12/09/11 19:36	1.00
Toluene	ND		0.00182	0.00100	mg/kg dry	☼	11/29/11 14:45	12/09/11 19:36	1.00
Xylenes, total	ND		0.00455	0.00228	mg/kg dry	☼	11/29/11 14:45	12/09/11 19:36	1.00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4	109		70 - 130	11/29/11 14:45	12/09/11 19:36	1.00
Dibromofluoromethane	96		70 - 130	11/29/11 14:45	12/09/11 19:36	1.00
Toluene-d8	91		70 - 130	11/29/11 14:45	12/09/11 19:36	1.00
4-Bromofluorobenzene	113		70 - 130	11/29/11 14:45	12/09/11 19:36	1.00

## Method: SW846 8270D - Polyaromatic Hydrocarbons by EPA 8270D

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Acenaphthylene	ND		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Anthracene	ND		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Benzo (a) anthracene	ND		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Benzo (a) pyrene	ND		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Benzo (b) fluoranthene	ND		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Benzo (g,h,i) perylene	ND		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Benzo (k) fluoranthene	ND		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Chrysene	ND		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Dibenz (a,h) anthracene	ND		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Fluoranthene	ND		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Fluorene	0.100		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Indeno (1,2,3-cd) pyrene	ND		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Naphthalene	0.170		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Phenanthrene	0.155		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
Pyrene	ND		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
1-Methylnaphthalene	0.553		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00
2-Methylnaphthalene	0.712		0.0779	0.0396	mg/kg dry	☼	12/09/11 10:02	12/10/11 18:51	1.00

Surrogate	%Recovery	Qualifier	Limits	Prepared	Analyzed	Dil Fac
Terphenyl-d14	97		18 - 120	12/09/11 10:02	12/10/11 18:51	1.00
2-Fluorobiphenyl	79		14 - 120	12/09/11 10:02	12/10/11 18:51	1.00
Nitrobenzene-d5	88		17 - 120	12/09/11 10:02	12/10/11 18:51	1.00

## Method: SW-846 - General Chemistry Parameters

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
% Dry Solids	84.0		0.500	0.500	%		12/08/11 10:43	12/09/11 09:10	1.00



# Client Sample Results

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

Client Sample ID: 370 Aspen

Date Collected: 12/01/11 12:00

Date Received: 12/05/11 08:30

Lab Sample ID: NVL0585-03

Matrix: Soil

Percent Solids: 83.2

5

## Method: SW846 8260B - Volatile Organic Compounds by EPA Method 8260B - RE1

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.00249	0.00137	mg/kg dry	☞	12/01/11 12:00	12/13/11 18:26	1.00
Ethylbenzene	ND		0.00249	0.00137	mg/kg dry	☞	12/01/11 12:00	12/13/11 18:26	1.00
Toluene	ND		0.00249	0.00137	mg/kg dry	☞	12/01/11 12:00	12/13/11 18:26	1.00
Xylenes, total	ND		0.00623	0.00312	mg/kg dry	☞	12/01/11 12:00	12/13/11 18:26	1.00
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4	100		70 - 130				12/01/11 12:00	12/13/11 18:26	1.00
Dibromofluoromethane	101		70 - 130				12/01/11 12:00	12/13/11 18:26	1.00
Toluene-d8	101		70 - 130				12/01/11 12:00	12/13/11 18:26	1.00
4-Bromofluorobenzene	150	ZX	70 - 130				12/01/11 12:00	12/13/11 18:26	1.00

## Method: SW846 8260B - Volatile Organic Compounds by EPA Method 8260B - RE2

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Naphthalene	ND	RL1	0.322	0.161	mg/kg dry	☞	12/01/11 12:00	12/13/11 18:57	50.0
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4	89		70 - 130				12/01/11 12:00	12/13/11 18:57	50.0
Dibromofluoromethane	92		70 - 130				12/01/11 12:00	12/13/11 18:57	50.0
Toluene-d8	92		70 - 130				12/01/11 12:00	12/13/11 18:57	50.0
4-Bromofluorobenzene	106		70 - 130				12/01/11 12:00	12/13/11 18:57	50.0

## Method: SW846 8270D - Polyaromatic Hydrocarbons by EPA 8270D

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Acenaphthylene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Anthracene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Benzo (a) anthracene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Benzo (a) pyrene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Benzo (b) fluoranthene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Benzo (g,h,i) perylene	0.0517	J	0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Benzo (k) fluoranthene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Chrysene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Dibenz (a,h) anthracene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Fluoranthene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Fluorene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Indeno (1,2,3-cd) pyrene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Naphthalene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Phenanthrene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Pyrene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
1-Methylnaphthalene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
2-Methylnaphthalene	ND		0.0781	0.0396	mg/kg dry	☞	12/09/11 10:02	12/10/11 19:10	1.00
Surrogate	%Recovery	Qualifier	Limits				Prepared	Analyzed	Dil Fac
Terphenyl-d14	97		18 - 120				12/09/11 10:02	12/10/11 19:10	1.00
2-Fluorobiphenyl	71		14 - 120				12/09/11 10:02	12/10/11 19:10	1.00
Nitrobenzene-d5	80		17 - 120				12/09/11 10:02	12/10/11 19:10	1.00

## Method: SW-846 - General Chemistry Parameters

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
% Dry Solids	83.2		0.500	0.500	%		12/08/11 10:43	12/09/11 09:10	1.00



## QC Sample Results

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

### Method: SW846 8260B - Volatile Organic Compounds by EPA Method 8260B

Lab Sample ID: 11L1207-BLK1

Matrix: Soil

Analysis Batch: U021754

Client Sample ID: Method Blank

Prep Type: Total

Prep Batch: 11L1207\_P

Analyte	Blank Result	Blank Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.00200	0.00110	mg/kg wet		12/09/11 10:14	12/09/11 12:50	1.00
Ethylbenzene	ND		0.00200	0.00110	mg/kg wet		12/09/11 10:14	12/09/11 12:50	1.00
Naphthalene	ND		0.00500	0.00250	mg/kg wet		12/09/11 10:14	12/09/11 12:50	1.00
Toluene	ND		0.00200	0.00110	mg/kg wet		12/09/11 10:14	12/09/11 12:50	1.00
Xylenes, total	ND		0.00500	0.00250	mg/kg wet		12/09/11 10:14	12/09/11 12:50	1.00

Surrogate	Blank %Recovery	Blank Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4	100		70 - 130	12/09/11 10:14	12/09/11 12:50	1.00
Dibromofluoromethane	100		70 - 130	12/09/11 10:14	12/09/11 12:50	1.00
Toluene-d8	101		70 - 130	12/09/11 10:14	12/09/11 12:50	1.00
4-Bromofluorobenzene	100		70 - 130	12/09/11 10:14	12/09/11 12:50	1.00

Lab Sample ID: 11L1207-BLK2

Matrix: Soil

Analysis Batch: U021754

Client Sample ID: Method Blank

Prep Type: Total

Prep Batch: 11L1207\_P

Analyte	Blank Result	Blank Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.100	0.0550	mg/kg wet		12/09/11 10:14	12/09/11 13:21	50.0
Ethylbenzene	ND		0.100	0.0550	mg/kg wet		12/09/11 10:14	12/09/11 13:21	50.0
Naphthalene	ND		0.250	0.125	mg/kg wet		12/09/11 10:14	12/09/11 13:21	50.0
Toluene	ND		0.100	0.0550	mg/kg wet		12/09/11 10:14	12/09/11 13:21	50.0
Xylenes, total	ND		0.250	0.125	mg/kg wet		12/09/11 10:14	12/09/11 13:21	50.0

Surrogate	Blank %Recovery	Blank Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4	101		70 - 130	12/09/11 10:14	12/09/11 13:21	50.0
Dibromofluoromethane	102		70 - 130	12/09/11 10:14	12/09/11 13:21	50.0
Toluene-d8	102		70 - 130	12/09/11 10:14	12/09/11 13:21	50.0
4-Bromofluorobenzene	95		70 - 130	12/09/11 10:14	12/09/11 13:21	50.0

Lab Sample ID: 11L1207-BS1

Matrix: Soil

Analysis Batch: U021754

Client Sample ID: Lab Control Sample

Prep Type: Total

Prep Batch: 11L1207\_P

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	Limits
Benzene	50.0	52.5		ug/kg		105	75 - 127
Ethylbenzene	50.0	52.8		ug/kg		106	80 - 134
Naphthalene	50.0	49.9		ug/kg		100	69 - 150
Toluene	50.0	48.9		ug/kg		98	80 - 132
Xylenes, total	150	159		ug/kg		106	80 - 137

Surrogate	LCS %Recovery	LCS Qualifier	Limits
1,2-Dichloroethane-d4	102		70 - 130
Dibromofluoromethane	102		70 - 130
Toluene-d8	98		70 - 130
4-Bromofluorobenzene	99		70 - 130

## QC Sample Results

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

### Method: SW846 8260B - Volatile Organic Compounds by EPA Method 8260B (Continued)

**Lab Sample ID: 11L1207-BSD1**

**Matrix: Soil**

**Analysis Batch: U021754**

**Client Sample ID: Lab Control Sample Dup**

**Prep Type: Total**

**Prep Batch: 11L1207\_P**

Analyte	Spike Added	LCS Dup Result	LCS Dup Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Benzene	50.0	50.5		ug/kg		101	75 - 127	4	50
Ethylbenzene	50.0	50.4		ug/kg		101	80 - 134	5	50
Naphthalene	50.0	49.5		ug/kg		99	69 - 150	1	50
Toluene	50.0	47.2		ug/kg		94	80 - 132	4	50
Xylenes, total	150	150		ug/kg		100	80 - 137	6	50

Surrogate	LCS Dup %Recovery	LCS Dup Qualifier	Limits
1,2-Dichloroethane-d4	102		70 - 130
Dibromofluoromethane	101		70 - 130
Toluene-d8	98		70 - 130
4-Bromofluorobenzene	101		70 - 130

**Lab Sample ID: 11L3001-BLK1**

**Matrix: Soil**

**Analysis Batch: U021759**

**Client Sample ID: Method Blank**

**Prep Type: Total**

**Prep Batch: 11L3001\_P**

Analyte	Blank Result	Blank Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.00200	0.00110	mg/kg wet		12/12/11 09:43	12/12/11 11:48	1.00
Ethylbenzene	ND		0.00200	0.00110	mg/kg wet		12/12/11 09:43	12/12/11 11:48	1.00
Naphthalene	ND		0.00500	0.00250	mg/kg wet		12/12/11 09:43	12/12/11 11:48	1.00
Toluene	ND		0.00200	0.00110	mg/kg wet		12/12/11 09:43	12/12/11 11:48	1.00
Xylenes, total	ND		0.00500	0.00250	mg/kg wet		12/12/11 09:43	12/12/11 11:48	1.00

Surrogate	Blank %Recovery	Blank Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4	103		70 - 130	12/12/11 09:43	12/12/11 11:48	1.00
Dibromofluoromethane	101		70 - 130	12/12/11 09:43	12/12/11 11:48	1.00
Toluene-d8	98		70 - 130	12/12/11 09:43	12/12/11 11:48	1.00
4-Bromofluorobenzene	97		70 - 130	12/12/11 09:43	12/12/11 11:48	1.00

**Lab Sample ID: 11L3001-BLK2**

**Matrix: Soil**

**Analysis Batch: U021759**

**Client Sample ID: Method Blank**

**Prep Type: Total**

**Prep Batch: 11L3001\_P**

Analyte	Blank Result	Blank Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.100	0.0550	mg/kg wet		12/12/11 09:43	12/12/11 12:19	50.0
Ethylbenzene	ND		0.100	0.0550	mg/kg wet		12/12/11 09:43	12/12/11 12:19	50.0
Naphthalene	ND		0.250	0.125	mg/kg wet		12/12/11 09:43	12/12/11 12:19	50.0
Toluene	ND		0.100	0.0550	mg/kg wet		12/12/11 09:43	12/12/11 12:19	50.0
Xylenes, total	ND		0.250	0.125	mg/kg wet		12/12/11 09:43	12/12/11 12:19	50.0

Surrogate	Blank %Recovery	Blank Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4	97		70 - 130	12/12/11 09:43	12/12/11 12:19	50.0
Dibromofluoromethane	99		70 - 130	12/12/11 09:43	12/12/11 12:19	50.0
Toluene-d8	100		70 - 130	12/12/11 09:43	12/12/11 12:19	50.0
4-Bromofluorobenzene	98		70 - 130	12/12/11 09:43	12/12/11 12:19	50.0



# QC Sample Results

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

## Method: SW846 8260B - Volatile Organic Compounds by EPA Method 8260B (Continued)

Lab Sample ID: 11L3001-BS1

Matrix: Soil

Analysis Batch: U021759

Client Sample ID: Lab Control Sample

Prep Type: Total

Prep Batch: 11L3001\_P

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Benzene	50.0	51.4		ug/kg		103	75 - 127
Ethylbenzene	50.0	51.7		ug/kg		103	80 - 134
Naphthalene	50.0	48.8		ug/kg		98	69 - 150
Toluene	50.0	47.3		ug/kg		95	80 - 132
Xylenes, total	150	154		ug/kg		103	80 - 137

Surrogate	LCS %Recovery	LCS Qualifier	Limits
1,2-Dichloroethane-d4	100		70 - 130
Dibromofluoromethane	102		70 - 130
Toluene-d8	96		70 - 130
4-Bromofluorobenzene	105		70 - 130

Lab Sample ID: 11L3001-MS1

Matrix: Soil

Analysis Batch: U021759

Client Sample ID: Matrix Spike

Prep Type: Total

Prep Batch: 11L3001\_P

Analyte	Sample Result	Sample Qualifier	Spike Added	Matrix Spike Result	Matrix Spike Qualifier	Unit	D	%Rec	%Rec. Limits
Benzene	ND		2.10	2.25		mg/kg wet		107	31 - 143
Ethylbenzene	ND		2.10	2.21		mg/kg wet		105	23 - 161
Naphthalene	ND		2.10	2.13		mg/kg wet		101	10 - 176
Toluene	ND		2.10	2.01		mg/kg wet		96	30 - 155
Xylenes, total	ND		6.30	6.57		mg/kg wet		104	25 - 162

Surrogate	Matrix Spike %Recovery	Matrix Spike Qualifier	Limits
1,2-Dichloroethane-d4	99		70 - 130
Dibromofluoromethane	99		70 - 130
Toluene-d8	94		70 - 130
4-Bromofluorobenzene	106		70 - 130

Lab Sample ID: 11L3001-MSD1

Matrix: Soil

Analysis Batch: U021759

Client Sample ID: Matrix Spike Duplicate

Prep Type: Total

Prep Batch: 11L3001\_P

Analyte	Sample Result	Sample Qualifier	Spike Added	Matrix Spike Dup Result	Matrix Spike Dup Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	Limit
Benzene	ND		2.10	2.41		mg/kg wet		114	31 - 143	7	50
Ethylbenzene	ND		2.10	2.11		mg/kg wet		100	23 - 161	4	50
Naphthalene	ND		2.10	2.22		mg/kg wet		106	10 - 176	4	50
Toluene	ND		2.10	2.02		mg/kg wet		96	30 - 155	0.9	50
Xylenes, total	ND		6.30	6.19		mg/kg wet		98	25 - 162	6	50

Surrogate	Matrix Spike Dup %Recovery	Matrix Spike Dup Qualifier	Limits
1,2-Dichloroethane-d4	99		70 - 130
Dibromofluoromethane	97		70 - 130
Toluene-d8	94		70 - 130
4-Bromofluorobenzene	106		70 - 130

# QC Sample Results

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

## Method: SW846 8260B - Volatile Organic Compounds by EPA Method 8260B (Continued)

Lab Sample ID: 11L3198-BLK1

Matrix: Soil

Analysis Batch: U021855

Client Sample ID: Method Blank

Prep Type: Total

Prep Batch: 11L3198\_P

Analyte	Blank Result	Blank Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.00200	0.00110	mg/kg wet		12/13/11 00:33	12/13/11 12:12	1.00
Ethylbenzene	ND		0.00200	0.00110	mg/kg wet		12/13/11 00:33	12/13/11 12:12	1.00
Naphthalene	ND		0.00500	0.00250	mg/kg wet		12/13/11 00:33	12/13/11 12:12	1.00
Toluene	ND		0.00200	0.00110	mg/kg wet		12/13/11 00:33	12/13/11 12:12	1.00
Xylenes, total	ND		0.00500	0.00250	mg/kg wet		12/13/11 00:33	12/13/11 12:12	1.00

Surrogate	Blank %Recovery	Blank Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4	98		70 - 130	12/13/11 00:33	12/13/11 12:12	1.00
Dibromofluoromethane	99		70 - 130	12/13/11 00:33	12/13/11 12:12	1.00
Toluene-d8	94		70 - 130	12/13/11 00:33	12/13/11 12:12	1.00
4-Bromofluorobenzene	104		70 - 130	12/13/11 00:33	12/13/11 12:12	1.00

Lab Sample ID: 11L3198-BLK2

Matrix: Soil

Analysis Batch: U021855

Client Sample ID: Method Blank

Prep Type: Total

Prep Batch: 11L3198\_P

Analyte	Blank Result	Blank Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Benzene	ND		0.100	0.0550	mg/kg wet		12/13/11 00:33	12/13/11 12:43	50.0
Ethylbenzene	ND		0.100	0.0550	mg/kg wet		12/13/11 00:33	12/13/11 12:43	50.0
Naphthalene	ND		0.250	0.125	mg/kg wet		12/13/11 00:33	12/13/11 12:43	50.0
Toluene	ND		0.100	0.0550	mg/kg wet		12/13/11 00:33	12/13/11 12:43	50.0
Xylenes, total	ND		0.250	0.125	mg/kg wet		12/13/11 00:33	12/13/11 12:43	50.0

Surrogate	Blank %Recovery	Blank Qualifier	Limits	Prepared	Analyzed	Dil Fac
1,2-Dichloroethane-d4	97		70 - 130	12/13/11 00:33	12/13/11 12:43	50.0
Dibromofluoromethane	100		70 - 130	12/13/11 00:33	12/13/11 12:43	50.0
Toluene-d8	96		70 - 130	12/13/11 00:33	12/13/11 12:43	50.0
4-Bromofluorobenzene	104		70 - 130	12/13/11 00:33	12/13/11 12:43	50.0

Lab Sample ID: 11L3198-BS1

Matrix: Soil

Analysis Batch: U021855

Client Sample ID: Lab Control Sample

Prep Type: Total

Prep Batch: 11L3198\_P

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Benzene	50.0	52.8		ug/kg		106	75 - 127
Ethylbenzene	50.0	51.4		ug/kg		103	80 - 134
Naphthalene	50.0	51.8		ug/kg		104	69 - 150
Toluene	50.0	47.7		ug/kg		95	80 - 132
Xylenes, total	150	153		ug/kg		102	80 - 137

Surrogate	LCS %Recovery	LCS Qualifier	Limits
1,2-Dichloroethane-d4	99		70 - 130
Dibromofluoromethane	100		70 - 130
Toluene-d8	95		70 - 130
4-Bromofluorobenzene	104		70 - 130



# QC Sample Results

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

## Method: SW846 8260B - Volatile Organic Compounds by EPA Method 8260B (Continued)

Lab Sample ID: 11L3198-BSD1

Matrix: Soil

Analysis Batch: U021855

Client Sample ID: Lab Control Sample Dup

Prep Type: Total

Prep Batch: 11L3198\_P

Analyte	Spike Added	LCS Dup Result	LCS Dup Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Benzene	50.0	53.3		ug/kg		107	75 - 127	1	50
Ethylbenzene	50.0	51.3		ug/kg		103	80 - 134	0.3	50
Naphthalene	50.0	53.3		ug/kg		107	69 - 150	3	50
Toluene	50.0	47.6		ug/kg		95	80 - 132	0.2	50
Xylenes, total	150	153		ug/kg		102	80 - 137	0.4	50

Surrogate	LCS Dup %Recovery	LCS Dup Qualifier	Limits
1,2-Dichloroethane-d4	99		70 - 130
Dibromofluoromethane	101		70 - 130
Toluene-d8	94		70 - 130
4-Bromofluorobenzene	108		70 - 130

Lab Sample ID: 11L3198-MS1

Matrix: Soil

Analysis Batch: U021855

Client Sample ID: Matrix Spike

Prep Type: Total

Prep Batch: 11L3198\_P

Analyte	Sample Result	Sample Qualifier	Spike Added	Matrix Spike Result	Matrix Spike Qualifier	Unit	D	%Rec	%Rec. Limits
Benzene	ND		42.2	53.3		mg/kg wet		126	31 - 143
Ethylbenzene	3.22		42.2	56.9		mg/kg wet		127	23 - 161
Naphthalene	2.35		42.2	61.0		mg/kg wet		139	10 - 176
Toluene	ND		42.2	47.3		mg/kg wet		112	30 - 155
Xylenes, total	ND		126	157		mg/kg wet		124	25 - 162

Surrogate	Matrix Spike %Recovery	Matrix Spike Qualifier	Limits
1,2-Dichloroethane-d4	100		70 - 130
Dibromofluoromethane	100		70 - 130
Toluene-d8	105		70 - 130
4-Bromofluorobenzene	114		70 - 130

Lab Sample ID: 11L3198-MSD1

Matrix: Soil

Analysis Batch: U021855

Client Sample ID: Matrix Spike Duplicate

Prep Type: Total

Prep Batch: 11L3198\_P

Analyte	Sample Result	Sample Qualifier	Spike Added	Matrix Spike Dup Result	Matrix Spike Dup Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Benzene	ND		42.2	47.8		mg/kg wet		113	31 - 143	11	50
Ethylbenzene	3.22		42.2	51.1		mg/kg wet		114	23 - 161	11	50
Naphthalene	2.35		42.2	52.0		mg/kg wet		118	10 - 176	16	50
Toluene	ND		42.2	42.3		mg/kg wet		100	30 - 155	11	50
Xylenes, total	ND		126	141		mg/kg wet		111	25 - 162	11	50

Surrogate	Matrix Spike Dup %Recovery	Matrix Spike Dup Qualifier	Limits
1,2-Dichloroethane-d4	100		70 - 130
Dibromofluoromethane	99		70 - 130
Toluene-d8	105		70 - 130
4-Bromofluorobenzene	115		70 - 130

# QC Sample Results

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

## Method: SW846 8270D - Polyaromatic Hydrocarbons by EPA 8270D

Lab Sample ID: 11L1216-BLK1

Matrix: Soil

Analysis Batch: 11L1216

Client Sample ID: Method Blank

Prep Type: Total

Prep Batch: 11L1216\_P

Analyte	Blank Result	Blank Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Acenaphthene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Acenaphthylene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Anthracene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Benzo (a) anthracene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Benzo (a) pyrene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Benzo (b) fluoranthene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Benzo (g,h,i) perylene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Benzo (k) fluoranthene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Chrysene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Dibenz (a,h) anthracene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Fluoranthene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Fluorene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Indeno (1,2,3-cd) pyrene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Naphthalene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Phenanthrene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
Pyrene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
1-Methylnaphthalene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00
2-Methylnaphthalene	ND		0.0670	0.0340	mg/kg wet		12/09/11 10:02	12/10/11 17:08	1.00

Surrogate	Blank %Recovery	Blank Qualifier	Limits	Prepared	Analyzed	Dil Fac
Terphenyl-d14	118		18 - 120	12/09/11 10:02	12/10/11 17:08	1.00
2-Fluorobiphenyl	94		14 - 120	12/09/11 10:02	12/10/11 17:08	1.00
Nitrobenzene-d5	102		17 - 120	12/09/11 10:02	12/10/11 17:08	1.00

Lab Sample ID: 11L1216-BS1

Matrix: Soil

Analysis Batch: 11L1216

Client Sample ID: Lab Control Sample

Prep Type: Total

Prep Batch: 11L1216\_P

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	Limits
Acenaphthene	1.67	1.51		mg/kg wet		90	36 - 120
Acenaphthylene	1.67	1.52		mg/kg wet		91	38 - 120
Anthracene	1.67	1.75		mg/kg wet		105	46 - 124
Benzo (a) anthracene	1.67	1.73		mg/kg wet		104	45 - 120
Benzo (a) pyrene	1.67	1.76		mg/kg wet		106	45 - 120
Benzo (b) fluoranthene	1.67	1.71		mg/kg wet		103	42 - 120
Benzo (g,h,i) perylene	1.67	1.73		mg/kg wet		104	38 - 120
Benzo (k) fluoranthene	1.67	1.60		mg/kg wet		96	42 - 120
Chrysene	1.67	1.71		mg/kg wet		103	43 - 120
Dibenz (a,h) anthracene	1.67	1.73		mg/kg wet		104	32 - 128
Fluoranthene	1.67	1.73		mg/kg wet		104	46 - 120
Fluorene	1.67	1.71		mg/kg wet		103	42 - 120
Indeno (1,2,3-cd) pyrene	1.67	1.74		mg/kg wet		104	41 - 121
Naphthalene	1.67	1.56		mg/kg wet		94	32 - 120
Phenanthrene	1.67	1.72		mg/kg wet		103	45 - 120
Pyrene	1.67	1.69		mg/kg wet		102	43 - 120
1-Methylnaphthalene	1.67	1.16		mg/kg wet		70	32 - 120
2-Methylnaphthalene	1.67	1.38		mg/kg wet		83	28 - 120



# QC Sample Results

Client: EEG - Small Business Group, Inc. (2449)

TestAmerica Job ID: NVL0585

Project/Site: [none]

## Method: SW846 8270D - Polyaromatic Hydrocarbons by EPA 8270D (Continued)

Lab Sample ID: 11L1216-BS1

Matrix: Soil

Analysis Batch: 11L1216

Client Sample ID: Lab Control Sample

Prep Type: Total

Prep Batch: 11L1216\_P

Surrogate	LCS %Recovery	LCS Qualifier	Limits
Terphenyl-d14	103		18 - 120
2-Fluorobiphenyl	82		14 - 120
Nitrobenzene-d5	81		17 - 120

Lab Sample ID: 11L1216-MS1

Matrix: Soil

Analysis Batch: 11L1216

Client Sample ID: 328 Ash-1

Prep Type: Total

Prep Batch: 11L1216\_P

Analyte	Sample Result	Sample Qualifier	Spike Added	Matrix Spike Result	Matrix Spike Qualifier	Unit	D	%Rec	Limits
Acenaphthene	ND		1.92	1.63		mg/kg dry	☉	85	19 - 120
Acenaphthylene	ND		1.92	1.58		mg/kg dry	☉	82	25 - 120
Anthracene	0.0445	J	1.92	1.90		mg/kg dry	☉	96	28 - 125
Benzo (a) anthracene	0.123		1.92	2.06		mg/kg dry	☉	101	23 - 120
Benzo (a) pyrene	ND		1.92	1.88		mg/kg dry	☉	98	15 - 128
Benzo (b) fluoranthene	ND		1.92	1.86		mg/kg dry	☉	97	12 - 133
Benzo (g,h,i) perylene	ND		1.92	1.81		mg/kg dry	☉	94	22 - 120
Benzo (k) fluoranthene	ND		1.92	1.76		mg/kg dry	☉	92	28 - 120
Chrysene	0.101		1.92	2.00		mg/kg dry	☉	99	20 - 120
Dibenz (a,h) anthracene	ND		1.92	1.78		mg/kg dry	☉	93	12 - 128
Fluoranthene	0.381		1.92	2.66		mg/kg dry	☉	118	10 - 143
Fluorene	0.0495	J	1.92	1.88		mg/kg dry	☉	95	20 - 120
Indeno (1,2,3-cd) pyrene	ND		1.92	1.83		mg/kg dry	☉	95	22 - 121
Naphthalene	ND		1.92	1.68		mg/kg dry	☉	87	10 - 120
Phenanthrene	0.277		1.92	2.31		mg/kg dry	☉	106	21 - 122
Pyrene	0.287		1.92	2.36		mg/kg dry	☉	108	20 - 123
1-Methylnaphthalene	0.0815		1.92	1.32		mg/kg dry	☉	64	10 - 120
2-Methylnaphthalene	ND		1.92	1.46		mg/kg dry	☉	76	13 - 120

Surrogate	Matrix Spike %Recovery	Matrix Spike Qualifier	Limits
Terphenyl-d14	90		18 - 120
2-Fluorobiphenyl	74		14 - 120
Nitrobenzene-d5	70		17 - 120

Lab Sample ID: 11L1216-MSD1

Matrix: Soil

Analysis Batch: 11L1216

Client Sample ID: 328 Ash-1

Prep Type: Total

Prep Batch: 11L1216\_P

Analyte	Sample Result	Sample Qualifier	Spike Added	Matrix Spike Dup Result	Matrix Spike Dup Qualifier	Unit	D	%Rec	Limits	RPD	Limit
Acenaphthene	ND		1.90	1.60		mg/kg dry	☉	84	19 - 120	2	50
Acenaphthylene	ND		1.90	1.59		mg/kg dry	☉	83	25 - 120	0.6	50
Anthracene	0.0445	J	1.90	1.87		mg/kg dry	☉	96	28 - 125	2	49
Benzo (a) anthracene	0.123		1.90	1.94		mg/kg dry	☉	96	23 - 120	6	50
Benzo (a) pyrene	ND		1.90	1.86		mg/kg dry	☉	98	15 - 128	1	50
Benzo (b) fluoranthene	ND		1.90	1.89		mg/kg dry	☉	99	12 - 133	2	50
Benzo (g,h,i) perylene	ND		1.90	1.74		mg/kg dry	☉	91	22 - 120	4	50
Benzo (k) fluoranthene	ND		1.90	1.61		mg/kg dry	☉	85	28 - 120	9	45
Chrysene	0.101		1.90	1.89		mg/kg dry	☉	94	20 - 120	6	49
Dibenz (a,h) anthracene	ND		1.90	1.77		mg/kg dry	☉	93	12 - 128	0.9	50
Fluoranthene	0.381		1.90	2.45		mg/kg dry	☉	108	10 - 143	8	50

## QC Sample Results

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

### Method: SW846 8270D - Polyaromatic Hydrocarbons by EPA 8270D (Continued)

Lab Sample ID: 11L1216-MSD1

Client Sample ID: 328 Ash-1

Matrix: Soil

Prep Type: Total

Analysis Batch: 11L1216

Prep Batch: 11L1216\_P

Analyte	Sample	Sample	Spike	Matrix Spike Dup	Matrix Spike Dup	Unit	D	%Rec	%Rec.		RPD	Limit
	Result	Qualifier	Added	Result	Qualifier				Limits	RPD		
Fluorene	0.0495	J	1.90	1.86		mg/kg dry	☼	95	20 - 120	1		50
Indeno (1,2,3-cd) pyrene	ND		1.90	1.77		mg/kg dry	☼	93	22 - 121	3		50
Naphthalene	ND		1.90	1.70		mg/kg dry	☼	89	10 - 120	2		50
Phenanthrene	0.277		1.90	2.20		mg/kg dry	☼	101	21 - 122	5		50
Pyrene	0.287		1.90	2.19		mg/kg dry	☼	100	20 - 123	7		50
1-Methylnaphthalene	0.0815		1.90	1.33		mg/kg dry	☼	66	10 - 120	0.8		50
2-Methylnaphthalene	ND		1.90	1.51		mg/kg dry	☼	79	13 - 120	4		50
<b>Matrix Spike Dup</b>												
<b>Surrogate</b>	<b>%Recovery</b>	<b>Qualifier</b>	<b>Limits</b>									
Terphenyl-d14	89		18 - 120									
2-Fluorobiphenyl	75		14 - 120									
Nitrobenzene-d5	75		17 - 120									

### Method: SW-846 - General Chemistry Parameters

Lab Sample ID: 11L1897-DUP1

Client Sample ID: Duplicate

Matrix: Soil

Prep Type: Total

Analysis Batch: 11L1897

Prep Batch: 11L1897\_P

Analyte	Sample	Sample	Duplicate	Duplicate	Unit	D	RPD	Limit
	Result	Qualifier	Result	Qualifier				
% Dry Solids	81.4		80.6		%		1	20



## QC Association Summary

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

### GCMS Volatiles

#### Analysis Batch: U021754

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
11L1207-BLK1	Method Blank	Total	Soil	SW846 8260B	11L1207_P
11L1207-BLK2	Method Blank	Total	Soil	SW846 8260B	11L1207_P
11L1207-BS1	Lab Control Sample	Total	Soil	SW846 8260B	11L1207_P
11L1207-BSD1	Lab Control Sample Dup	Total	Soil	SW846 8260B	11L1207_P
NVL0585-02	328 Ash-2	Total	Soil	SW846 8260B	11L1207_P

#### Analysis Batch: U021759

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
11L3001-BLK1	Method Blank	Total	Soil	SW846 8260B	11L3001_P
11L3001-BLK2	Method Blank	Total	Soil	SW846 8260B	11L3001_P
11L3001-BS1	Lab Control Sample	Total	Soil	SW846 8260B	11L3001_P
11L3001-MS1	Matrix Spike	Total	Soil	SW846 8260B	11L3001_P
11L3001-MSD1	Matrix Spike Duplicate	Total	Soil	SW846 8260B	11L3001_P
NVL0585-01 - RE1	328 Ash-1	Total	Soil	SW846 8260B	11L3001_P

#### Analysis Batch: U021855

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
11L3198-BLK1	Method Blank	Total	Soil	SW846 8260B	11L3198_P
11L3198-BLK2	Method Blank	Total	Soil	SW846 8260B	11L3198_P
11L3198-BS1	Lab Control Sample	Total	Soil	SW846 8260B	11L3198_P
11L3198-BSD1	Lab Control Sample Dup	Total	Soil	SW846 8260B	11L3198_P
11L3198-MS1	Matrix Spike	Total	Soil	SW846 8260B	11L3198_P
11L3198-MSD1	Matrix Spike Duplicate	Total	Soil	SW846 8260B	11L3198_P
NVL0585-03 - RE1	370 Aspen	Total	Soil	SW846 8260B	11L3198_P
NVL0585-03 - RE2	370 Aspen	Total	Soil	SW846 8260B	11L3198_P

#### Prep Batch: 11L1207\_P

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
11L1207-BLK1	Method Blank	Total	Soil	EPA 5035	
11L1207-BLK2	Method Blank	Total	Soil	EPA 5035	
11L1207-BS1	Lab Control Sample	Total	Soil	EPA 5035	
11L1207-BSD1	Lab Control Sample Dup	Total	Soil	EPA 5035	
NVL0585-02	328 Ash-2	Total	Soil	EPA 5035	

#### Prep Batch: 11L3001\_P

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
11L3001-BLK1	Method Blank	Total	Soil	EPA 5035	
11L3001-BLK2	Method Blank	Total	Soil	EPA 5035	
11L3001-BS1	Lab Control Sample	Total	Soil	EPA 5035	
11L3001-MS1	Matrix Spike	Total	Soil	EPA 5035	
11L3001-MSD1	Matrix Spike Duplicate	Total	Soil	EPA 5035	
NVL0585-01 - RE1	328 Ash-1	Total	Soil	EPA 5035	

#### Prep Batch: 11L3198\_P

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
11L3198-BLK1	Method Blank	Total	Soil	EPA 5035	
11L3198-BLK2	Method Blank	Total	Soil	EPA 5035	
11L3198-BS1	Lab Control Sample	Total	Soil	EPA 5035	
11L3198-BSD1	Lab Control Sample Dup	Total	Soil	EPA 5035	
11L3198-MS1	Matrix Spike	Total	Soil	EPA 5035	
11L3198-MSD1	Matrix Spike Duplicate	Total	Soil	EPA 5035	
NVL0585-03 - RE1	370 Aspen	Total	Soil	EPA 5035	

## QC Association Summary

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

### GCMS Volatiles (Continued)

#### Prep Batch: 11L3198\_P (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
NVL0585-03 - RE2	370 Aspen	Total	Soil	EPA 5035	

### GCMS Semivolatiles

#### Analysis Batch: 11L1216

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
11L1216-BLK1	Method Blank	Total	Soil	SW846 8270D	11L1216_P
11L1216-BS1	Lab Control Sample	Total	Soil	SW846 8270D	11L1216_P
11L1216-MS1	328 Ash-1	Total	Soil	SW846 8270D	11L1216_P
11L1216-MSD1	328 Ash-1	Total	Soil	SW846 8270D	11L1216_P
NVL0585-01	328 Ash-1	Total	Soil	SW846 8270D	11L1216_P
NVL0585-02	328 Ash-2	Total	Soil	SW846 8270D	11L1216_P
NVL0585-03	370 Aspen	Total	Soil	SW846 8270D	11L1216_P

#### Prep Batch: 11L1216\_P

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
11L1216-BLK1	Method Blank	Total	Soil	EPA 3550C	
11L1216-BS1	Lab Control Sample	Total	Soil	EPA 3550C	
11L1216-MS1	328 Ash-1	Total	Soil	EPA 3550C	
11L1216-MSD1	328 Ash-1	Total	Soil	EPA 3550C	
NVL0585-01	328 Ash-1	Total	Soil	EPA 3550C	
NVL0585-02	328 Ash-2	Total	Soil	EPA 3550C	
NVL0585-03	370 Aspen	Total	Soil	EPA 3550C	

### Extractions

#### Analysis Batch: 11L1897

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
11L1897-DUP1	Duplicate	Total	Soil	SW-846	11L1897_P
NVL0585-01	328 Ash-1	Total	Soil	SW-846	11L1897_P
NVL0585-02	328 Ash-2	Total	Soil	SW-846	11L1897_P
NVL0585-03	370 Aspen	Total	Soil	SW-846	11L1897_P

#### Prep Batch: 11L1897\_P

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
11L1897-DUP1	Duplicate	Total	Soil	% Solids	
NVL0585-01	328 Ash-1	Total	Soil	% Solids	
NVL0585-02	328 Ash-2	Total	Soil	% Solids	
NVL0585-03	370 Aspen	Total	Soil	% Solids	

## Lab Chronicle

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

**Client Sample ID: 328 Ash-1**

Date Collected: 11/29/11 13:45

Date Received: 12/05/11 08:30

**Lab Sample ID: NVL0585-01**

Matrix: Soil

Percent Solids: 85.3

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total	Prep	EPA 5035	RE1	0.794	11L3001_P	11/29/11 13:45	AAN	TAL NSH
Total	Analysis	SW846 8260B	RE1	1.00	U021759	12/12/11 17:00	KKK H	TAL NSH
Total	Prep	EPA 3550C		0.998	11L1216_P	12/09/11 10:02	MAH	TAL NSH
Total	Analysis	SW846 8270D		1.00	11L1216	12/10/11 18:32	BES	TAL NSH
Total	Prep	% Solids		1.00	11L1897_P	12/08/11 10:43	RRS	TAL NSH
Total	Analysis	SW-846		1.00	11L1897	12/09/11 09:10	RRS	TAL NSH

**Client Sample ID: 328 Ash-2**

Date Collected: 11/29/11 14:45

Date Received: 12/05/11 08:30

**Lab Sample ID: NVL0585-02**

Matrix: Soil

Percent Solids: 84

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total	Prep	EPA 5035		0.765	11L1207_P	11/29/11 14:45	AAN	TAL NSH
Total	Analysis	SW846 8260B		1.00	U021754	12/09/11 19:36	KKK H	TAL NSH
Total	Prep	EPA 3550C		0.977	11L1216_P	12/09/11 10:02	MAH	TAL NSH
Total	Analysis	SW846 8270D		1.00	11L1216	12/10/11 18:51	BES	TAL NSH
Total	Prep	% Solids		1.00	11L1897_P	12/08/11 10:43	RRS	TAL NSH
Total	Analysis	SW-846		1.00	11L1897	12/09/11 09:10	RRS	TAL NSH

**Client Sample ID: 370 Aspen**

Date Collected: 12/01/11 12:00

Date Received: 12/05/11 08:30

**Lab Sample ID: NVL0585-03**

Matrix: Soil

Percent Solids: 83.2

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total	Prep	EPA 5035	RE1	1.04	11L3198_P	12/01/11 12:00	AAN	TAL NSH
Total	Analysis	SW846 8260B	RE1	1.00	U021855	12/13/11 18:26	KKK H	TAL NSH
Total	Prep	EPA 5035	RE2	1.07	11L3198_P	12/01/11 12:00	AAN	TAL NSH
Total	Analysis	SW846 8260B	RE2	50.0	U021855	12/13/11 18:57	KKK H	TAL NSH
Total	Prep	EPA 3550C		0.970	11L1216_P	12/09/11 10:02	MAH	TAL NSH
Total	Analysis	SW846 8270D		1.00	11L1216	12/10/11 19:10	BES	TAL NSH
Total	Prep	% Solids		1.00	11L1897_P	12/08/11 10:43	RRS	TAL NSH
Total	Analysis	SW-846		1.00	11L1897	12/09/11 09:10	RRS	TAL NSH

### Laboratory References:

TAL NSH = TestAmerica Nashville, 2960 Foster Creighton Road, Nashville, TN 37204, TEL 800-765-0980

Method Summary

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

Method	Method Description	Protocol	Laboratory
SW-846	General Chemistry Parameters		TAL NSH
SW846 8260B	Volatile Organic Compounds by EPA Method 8260B		TAL NSH
SW846 8270D	Polyaromatic Hydrocarbons by EPA 8270D		TAL NSH

Protocol References:

Laboratory References:

TAL NSH = TestAmerica Nashville, 2960 Foster Creighton Road, Nashville, TN 37204, TEL 800-765-0980



## Certification Summary

Client: EEG - Small Business Group, Inc. (2449)  
Project/Site: [none]

TestAmerica Job ID: NVL0585

Laboratory	Authority	Program	EPA Region	Certification ID
TestAmerica Nashville		ACIL		393
TestAmerica Nashville	A2LA	ISO/IEC 17025		0453.07
TestAmerica Nashville	A2LA	WY UST		453.07
TestAmerica Nashville	AIHA - LAP	IHLAP		100790
TestAmerica Nashville	Alabama	State Program	4	41150
TestAmerica Nashville	Alaska	Alaska UST	10	UST-087
TestAmerica Nashville	Arizona	State Program	9	AZ0473
TestAmerica Nashville	Arkansas	State Program	6	88-0737
TestAmerica Nashville	California	NELAC	9	1168CA
TestAmerica Nashville	Canada (CALA)	Canada (CALA)		3744
TestAmerica Nashville	Colorado	State Program	8	N/A
TestAmerica Nashville	Connecticut	State Program	1	PH-0220
TestAmerica Nashville	Florida	NELAC	4	E87358
TestAmerica Nashville	Illinois	NELAC	5	200010
TestAmerica Nashville	Iowa	State Program	7	131
TestAmerica Nashville	Kansas	NELAC	7	E-10229
TestAmerica Nashville	Kentucky	Kentucky UST	4	19
TestAmerica Nashville	Kentucky	State Program	4	90038
TestAmerica Nashville	Louisiana	NELAC	6	30613
TestAmerica Nashville	Louisiana	NELAC	6	LA100011
TestAmerica Nashville	Maryland	State Program	3	316
TestAmerica Nashville	Massachusetts	State Program	1	M-TN032
TestAmerica Nashville	Minnesota	NELAC	5	047-999-345
TestAmerica Nashville	Mississippi	State Program	4	N/A
TestAmerica Nashville	Montana	MT DEQ UST	8	NA
TestAmerica Nashville	New Hampshire	NELAC	1	2963
TestAmerica Nashville	New Jersey	NELAC	2	TN965
TestAmerica Nashville	New York	NELAC	2	11342
TestAmerica Nashville	North Carolina	North Carolina DENR	4	387
TestAmerica Nashville	North Dakota	State Program	8	R-146
TestAmerica Nashville	Ohio	OVAP	5	CL0033
TestAmerica Nashville	Oklahoma	State Program	6	9412
TestAmerica Nashville	Oregon	NELAC	10	TN200001
TestAmerica Nashville	Pennsylvania	NELAC	3	68-00585
TestAmerica Nashville	Rhode Island	State Program	1	LAO00268
TestAmerica Nashville	South Carolina	State Program	4	84009
TestAmerica Nashville	South Carolina	State Program	4	84009
TestAmerica Nashville	Tennessee	State Program	4	2008
TestAmerica Nashville	Texas	NELAC	6	T104704077-09-TX
TestAmerica Nashville	USDA	USDA		S-48469
TestAmerica Nashville	Utah	NELAC	8	TAN
TestAmerica Nashville	Virginia	NELAC Secondary AB	3	460152
TestAmerica Nashville	Virginia	State Program	3	00323
TestAmerica Nashville	Washington	State Program	10	C789
TestAmerica Nashville	West Virginia	West Virginia DEP	3	219
TestAmerica Nashville	Wisconsin	State Program	5	998020430

Accreditation may not be offered or required for all methods and analytes reported in this package. Please contact your project manager for the laboratory's current list of certified methods and analytes.

## THE LEADER IN ENVIRONMENTAL TESTING

Phone: 615-726-0177  
Toll Free: 800-765-0980  
Fax: 615-726-3404

To assist us in using the proper analytical methods, is this work being conducted for regulatory purposes?

**Sampler Signature:**

Enforcement Action?	Yes	No
1. Is the information provided in the report accurate and complete?		
2. Is the information provided in the report reliable?		
3. Is the information provided in the report relevant?		
4. Is the information provided in the report timely?		
5. Is the information provided in the report clear and concise?		
6. Is the information provided in the report consistent with other information?		
7. Is the information provided in the report useful for decision making?		
8. Is the information provided in the report accessible to all who need it?		
9. Is the information provided in the report secure?		
10. Is the information provided in the report compliant with applicable laws and regulations?		

PO#: 1035

**Project #:**

Sample ID / Description		Date Sampled	Time Sampled	No. of Containers Shipped	Grab	Composite	Field Filtered	Use	Preservative	Matrix	Analyze For:
									HNO <sub>3</sub> (Red Label) HCl (Blue Label) NaOH (Orange Label) H <sub>2</sub> SO <sub>4</sub> Plastic (Yellow Label) H <sub>2</sub> SO <sub>4</sub> Glass (Yellow Label) None (Black Label) Other (Specify)	Groundwater Wastewater Drinking Water Sludge Soil Other (specify):	BTEX + Napht - 82600 PAH - 82700
328	Ash-1	11/29/11	1345	5	X				2	21	X X X
328	Ash-2	11/29/11	1445	5	X				2	21	X X X
320	Aspen	11/30/11	1200	5	X				2	21	X X X
<div> <div>Special Instructions:</div> <div> <div>Relinquished by: <i>[Signature]</i></div> <div>Relinquished by:</div> </div> <div> <div>Date: 12/2/11</div> <div>Date:</div> </div> <div> <div>Time: 1000</div> <div>Time:</div> </div> <div> <div>Method of Shipment: FEDEX</div> <div>Received by:</div> <div>Received by TestAmerica:</div> </div> <div> <div>Date:</div> <div>Date: 12/5/11</div> </div> <div> <div>Time:</div> <div>Time: 0830</div> </div> </div> <div> <div>Laboratory Comments:</div> <div>Temperature Upon Receipt:</div> <div>VOCs Free of Headspace?</div> </div>											

ATTACHMENT A

# UST Certificate of Disposal

## CONTRACTOR

Small Business Group, Inc.  
10179 Highway 78  
Ladson, SC 29456

TEL (843) 879-0403  
FAX (843) 879-0401

## TANK ID & LOCATION

UST 328Ash-1; 328 Ash Street, Laurel Bay Housing Area, MCAS Beaufort, S.C.

---

## DISPOSAL LOCATION

Coastal Auto Salvage Co., Inc.  
130 Laurel Bay Road  
Beaufort, S.C. 29906

### TYPE OF TANK

### SIZE (GAL)

Steel

280

---

## CLEANING/DISPOSAL METHOD

The tank and piping were unearthed, cut open, cleaned with a pressure washer, cut into sections, and recycled.

## DISPOSAL CERTIFICATION

I certify that the above tank, piping and equipment has been properly cleaned and disposed of.

T. E. McElree / 1/11/12  
(Name) (Date)





# NON-HAZARDOUS MANIFEST

<b>NON-HAZARDOUS MANIFEST</b>		1. Generator's US EPA ID No.		Manifest Doc No.		2. Page 1 of 1			
3. Generator's Mailing Address: MCAS, BEAUFORT LAUREL BAY HOUSING BEAUFORT, SC 29907		4. Generator's Phone 843-228-6461		Generator's Site Address (If different than mailing):		A. Manifest Number <b>WMNA</b> 00316827			
5. Transporter 1 Company Name EEG, INC.		6. US EPA ID Number		C. State Transporter's ID		D. Transporter's Phone 843-879-0411			
7. Transporter 2 Company Name		8. US EPA ID Number		E. State Transporter's ID		F. Transporter's Phone			
9. Designated Facility Name and Site Address HICKORY HILL LANDFILL 2621 LOW COUNTRY ROAD RIDGELAND, SC 29936		10. US EPA ID Number		G. State Facility ID		H. State Facility Phone 843-987-4643			
GENERATOR	11. Description of Waste Materials		12. Containers		13. Total Quantity	14. Unit Wt./Vol.	1. Misc. Comments		
	a. HEATING OIL TANKS FILLED WITH SAND WM Profile # 102655SC		No.	Type					
	b. WM Profile #								
	c. WM Profile #								
	d. WM Profile #								
	J. Additional Descriptions for Materials Listed Above		K. Disposal Location						
		Cell		Level					
		Grid							
15. Special Handling Instructions and Additional Information 457's from 2) 338 Ash-2 4) 370 Aspen ✓ 1) 305 Ash ✓ 3) 328 Ash-2 ✓ 5) 383 Aspen-2 ✓									
Purchase Order #		EMERGENCY CONTACT / PHONE NO.:							
16. GENERATOR'S CERTIFICATE: I hereby certify that the above-described materials are not hazardous wastes as defined by CFR Part 261 or any applicable state law, have been fully and accurately described, classified and packaged and are in proper condition for transportation according to applicable regulations.									
Printed Name W.G. [Signature]		Signature "On behalf of" [Signature]				Month 12	Day 7	Year 11	
TRANSPORTER	17. Transporter 1 Acknowledgement of Receipt of Materials		Printed Name James Baldwin		Signature James Baldwin		Month 1	Day 4	Year 12
	18. Transporter 2 Acknowledgement of Receipt of Materials		Printed Name		Signature		Month	Day	Year
FACILITY	19. Certificate of Final Treatment/Disposal I certify, on behalf of the above listed treatment facility, that to the best of my knowledge, the above-described waste was managed in compliance with all applicable laws, regulations, permits and licenses on the dates listed above.								
	20. Facility Owner or Operator: Certification of receipt of non-hazardous materials covered by this manifest.								
Printed Name Toni Cotfield		Signature Toni Cotfield				Month 1	Day 4	Year 12	

White- TREATMENT, STORAGE, DISPOSAL FACILITY COPY

Blue- GENERATOR #2 COPY

Yellow- GENERATOR #1 COPY

Pink- FACILITY USE ONLY

Gold- TRANSPORTER #1 COPY

**Appendix C**  
**Laboratory Analytical Report - Groundwater**

# Volatile Organic Compounds by GC/MS

Client: <b>AECOM - Resolution Consultants</b>	Laboratory ID: <b>SC03027-011</b>
Description: <b>BEALB328TW02WG20170302</b>	Matrix: <b>Aqueous</b>
Date Sampled: <b>03/02/2017 1045</b>	
Date Received: <b>03/03/2017</b>	

Run	Prep Method	Analytical Method	Dilution	Analysis Date	Analyst	Prep Date	Batch
1	5030B	8260B	1	03/07/2017 1255	PMV		36403

Parameter	CAS Number	Analytical Method	Result	Q	LOQ	LOD	DL	Units	Run
Benzene	71-43-2	8260B	0.80	U	1.0	0.80	0.40	ug/L	1
Ethylbenzene	100-41-4	8260B	0.80	U	1.0	0.80	0.40	ug/L	1
<b>Naphthalene</b>	<b>91-20-3</b>	<b>8260B</b>	<b>2.6</b>		<b>1.0</b>	0.80	<b>0.40</b>	<b>ug/L</b>	<b>1</b>
Toluene	108-88-3	8260B	0.80	U	1.0	0.80	0.40	ug/L	1
Xylenes (total)	1330-20-7	8260B	0.80	U	1.0	0.80	0.40	ug/L	1

Surrogate	Q	Run 1 % Recovery	Acceptance Limits
Bromofluorobenzene		106	85-114
Dibromofluoromethane		108	80-119
1,2-Dichloroethane-d4		99	81-118
Toluene-d8		98	89-112

PQL = Practical quantitation limit      B = Detected in the method blank      E = Quantitation of compound exceeded the calibration range      H = Out of holding time      Q = Surrogate failure  
 ND = Not detected at or above the MDL      J = Estimated result < PQL and ≥ MDL      P = The RPD between two GC columns exceeds 40%      N = Recovery is out of criteria      L = LCS/LCSD failure  
 Where applicable, all soil sample analysis are reported on a dry weight basis unless flagged with a "W"      S = MS/MSD failure

Shealy Environmental Services, Inc.  
 106 Vantage Point Drive   West Columbia, SC 29172   (803) 791-9700   Fax (803) 791-9111   www.shealylab.com

# Semivolatile Organic Compounds by GC/MS

Client: <b>AECOM - Resolution Consultants</b>	Laboratory ID: <b>SC03027-011</b>
Description: <b>BEALB328TW02WG20170302</b>	Matrix: <b>Aqueous</b>
Date Sampled: <b>03/02/2017 1045</b>	
Date Received: <b>03/03/2017</b>	

Run	Prep Method	Analytical Method	Dilution	Analysis Date	Analyst	Prep Date	Batch
1	3520C	8270D	1	03/11/2017 0107	RBH	03/05/2017 1656	36264

Parameter	CAS Number	Analytical Method	Result	Q	LOQ	LOD	DL	Units	Run
Benzo(a)anthracene	56-55-3	8270D	0.10	U	0.20	0.10	0.040	ug/L	1
Benzo(b)fluoranthene	205-99-2	8270D	0.10	U	0.20	0.10	0.040	ug/L	1
Benzo(k)fluoranthene	207-08-9	8270D	0.10	U	0.20	0.10	0.040	ug/L	1
Chrysene	218-01-9	8270D	0.10	U	0.20	0.10	0.040	ug/L	1
Dibenzo(a,h)anthracene	53-70-3	8270D	0.10	U	0.20	0.10	0.040	ug/L	1

Surrogate	Q	Run 1 % Recovery	Acceptance Limits
Nitrobenzene-d5		68	44-120
2-Fluorobiphenyl		64	44-119
Terphenyl-d14		84	50-134

PQL = Practical quantitation limit      B = Detected in the method blank      E = Quantitation of compound exceeded the calibration range      H = Out of holding time      Q = Surrogate failure  
 ND = Not detected at or above the MDL      J = Estimated result < PQL and ≥ MDL      P = The RPD between two GC columns exceeds 40%      N = Recovery is out of criteria      L = LCS/LCSD failure  
 Where applicable, all soil sample analysis are reported on a dry weight basis unless flagged with a "W"      S = MS/MSD failure

Shealy Environmental Services, Inc.  
 106 Vantage Point Drive   West Columbia, SC 29172   (803) 791-9700   Fax (803) 791-9111   www.shealylab.com

## **Appendix D**

### **Regulatory Correspondence**





August 24, 2016

Commanding Officer  
Attention: NREAO Mr. William A. Drawdy  
United State Marine Corps Air Station  
Post Office Box 55001  
Beaufort, SC 29904-5001

RE: IGWA  
Laurel Bay Underground Tank Assessment Reports

Dear Mr. Drawdy:

The South Carolina Department of Health and Environmental Control (the Department) received the Underground Storage Tanks (USTs) Assessment Reports for the addresses listed in the attachment. The regulatory authority for the investigation and cleanup of releases from these tank systems is the South Carolina Pollution Control Act (S.C. Code Ann. §48-1-10 et seq., as amended).

The Department has reviewed the referenced reports. The submitted analytical results indicate that petroleum constituents are above established Risk-Based Screening Levels and additional investigation is warranted. Specifically, the Department requests that a groundwater sampling proposal be generated to determine if there has been an impact to groundwater at these sites.

Please note that the Department's decision is based on information provided by the Marine Corps Air Station (MCAS) to date. Any information found to be contradictory to this decision may require additional action. Furthermore, the Department retains the right to request further investigation if deemed necessary.

If you have any questions, please contact me at [petruslb@dhec.sc.gov](mailto:petruslb@dhec.sc.gov) or 803-898-0294.

Sincerely,

Laurel Petrus, Environmental Engineer Associate  
RCRA Federal Facilities Section

Cc: Russell Berry, EQC Region 8 (via email)  
Shawn Dolan, Resolution Consultants (via email)  
Bryan Beck, NAVFAC MIDATLANTIC (via email)  
Craig Ehde (via email)

Attachment to: Petrus to Drawdy, August 24, 2016

Subject: IGWA, Laurel Bay Underground Tank Assessment Reports

Draft Final Initial Groundwater Investigation Report for (41 addresses)

Monitoring Well Investigation Recommendation	
122 Banyan	905 Barracuda
159 Cypress Tank 2	921 Barracuda
221 Cypress	935 Albacore
283 Birch Tank 2	946 Albacore
328 Ash Tank 2	1037 Iris
346 Ash	1039 Iris
359 Aspen	1110 Iris
370 Aspen	1134 Iris
377 Aspen	1143 Iris
409 Elderberry	1202 Cardinal
486 Laurel Bay	1212 Cardinal
515 Laurel Bay	1222 Cardinal
542 Laurel Bay	1224 Cardinal
593 Aster	1226 Dove
630 Dahlia	1236 Dove
693 Camellia	1245 Dove
723 Blue Bell	1247 Dove
774 Althea	1274 Albatross
860 Dolphin	1319 Albatross
873 Cobia	1337 Albatross
883 Cobia	





July 27, 2017

Commanding Officer  
Attention: NREAO Mr. William A. Drawdy  
United State Marine Corps Air Station  
Post Office Box 55001  
Beaufort, SC 29904-5001

RE: Draft Final Initial Groundwater Investigation Report, February and March 2017

Dear Mr. Drawdy:

The South Carolina Department of Health and Environmental Control (DHEC) received groundwater data from temporary monitoring well installations in the Draft Final Groundwater Investigation Report, Laurel Bay Military Housing Area for the fifty two (52) addresses shown in the attachment. The regulatory authority for the investigation and cleanup of releases from these tank systems is the South Carolina Pollution Control Act (S.C. Code Ann. §48-1-10 et seq., as amended).

Per DHEC's request, groundwater samples were collected from the attached referenced addresses. DHEC reviewed the groundwater data and previous investigations and it agrees with the conclusions and recommendations included in the document. To further assess the impact to groundwater, permanent groundwater monitoring wells should be installed at the three (3) stated addresses. For the remaining forty nine (49) addresses, there is no indication of contamination on the property and therefore no further investigation is required at this time.

Please note that DHEC's decision is based on information provided by the Marine Corps Air Station (MCAS) to date. Any information found to be contradictory to this decision may require additional action. Furthermore, DHEC retains the right to request further investigation if deemed necessary.

If you have any questions, please contact me at [petruslb@dhec.sc.gov](mailto:petruslb@dhec.sc.gov) or 803-898-0294.

Sincerely,

Laurel Petrus, Environmental Engineer Associate  
Bureau of Land and Waste Management

Cc: Russell Berry, EQC Region 8  
Shawn Dolan, Resolution Consultants  
Bryan Beck, NAVFAC MIDLANT

Attachment to: Petrus to Drawdy                      Dated July 27, 2017

Draft Final Initial Groundwater Investigation Report for (52 addresses)

Permanent Well Installation recommendation (3 Addresses):

---

- 254 Beech Street (110 ug/L)
- 268 Beech Street (28 ug/L)
- 774 Althea Street (35 ug/L)

No Further Action recommendation (49 addresses):

- 113 Birch Drive
- 121 Banyan Drive
- 122 Banyan Drive
- 159 Cypress Street
- 221 Cypress Street
- 274 Birch Drive
- 279 Birch Drive
- 283 Birch Drive
- 328 Ash Street
- 346 Ash Street
- 359 Aspen Street
- 370 Aspen Street
- 377 Aspen Street
- 409 Elderberry Drive
- 465 Dogwood Drive
- 480 Laurel Bay Boulevard
- 486 Laurel Bay Boulevard
- 515 Laurel Bay Boulevard
- 542 Laurel Bay Boulevard
- 593 Aster Street
- 630 Dahlia Drive
- 641 Dahlia Drive
- 693 Camelia Drive
- 723 Bluebell Lane
- 860 Dolphin Street
- 873 Cobia Drive
- 883 Cobia Drive
- 905 Barracuda Drive
- 921 Barracuda Drive
- 935 Albacore Street
- 946 Albacore Street
- 1037 Iris Lane
- 1039 Iris Lane
- 1110 Iris Lane
- 1134 Iris Lane
- 1143 Iris Lane
- 1177 Bobwhite Drive
- 1202 Cardinal Lane
- 1212 Cardinal Lane
- 1222 Cardinal Lane
- 1224 Cardinal Lane
- 1226 Dove Lane
- 1236 Dove Lane
- 1245 Dove Lane
- 1247 Dove Lane
- 1274 Albatross Drive
- 1319 Albatross Drive
- 1337 Albatross Drive
- 1346 Cardinal Lane