

SUMMARY REPORT
43 BARRACUDA DRIVE (FORMERLY 904 BARRACUDA DRIVE)
LAUREL BAY MILITARY HOUSING AREA
MARINE CORPS AIR STATION BEAUFORT
BEAUFORT, SC

Revision: 0
Prepared for:

Department of the Navy
Naval Facilities Engineering Command, Mid-Atlantic
9324 Virginia Avenue
Norfolk, Virginia 23511-3095

and



Naval Facilities Engineering Command Atlantic
9324 Virginia Avenue
Norfolk, Virginia 23511-3095

JUNE 2021

SUMMARY REPORT
43 BARRACUDA DRIVE (FORMERLY 904 BARRACUDA DRIVE)
LAUREL BAY MILITARY HOUSING AREA
MARINE CORPS AIR STATION BEAUFORT
BEAUFORT, SC

Revision: 0
Prepared for:

Department of the Navy
Naval Facilities Engineering Command, Mid- Atlantic
9324 Virginia Avenue
Norfolk, Virginia 23511-3095

and



Naval Facilities Engineering Command Atlantic

9324 Virginia Avenue
Norfolk, Virginia 23511-3095

Prepared by:



CDM - AECOM Multimedia Joint Venture
10560 Arrowhead Drive, Suite 500
Fairfax, Virginia 22030

Contract Number: N62470-14-D-9016
CTO WE52
JUNE 2021

Table of Contents

1.0	INTRODUCTION.....	1
1.1	BACKGROUND INFORMATION.....	1
1.2	UST REMOVAL AND ASSESSMENT PROCESS.....	2
2.0	SAMPLING ACTIVITIES AND RESULTS.....	3
2.1	UST REMOVAL AND SOIL SAMPLING	3
2.2	SOIL ANALYTICAL RESULTS.....	4
3.0	PROPERTY STATUS	4
4.0	REFERENCES.....	4

Table

Table 1	Laboratory Analytical Results - Soil
---------	--------------------------------------

Appendices

Appendix A	Multi-Media Selection Process for LBMH
Appendix B	UST Assessment Report
Appendix C	Regulatory Correspondence

List of Acronyms

bgs	below ground surface
BTEX	benzene, toluene, ethylbenzene, and xylenes
CTO	Contract Task Order
COPC	constituents of potential concern
IDIQ	Indefinite Delivery, Indefinite Quantity
IGWA	Initial Groundwater Assessment
JV	Joint Venture
LBMH	Laurel Bay Military Housing
MCAS	Marine Corps Air Station
NAVFAC Mid-Lant	Naval Facilities Engineering Command Mid-Atlantic
NFA	No Further Action
PAH	polynuclear aromatic hydrocarbon
QAPP	Quality Assurance Program Plan
RBSL	risk-based screening level
SCDHEC	South Carolina Department of Health and Environmental Control
Site	LBMH area at MCAS Beaufort, South Carolina
UST	underground storage tank
VISL	vapor intrusion screening level

1.0 INTRODUCTION

The CDM - AECOM Multimedia Joint Venture (JV) was contracted by the Naval Facilities Engineering Command, Mid-Atlantic (NAVFAC Mid-Lant) to provide reporting services for the heating oil underground storage tanks (USTs) located in Laurel Bay Military Housing (LBMH) area at the Marine Corps Air Station (MCAS) Beaufort, South Carolina (Site). This work has been awarded under Contract Task Order (CTO) WE52 of the Indefinite Delivery, Indefinite Quantity (IDIQ) Multimedia Environmental Compliance Contract (Contract No. N62470-14-D-9016).

As of January 2014, the LBMH addresses were re-numbered to comply with the E-911 emergency response addressing system; however, in order to remain consistent with historical sampling and reporting for LBMH area, the residences will continue to be referenced with their original address numbers in sample nomenclature and reporting documents.

This report summarizes the results the environmental investigation activities associated with the storage of home heating oil and the potential release of petroleum constituents at the referenced property. Based on the results of the investigation, a No Further Action (NFA) determination has been made by the South Carolina Department of Health and Environmental Control (SCDHEC) for 43 Barracuda Drive (Formerly 904 Barracuda Drive). This NFA determination indicates that there are no unacceptable risks to human health or the environment for the petroleum constituents associated with the home heating oil USTs. The following information is included in this report:

- Background information;
- Sampling activities and results; and
- A determination of the property status.

1.1 Background Information

The LBMH area is located approximately 3.5 miles west of MCAS Beaufort. The area is approximately 970 acres in size and serves as an enlisted and officer family housing area. The area is configured with single family and duplex residential structures, and includes recreation, open space, and community facilities. The community includes approximately 1,300 housing units, including legacy Capehart style homes and newer duplex style homes. The housing area

is bordered on the west by salt marshes and the Broad River, and to the north, east and south by uplands. Forested areas lie along the northern and northeastern borders.

Capehart style homes within the LBMH area were formerly heated using heating oil stored in USTs at each residence. There were 1,100 Capehart style housing units in the LBMH area. The newer duplex homes within the LBMH area never utilized heating oil tanks. Heating oil has not been used at Laurel Bay since the mid-1980s. As was the accepted practice at the time, USTs were drained, filled with dirt, capped, and left in place when they were removed from service. Residential USTs are not regulated in the State of South Carolina (i.e., there are no federal or state laws governing installation, management, or removal).

In 2007, MCAS Beaufort began a voluntary program to remove the unregulated, residential USTs and conduct sampling activities to determine if, and to what extent, petroleum constituents may have impacted the surrounding environment. MCAS Beaufort coordinated with SCDHEC to develop removal procedures that were consistent with procedural requirements for regulated USTs. All tank removal activities and follow-on actions are conducted in coordination with SCDHEC. To date, all known USTs have been removed from all residential properties within the LBMH area.

1.2 UST Removal and Assessment Process

During the UST removal process, a soil sample was collected from beneath the UST excavations (approximately 4 to 6 feet [ft] below ground surface [bgs]) and analyzed for a predetermined list of constituents of potential concern (COPCs) associated with the petroleum compounds found in home heating oil. These COPCs, derived from the *Quality Assurance Program Plan (QAPP) for the Underground Storage Tank Management Division, Revision 3.1* (SCDHEC, 2016) and the *Underground Storage Tank Assessment Instructions for Permanent Closure and Change-In-Service*, (SCDHEC, 2018), are as follows:

- benzene, toluene, ethylbenzene, and xylenes (BTEX),
- naphthalene, and
- five select polynuclear aromatic hydrocarbon (PAHs): benzo(a)anthracene, benzo(b)fluoranthene, benzo(k)fluoranthene, chrysene and dibenz(a,h)anthracene.

Soil sample results were submitted by MCAS Beaufort to SCDHEC utilizing SCDHEC's UST Assessment Report form. In accordance with SCDHEC's *QAPP for the UST Management*

Division (SCDHEC, 2016), the soil screening levels consists of SCDHEC risk-based screening levels (RBSLs). It should be noted that the RBSLs for select PAHs were revised in Revision 2.0 of the QAPP (SCDHEC, 2013) and were revised again in Revision 3.0 (SCDHEC, 2015). The screening levels used for evaluation at each site were those levels that were in effect at the time of reporting and review by SCDHEC.

The results of the soil sampling at each former UST location were used to determine if a potential for groundwater contamination exists (i.e., soil results greater than RBSLs) and subsequently to select properties for follow-up initial groundwater assessment (IGWA) sampling. The results of the IGWA sampling (if necessary) are used to determine the presence or absence of the aforementioned COPCs in groundwater and identify whether former UST locations will require additional delineation of COPCs in groundwater. In order to delineate the extent of impact to groundwater, permanent wells are installed and a sampling program is established for those former UST locations where IGWA sampling has indicated the presence of COPCs in excess of the SCDHEC RBSLs for groundwater. Groundwater analytical results are also compared to the site specific groundwater vapor intrusion screening levels (VISLs) to evaluate the potential for vapor intrusion and the necessity for an investigation associated with this media. A multi-media investigation selection process tree, applicable to the LBMH UST investigations, is presented as Appendix A.

2.0 SAMPLING ACTIVITIES AND RESULTS

The following section presents the sampling activities and associated results for 43 Barracuda Drive (Formerly 904 Barracuda Drive). Details regarding the soil investigation at this site are provided in the *SCDHEC UST Assessment Report – 904 Barracuda Drive* (MCAS Beaufort, 2011). The UST Assessment Report is provided in Appendix B.

2.1 UST Removal and Soil Sampling

On January 4, 2011, a single 280 gallon heating oil UST was removed from the front yard adjacent to the porch area at 43 Barracuda Drive (Formerly 904 Barracuda Drive). The former UST location is indicated on Figures 2 and 3 of the UST Assessment Report (Appendix B). The UST was removed and properly disposed of (i.e., shipped offsite for recycling or transported to a landfill). There was no visual evidence (i.e., staining or sheen) of petroleum impact at the time of the UST removal. According to the UST Assessment Report (Appendix B), the depth to the base of the UST was 7'0" bgs and a single soil sample was collected from that depth. The

sample was collected from the fill port side of the former UST to represent a worst case scenario.

Following UST removal, a soil sample was collected from the base of the excavation and shipped to an offsite laboratory for analysis of the petroleum COPCs. Sampling was performed in accordance with applicable South Carolina regulation R.61-92, Part 280 (SCDHEC, 2017) and assessment guidelines.

2.2 Soil Analytical Results

A summary of the laboratory analytical results and SCDHEC RBSLs is presented in Table 1. A copy of the laboratory analytical data report is included in the UST Assessment Report presented in Appendix B. The laboratory analytical data report includes the soil results for the additional PAHs that were analyzed, but do not have associated RBSLs.

The soil sample results were submitted by MCAS Beaufort to SCDHEC utilizing SCDHEC's UST Assessment Report form (Appendix B). The results of the soil sampling at the former UST location were used by MCAS Beaufort, in consultation with SCDHEC, to determine a path forward (i.e., additional sampling or NFA) for the property. The soil results collected from 43 Barracuda Drive (Formerly 904 Barracuda Drive) were less than the SCDHEC RBSLs, which indicated the subsurface was not impacted by COPCs associated with the former UST at concentrations that presented a potential risk to human health and the environment.

3.0 PROPERTY STATUS

Based on the analytical results for soil, SCDHEC made the determination that NFA was required for 43 Barracuda Drive (Formerly 904 Barracuda Drive). This NFA determination was obtained in a letter dated July 1, 2015. SCDHEC's NFA letter is provided in Appendix C.

4.0 REFERENCES

Marine Corps Air Station Beaufort, 2011. *South Carolina Department of Health and Environmental Control (SCDHEC) Underground Storage Tank Assessment Report – 904 Barracuda Drive, Laurel Bay Military Housing Area*, April 2011.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2013. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 2.0*, April 2013.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2015. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.0*, May 2015.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2016. *Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.1*, February 2016.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2017. *R.61-92, Part 280, Underground Storage Tank Control Regulations*, March 2017.

South Carolina Department of Health and Environmental Control Bureau of Land and Waste Management, 2018. *Underground Storage Tank Assessment Instructions for Permanent Closure and Change-In-Service*, March 2018.

Table

Table 1
Laboratory Analytical Results - Soil
43 Barracuda Drive (Formerly 904 Barracuda Drive)
Laurel Bay Military Housing Area
Marine Corps Air Station Beaufort
Beaufort, South Carolina

Constituent	SCDHEC RBSLs ⁽¹⁾	Results Sample Collected 01/04/11
Volatile Organic Compounds Analyzed by EPA Method 8260B (mg/kg)		
Benzene	0.003	ND
Ethylbenzene	1.15	ND
Naphthalene	0.036	ND
Toluene	0.627	ND
Xylenes, Total	13.01	ND
Semivolatile Organic Compounds Analyzed by EPA Method 8270D (mg/kg)		
Benzo(a)anthracene	0.66	ND
Benzo(b)fluoranthene	0.66	ND
Benzo(k)fluoranthene	0.66	ND
Chrysene	0.66	ND
Dibenz(a,h)anthracene	0.66	ND

Notes:

⁽¹⁾ South Carolina Risk-Based Screening Levels from the Quality Assurance Program Plan for the Underground Storage Tank Management Division, Revision 3.0 and 3.1 (SCDHEC, May 2015 and SCDHEC, February 2016) and the Underground Storage Tank Assessment Guidelines (SCDHEC, February 2006).

Bold font indicates the analyte was detected.

Bold font and shading indicates the concentration exceeds the SCDHEC RBSL.

EPA - United States Environmental Protection Agency

mg/kg - milligram per kilogram

ND - not detected at the reporting limit (or method detection limit if shown on the laboratory report). The laboratory report is provided in Appendix B.

RBSL - Risk-Based Screening Level

SCDHEC - South Carolina Department Of Health and Environmental Control

Appendix A
Multi-Media Selection Process for LBMH



Appendix A - Multi-Media Selection Process for LBMH

Appendix B
UST Assessment Report

South Carolina Department of Health and Environmental Control (SCDHEC)
Underground Storage Tank (UST) Assessment Report

Date Received

State Use Only

Submit Completed Form To:
UST Program
SCDHEC
2600 Bull Street
Columbia, South Carolina 29201
Telephone (803) 896-7957

I. OWNERSHIP OF UST (S)

MCAS Beaufort, Commanding Officer Attn: NREAO (Craig Ehde)

Owner Name (Corporation, Individual, Public Agency, Other)

P.O. Box 55001

Mailing Address

Beaufort,

South Carolina

29904-5001

City

State

Zip Code

843

228-7317

Craig Ehde

Area Code

Telephone Number

Contact Person

II. SITE IDENTIFICATION AND LOCATION

Permit I.D. #

Laurel Bay Military Housing Area, Marine Corps Air Station, Beaufort, SC

Facility Name or Company Site Identifier

904 Barracuda Street, Laurel Bay Military Housing Area

Street Address or State Road (as applicable)

Beaufort,

Beaufort

City

County

III. INSURANCE INFORMATION

Insurance Statement

The petroleum release reported to DHEC on _____ at Permit ID Number _____ may qualify to receive state monies to pay for appropriate site rehabilitation activities. Before participation is allowed in the State Clean-up fund, written confirmation of the existence or non-existence of an environmental insurance policy is required. **This section must be completed.**

Is there now, or has there ever been an insurance policy or other financial mechanism that covers this UST release? **YES**____ **NO**____ (check one)

If you answered **YES** to the above question, please complete the following information:

My policy provider is: _____

The policy deductible is: _____

The policy limit is: _____

If you have this type of insurance, please include a copy of the policy with this report.

IV. REQUEST FOR SUPERB FUNDING

I **DO** / **DO NOT** wish to participate in the SUPERB Program. (Circle one.)

V. CERTIFICATION (To be signed by the UST owner)

I certify that I have personally examined and am familiar with the information submitted in this and all attached documents; and that based on my inquiry of those individuals responsible for obtaining this information, I believe that the submitted information is true, accurate, and complete.

Name (Type or print.)

Signature

To be completed by Notary Public:

Sworn before me this _____ day of _____, 20____

(Name)

Notary Public for the state of _____
Please affix State seal if you are commissioned outside South Carolina

VI. UST INFORMATION

- A. Product...(ex. Gas, Kerosene).....
- B. Capacity...(ex. 1k, 2k).....
- C. Age.....
- D. Construction Material...(ex. Steel, FRP).....
- E. Month/Year of Last Use.....
- F. Depth (ft.) To Base of Tank.....
- G. Spill Prevention Equipment Y/N.....
- H. Overfill Prevention Equipment Y/N.....
- I. Method of Closure Removed/Filled.....
- J. Date Tanks Removed/Filled.....
- K. Visible Corrosion or Pitting Y/N.....
- L. Visible Holes Y/N.....

904 Barracuda				
Heating oil				
280 gal				
Late 1950s				
Steel				
Mid 1980s				
7'				
No				
No				
Removed				
1/4/11				
Yes				
Yes				

- M. Method of disposal for any USTs removed from the ground (attach disposal manifests)
UST 904Barracuda was removed from the ground, and disposed at a
Subtitle "D" landfill. See Attachment "A".
-
- N. Method of disposal for any liquid petroleum, sludges, or wastewaters removed from the USTs (attach disposal manifests)
UST 904Barracuda had been previously filled with sand by others.
-
- O. If any corrosion, pitting, or holes were observed, describe the location and extent for each UST
Corrosion, pitting and holes were found throughout the tank.

VII. PIPING INFORMATION

A. Construction Material..(ex. Steel, FRP).....

B. Distance from UST to Dispenser.....

C. Number of Dispensers.....

D. Type of System Pressure or Suction.....

E. Was Piping Removed from the Ground? Y/N

F. Visible Corrosion or Pitting Y/N.....

G. Visible Holes Y/N.....

H. Age.....

I. If any corrosion, pitting, or holes were observed, describe the location and extent for each piping run.

904				
Barracuda				
Steel & Copper				
N/A				
N/A				
Suction				
Yes				
Yes				
No				
Late 1950s				

Corrosion and pitting were found on the surface of the steel vent pipe. Copper supply and return lines were sound.

VIII. BRIEF SITE DESCRIPTION AND HISTORY

The USTs at the residences are constructed of single wall steel and formerly contained fuel oil for heating. These USTs were installed in the late 1950s and last used in the mid 1980s.

IX. SITE CONDITIONS

	Yes	No	Unk
A. Were any petroleum-stained or contaminated soils found in the UST excavation, soil borings, trenches, or monitoring wells? If yes, indicate depth and location on the site map.		X	
B. Were any petroleum odors detected in the excavation, soil borings, trenches, or monitoring wells? If yes, indicate location on site map and describe the odor (strong, mild, etc.)		X	
C. Was water present in the UST excavation, soil borings, or trenches? If yes, how far below land surface (indicate location and depth)?		X	
D. Did contaminated soils remain stockpiled on site after closure? If yes, indicate the stockpile location on the site map. Name of DHEC representative authorizing soil removal:		X	
E. Was a petroleum sheen or free product detected on any excavation or boring waters? If yes, indicate location and thickness.		X	

X. SAMPLE INFORMATION

A. SCDHEC Lab Certification Number 84009001

B.

Sample #	Location	Sample Type (Soil/Water)	Soil Type (Sand/Clay)	Depth*	Date/Time of Collection	Collected by	OVA #
904 B'cuda	Excav at fill end	Soil	Sandy	7'	1/4/11 1600 hrs	P. Shaw	
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							

* = Depth Below the Surrounding Land Surface

XI. SAMPLING METHODOLOGY

Provide a detailed description of the methods used to collect and store the samples. Also include the preservative used for each sample. Please use the space provided below.

Sampling was performed in accordance with SC DHEC R.61-92 Part 280 and SC DHEC Assessment Guidelines. Sample containers were prepared by the testing laboratory. The grab method was utilized to fill the sample containers leaving as little head space as possible and immediately capped. Soil samples were extracted from area below tank. The samples were marked, logged, and immediately placed in a sample cooler packed with ice to maintain an approximate temperature of 4 degrees Centigrade. Tools were thoroughly cleaned and decontaminated with the seven step decon process after each use. The samples remained in custody of SBG-EEG, Inc. until they were transferred to Test America Incorporated for analysis as documented in the Chain of Custody Record.


XII. RECEPTORS

	Yes	No
A. Are there any lakes, ponds, streams, or wetlands located within 1000 feet of the UST system? If yes, indicate type of receptor, distance, and direction on site map.		X
B. Are there any public, private, or irrigation water supply wells within 1000 feet of the UST system? If yes, indicate type of well, distance, and direction on site map.		X
C. Are there any underground structures (e.g., basements) Located within 100 feet of the UST system? If yes, indicate type of structure, distance, and direction on site map.		X
D. Are there any underground utilities (e.g., telephone, electricity, gas, water, sewer, storm drain) located within 100 feet of the UST system that could potentially come in contact with the contamination? *Sewer and water If yes, indicate the type of utility, distance, and direction on the site map.	*X	
E. Has contaminated soil been identified at a depth less than 3 feet below land surface in an area that is not capped by asphalt or concrete? If yes, indicate the area of contaminated soil on the site map.		X


XIII. SITE MAP

You must supply a scaled site map. It should include all buildings, road names, utilities, tank and dispenser island locations, labeled sample locations, extent of excavation, and any other pertinent information.

(Attach Site Map Here)





904 BARRACUDA ST.



SBG-EEG, Inc. 398 E. 5th North Street, Suite C Summerville SC 29483-6954 Ph. (843) 875-1930
Drawn By: L. DiAsio
Dwg Date: JAN 2011

**FIGURE 1: LOCATION MAP
904 BARRACUDA STREET
LAUREL BAY, BEAUFORT SC**



SBG-EEG

398 E. 5 NORTH ST., SUITE C
SUMMERVILLE, SC
29483-6954

FIGURE 2 SITE MAP
904 BARRACUDA ST., LAUREL BAY
MCAS BEAUFORT SC

SCALE: GRAPHIC

DWG DATE JAN 2011

904 BARRACUDA STREET



WATER

SEWER

CONCRETE
PORCH

EXCAVATION

FILL END


UST 904BARRACUDA

SOIL SAMPLE
904 BARRACUDA

ASPHALT DRIVEWAY

GRASS

GRAPHIC SCALE



UST 904BARRACUDA WAS
48" BELOW GRADE.

SBG-EEG

398 E. 5 NORTH ST., SUITE C
SUMMERVILLE, SC
29483-6954

FIGURE 3 UST SAMPLE LOCATIONS
904 BARRACUDA ST., LAUREL BAY
MCAS BEAUFORT SC

SCALE: GRAPHIC

DWG DATE JAN 2011



Picture 1: Location of UST 904Barracuda.



Picture 2: Tank pit after removal.

XIV. SUMMARY OF ANALYSIS RESULTS

Enter the soil analytical data for each soil boring for all COC in the table below and on the following page.

CoC	UST	904Barracuda						
Benzene		ND						
Toluene		ND						
Ethylbenzene		ND						
Xylenes		ND						
Naphthalene		ND						
Benzo (a) anthracene		ND						
Benzo (b) fluoranthene		ND						
Benzo (k) fluoranthene		ND						
Chrysene		ND						
Dibenz (a, h) anthracene		ND						
TPH (EPA 3550)								

CoC								
Benzene								
Toluene								
Ethylbenzene								
Xylenes								
Naphthalene								
Benzo (a) anthracene								
Benzo (b) fluoranthene								
Benzo (k) fluoranthene								
Chrysene								
Dibenz (a, h) anthracene								
TPH (EPA 3550)								

SUMMARY OF ANALYSIS RESULTS (cont'd)

Enter the ground water analytical data for each sample for all CoC in the table below. If free product is present, indicate the measured thickness to the nearest 0.01 feet.

CoC	RBSL (µg/l)	W-1	W-2	W -3	W -4
Free Product Thickness	None				
Benzene	5				
Toluene	1,000				
Ethylbenzene	700				
Xylenes	10,000				
Total BTEX	N/A				
MTBE	40				
Naphthalene	25				
Benzo (a) anthracene	10				
Benzo (b) flouranthene	10				
Benzo (k) flouranthene	10				
Chrysene	10				
Dibenz (a, h) anthracene	10				
EDB	.05				
1,2-DCA	5				
Lead	Site specific				

XV. ANALYTICAL RESULTS

You must submit the laboratory report and chain-of-custody form for the samples. These samples must be analyzed by a South Carolina certified laboratory.

(Attach Certified Analytical Results and Chain-of-Custody Here)
(Please see Form #4)

January 21, 2011 4:44:18PM

Client: EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn: Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Nbr: [none]
P/O Nbr: 1027
Date Received: 01/08/11

SAMPLE IDENTIFICATION	LAB NUMBER	COLLECTION DATE AND TIME
901 Barracuda	NUA0996-01	01/04/11 10:15
904 Barracuda	NUA0996-02	01/04/11 16:00
910 Barracuda	NUA0996-03	01/05/11 11:00
909 Barracuda	NUA0996-04	01/06/11 11:00
923 Albacore	NUA0996-05	01/06/11 16:00

An executed copy of the chain of custody, the project quality control data, and the sample receipt form are also included as an addendum to this report. If you have any questions relating to this analytical report, please contact your Laboratory Project Manager at 1-800-765-0980. Any opinions, if expressed, are outside the scope of the Laboratory's accreditation.

This material is intended only for the use of the individual(s) or entity to whom it is addressed, and may contain information that is privileged and confidential. If you are not the intended recipient, or the employee or agent responsible for delivering this material to the intended recipient, you are hereby notified that any dissemination, distribution, or copying of this material is strictly prohibited. If you have received this material in error, please notify us immediately at 615-726-0177.

South Carolina Certification Number: 84009

The Chain(s) of Custody, 3 pages, are included and are an integral part of this report.


These results relate only to the items tested. This report shall not be reproduced except in full and with permission of the laboratory.

All solids results are reported in wet weight unless specifically stated.

Estimated uncertainty is available upon request.

This report has been electronically signed.

Report Approved By:



Roxanne Connor

Program Manager - Conventional Accounts

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

ANALYTICAL REPORT

Analyte	Result	Flag	Units	MDL	MRL	Dilution Factor	Analysis Date/Time	Method	Analyst	Batch
Sample ID: NUA0996-01 (901 Barracuda - Soil) Sampled: 01/04/11 10:15										
General Chemistry Parameters										
Dry Solids	96.9		%	0.500	0.500	1	01/17/11 15:19	SW-846	AMS	11A1852
Volatile Organic Compounds by EPA Method 8260B										
Benzene	ND		mg/kg dry	0.00121	0.00219	1	01/13/11 13:47	SW846 8260B	MJH/H	11A1686
Ethylbenzene	ND		mg/kg dry	0.00107	0.00219	1	01/13/11 13:47	SW846 8260B	MJH/H	11A1686
1,2-Dichlorobenzene	0.00193	J	mg/kg dry	0.00186	0.00548	1	01/13/11 13:47	SW846 8260B	MJH/H	11A1686
1,4-Dichlorobenzene	0.000986	J	mg/kg dry	0.000975	0.00219	1	01/13/11 13:47	SW846 8260B	MJH/H	11A1686
1,3-Dichlorobenzene	ND		mg/kg dry	0.00208	0.00548	1	01/13/11 13:47	SW846 8260B	MJH/H	11A1686
1,1,1-Trichloroethane	100 %					1	01/13/11 13:47	SW846 8260B	MJH/H	11A1686
1,1,2-Trichloroethane	98 %					1	01/13/11 13:47	SW846 8260B	MJH/H	11A1686
1,2-Dibromochloroethane	105 %					1	01/13/11 13:47	SW846 8260B	MJH/H	11A1686
1,1-Dibromochloroethane	97 %					1	01/13/11 13:47	SW846 8260B	MJH/H	11A1686
Polyaromatic Hydrocarbons by EPA 8270D										
Acenaphthene	ND		mg/kg dry	0.0143	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Acenaphthylene	ND		mg/kg dry	0.0205	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Anthracene	ND		mg/kg dry	0.00921	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Benzo (a) anthracene	ND		mg/kg dry	0.0113	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Benzo (a) pyrene	ND		mg/kg dry	0.00819	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Benzo (b) fluoranthene	ND		mg/kg dry	0.0389	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Benzo (g,h,i) perylene	ND		mg/kg dry	0.00921	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Benzo (k) fluoranthene	ND		mg/kg dry	0.0379	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Benzofluorene	ND		mg/kg dry	0.0317	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Dibenz (a,h) anthracene	ND		mg/kg dry	0.0153	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Fluoranthene	ND		mg/kg dry	0.0113	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Fluorene	ND		mg/kg dry	0.0205	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Indeno (1,2,3-cd) pyrene	ND		mg/kg dry	0.0317	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Naphthalene	ND		mg/kg dry	0.0143	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Phenanthrene	ND		mg/kg dry	0.0102	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
Pyrene	ND		mg/kg dry	0.0235	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
1-Methylnaphthalene	ND		mg/kg dry	0.0123	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
2-Methylnaphthalene	ND		mg/kg dry	0.0215	0.0686	1	01/13/11 13:52	SW846 8270D	AJK	11A1728
1,2,3-Trichlorobenzene	57 %					1	01/13/11 13:52	SW846 8270D	AJK	11A1728
1,2,4-Trichlorobenzene	52 %					1	01/13/11 13:52	SW846 8270D	AJK	11A1728
1,3,5-Trichlorobenzene	51 %					1	01/13/11 13:52	SW846 8270D	AJK	11A1728

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

ANALYTICAL REPORT

Analyte	Result	Flag	Units	MDL	MRL	Dilution Factor	Analysis Date/Time	Method	Analyst	Batch
Sample ID: NUA0996-02 (904 Barracuda - Soil) Sampled: 01/04/11 16:00										
General Chemistry Parameters										
Dry Solids	91.2		%	0.500	0.500	1	01/17/11 15:19	SW-846	AMS	11A1852
Volatile Organic Compounds by EPA Method 8260B										
Benzene	ND		mg/kg dry	0.00116	0.00211	1	01/13/11 14:16	SW846 8260B	MJH/H	11A1686
Ethylbenzene	ND		mg/kg dry	0.00104	0.00211	1	01/13/11 14:16	SW846 8260B	MJH/H	11A1686
1,2-Dichlorobenzene	ND		mg/kg dry	0.00180	0.00528	1	01/13/11 14:16	SW846 8260B	MJH/H	11A1686
Toluene	ND		mg/kg dry	0.000940	0.00211	1	01/13/11 14:16	SW846 8260B	MJH/H	11A1686
Xylenes, total	ND		mg/kg dry	0.00201	0.00528	1	01/13/11 14:16	SW846 8260B	MJH/H	11A1686
1,2-Dichloroethane-d4 (67-138%)	102 %					1	01/13/11 14:16	SW846 8260B	MJH/H	11A1686
Dibromofluoromethane (75-125%)	98 %					1	01/13/11 14:16	SW846 8260B	MJH/H	11A1686
Toluene-d8 (76-129%)	106 %					1	01/13/11 14:16	SW846 8260B	MJH/H	11A1686
4-Bromofluorobenzene (67-147%)	106 %					1	01/13/11 14:16	SW846 8260B	MJH/H	11A1686
Polyaromatic Hydrocarbons by EPA 8270D										
Benaphthene	ND		mg/kg dry	0.0151	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
Benaphthylene	ND		mg/kg dry	0.0216	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
Anthracene	ND		mg/kg dry	0.00973	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
Benzo (a) anthracene	ND		mg/kg dry	0.0119	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
Benzo (a) pyrene	ND		mg/kg dry	0.00865	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
Benzo (b) fluoranthene	ND		mg/kg dry	0.0411	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
Benzo (g,h,i) perylene	ND		mg/kg dry	0.00973	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
Benzo (k) fluoranthene	ND		mg/kg dry	0.0400	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
Chrysene	ND		mg/kg dry	0.0335	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
Fluoranthene	ND		mg/kg dry	0.0162	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
Fluorene	ND		mg/kg dry	0.0119	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
Indeno (1,2,3-cd) pyrene	ND		mg/kg dry	0.0216	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
1,2,3,4-Benzophthalene	ND		mg/kg dry	0.0335	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
1,2,3,4-Benzophthalene	ND		mg/kg dry	0.0151	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
1,2,3,4-Benzophthalene	ND		mg/kg dry	0.0108	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
1,2,3,4-Benzophthalene	ND		mg/kg dry	0.0249	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
1-Methylnaphthalene	ND		mg/kg dry	0.0130	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
2-Methylnaphthalene	ND		mg/kg dry	0.0227	0.0724	1	01/13/11 14:13	SW846 8270D	AJK	11A1728
1,2,3,4-Terphenyl-d14 (18-120%)	58 %					1	01/13/11 14:13	SW846 8270D	AJK	11A1728
1,2,3,4-Terphenyl-d14 (18-120%)	57 %					1	01/13/11 14:13	SW846 8270D	AJK	11A1728
1,2,3,4-Terphenyl-d14 (18-120%)	56 %					1	01/13/11 14:13	SW846 8270D	AJK	11A1728

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

ANALYTICAL REPORT

Analyte	Result	Flag	Units	MDL	MRL	Dilution Factor	Analysis Date/Time	Method	Analyst	Batch
Sample ID: NUA0996-03 (910 Barracuda - Soil) Sampled: 01/05/11 11:00										
General Chemistry Parameters										
Dry Solids	96.4		%	0.500	0.500	1	01/17/11 15:19	SW846	AMS	11A1852
Volatile Organic Compounds by EPA Method 8260B										
Benzene	ND		mg/kg dry	0.00128	0.00233	1	01/13/11 14:45	SW846 8260B	MJH/H	11A1686
Ethylbenzene	ND		mg/kg dry	0.00114	0.00233	1	01/13/11 14:45	SW846 8260B	MJH/H	11A1686
1,2-Dichlorobenzene	ND		mg/kg dry	0.00198	0.00582	1	01/13/11 14:45	SW846 8260B	MJH/H	11A1686
Toluene	ND		mg/kg dry	0.00104	0.00233	1	01/13/11 14:45	SW846 8260B	MJH/H	11A1686
Xylenes, total	ND		mg/kg dry	0.00221	0.00582	1	01/13/11 14:45	SW846 8260B	MJH/H	11A1686
Surrogate: 1,2-Dichloroethane-d4 (67-138%)	102 %					1	01/13/11 14:45	SW846 8260B	MJH/H	11A1686
Surrogate: Dibromofluoromethane (75-125%)	99 %					1	01/13/11 14:45	SW846 8260B	MJH/H	11A1686
Surrogate: Toluene-d8 (76-129%)	105 %					1	01/13/11 14:45	SW846 8260B	MJH/H	11A1686
Surrogate: 4-Bromofluorobenzene (67-147%)	97 %					1	01/13/11 14:45	SW846 8260B	MJH/H	11A1686
Polycyclic Aromatic Hydrocarbons by EPA 8270D										
Acenaphthene	ND		mg/kg dry	0.0144	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Acenaphthylene	ND		mg/kg dry	0.0206	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Anthracene	ND		mg/kg dry	0.00927	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Benzo (a) anthracene	ND		mg/kg dry	0.0113	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Benzo (a) pyrene	ND		mg/kg dry	0.00824	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Benzo (b) fluoranthene	ND		mg/kg dry	0.0392	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Benzo (g,h,i) perylene	ND		mg/kg dry	0.00927	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Benzo (k) fluoranthene	ND		mg/kg dry	0.0381	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Benzofluoranthene	ND		mg/kg dry	0.0319	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Benzo (a,h) anthracene	ND		mg/kg dry	0.0155	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Fluoranthene	ND		mg/kg dry	0.0113	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Fluorene	ND		mg/kg dry	0.0206	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Indeno (1,2,3-cd) pyrene	ND		mg/kg dry	0.0319	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
1,2,3,4-Dibenzophthalene	ND		mg/kg dry	0.0144	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Benzo (a) anthracene	ND		mg/kg dry	0.0103	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Pyrene	ND		mg/kg dry	0.0237	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
1-Methylnaphthalene	ND		mg/kg dry	0.0124	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
2-Methylnaphthalene	ND		mg/kg dry	0.0216	0.0690	1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Surrogate: Terphenyl-d14 (18-120%)	60 %					1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Surrogate: 2-Fluorobiphenyl (14-120%)	50 %					1	01/13/11 16:42	SW846 8270D	AJK	11A1728
Surrogate: Nitrobenzene-d5 (17-120%)	48 %					1	01/13/11 16:42	SW846 8270D	AJK	11A1728

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

ANALYTICAL REPORT

Analyte	Result	Flag	Units	MDL	MRL	Dilution Factor	Analysis Date/Time	Method	Analyst	Batch
Sample ID: NUA0996-04 (909 Barracuda - Soil) Sampled: 01/06/11 11:00										
General Chemistry Parameters										
Dry Solids	92.5		%	0.500	0.500	1	01/17/11 15:19	SW846	AMS	11A1852
Volatile Organic Compounds by EPA Method 8260B										
Benzene	ND		mg/kg dry	0.00126	0.00228	1	01/13/11 15:14	SW846 8260B	MJH/H	11A1686
Ethylbenzene	ND		mg/kg dry	0.00112	0.00228	1	01/13/11 15:14	SW846 8260B	MJH/H	11A1686
1,2-Dichlorobenzene	ND		mg/kg dry	0.00194	0.00570	1	01/13/11 15:14	SW846 8260B	MJH/H	11A1686
1,4-Dichlorobenzene	ND		mg/kg dry	0.00102	0.00228	1	01/13/11 15:14	SW846 8260B	MJH/H	11A1686
1,2,4-Trichlorobenzene	ND		mg/kg dry	0.00217	0.00570	1	01/13/11 15:14	SW846 8260B	MJH/H	11A1686
1,1,1-Trichloroethane	99 %					1	01/13/11 15:14	SW846 8260B	MJH/H	11A1686
1,1,2,2-Tetrachloroethane	97 %					1	01/13/11 15:14	SW846 8260B	MJH/H	11A1686
1,1,1-Trichloroethane	104 %					1	01/13/11 15:14	SW846 8260B	MJH/H	11A1686
1,1,2,2-Tetrachloroethane	98 %					1	01/13/11 15:14	SW846 8260B	MJH/H	11A1686
Polyaromatic Hydrocarbons by EPA 8270D										
Acenaphthene	ND		mg/kg dry	0.0148	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
Acenaphthylene	ND		mg/kg dry	0.0212	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
Anthracene	ND		mg/kg dry	0.00952	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
Benzo (a) anthracene	ND		mg/kg dry	0.0116	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
Benzo (a) pyrene	ND		mg/kg dry	0.00846	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
Benzo (b) fluoranthene	ND		mg/kg dry	0.0402	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
Benzo (g,h,i) perylene	ND		mg/kg dry	0.00952	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
Benzo (k) fluoranthene	ND		mg/kg dry	0.0391	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
Benzofluoranthene	ND		mg/kg dry	0.0328	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
Benzo (a,h) anthracene	ND		mg/kg dry	0.0159	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
Fluoranthene	ND		mg/kg dry	0.0116	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
Fluorene	ND		mg/kg dry	0.0212	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
Indeno (1,2,3-cd) pyrene	ND		mg/kg dry	0.0328	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
1-Methylanthracene	ND		mg/kg dry	0.0148	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
1-Methylanthracene	ND		mg/kg dry	0.0106	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
1-Methylanthracene	ND		mg/kg dry	0.0243	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
1-Methylanthracene	ND		mg/kg dry	0.0127	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
1-Methylanthracene	ND		mg/kg dry	0.0222	0.0709	1	01/13/11 17:03	SW846 8270D	AJK	11A1728
1-Methylanthracene	57 %					1	01/13/11 17:03	SW846 8270D	AJK	11A1728
1-Methylanthracene	54 %					1	01/13/11 17:03	SW846 8270D	AJK	11A1728
1-Methylanthracene	52 %					1	01/13/11 17:03	SW846 8270D	AJK	11A1728

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

ANALYTICAL REPORT

Analyte	Result	Flag	Units	MDL	MRL	Dilution Factor	Analysis Date/Time	Method	Analyst	Batch
Sample ID: NUA0996-05 (923 Albacore - Soil) Sampled: 01/06/11 16:00										
General Chemistry Parameters										
Dry Solids	82.5		%	0.500	0.500	1	01/17/11 15:19	SW846	AMS	11A1852
Volatile Organic Compounds by EPA Method 8260B										
Benzene	ND		mg/kg dry	0.00118	0.00215	1	01/14/11 12:52	SW846 8260B	MJH/H	11A2821
Ethylbenzene	ND		mg/kg dry	0.00106	0.00215	1	01/14/11 12:52	SW846 8260B	MJH/H	11A2821
1,2,3-Trichlorobenzene	ND		mg/kg dry	0.00183	0.00538	1	01/14/11 12:52	SW846 8260B	MJH/H	11A2821
Toluene	ND		mg/kg dry	0.000958	0.00215	1	01/14/11 12:52	SW846 8260B	MJH/H	11A2821
Xylenes, total	ND		mg/kg dry	0.00205	0.00538	1	01/14/11 12:52	SW846 8260B	MJH/H	11A2821
Residue: 1,2-Dichloroethane-d4 (67-138%)	99 %					1	01/14/11 12:52	SW846 8260B	MJH/H	11A2821
Residue: Dibromofluoromethane (75-125%)	100 %					1	01/14/11 12:52	SW846 8260B	MJH/H	11A2821
Residue: Toluene-d8 (76-129%)	105 %					1	01/14/11 12:52	SW846 8260B	MJH/H	11A2821
Residue: 4-Bromofluorobenzene (67-147%)	104 %					1	01/14/11 12:52	SW846 8260B	MJH/H	11A2821
Polyaromatic Hydrocarbons by EPA 8270D										
Benzo(a)anthracene	ND		mg/kg dry	0.0166	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Benzo(b)fluoranthene	ND		mg/kg dry	0.0237	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Benzo(k)fluoranthene	0.173		mg/kg dry	0.0107	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Benzo(a)anthracene	1.30		mg/kg dry	0.0130	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Benzo(a)pyrene	0.587		mg/kg dry	0.00948	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Benzo(b)fluoranthene	0.746		mg/kg dry	0.0450	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Benzo(g,h,i)perylene	0.290		mg/kg dry	0.0107	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Benzo(k)fluoranthene	0.691		mg/kg dry	0.0438	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Chrysene	1.28		mg/kg dry	0.0367	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Fluoranthene	0.107		mg/kg dry	0.0178	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Fluorene	2.34		mg/kg dry	0.0130	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Indeno(1,2,3-cd)pyrene	ND		mg/kg dry	0.0237	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Naphthalene	0.287		mg/kg dry	0.0367	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Phenanthrene	ND		mg/kg dry	0.0166	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Pyrene	0.561		mg/kg dry	0.0118	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
1-Methylnaphthalene	2.00		mg/kg dry	0.0273	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
2-Methylnaphthalene	ND		mg/kg dry	0.0142	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Residue: Terphenyl-d14 (18-120%)	57 %			0.0249	0.0794	1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Residue: 2-Fluorobiphenyl (14-120%)	55 %					1	01/13/11 17:25	SW846 8270D	AJK	11A1728
Residue: Nitrobenzene-d5 (17-120%)	56 %					1	01/13/11 17:25	SW846 8270D	AJK	11A1728

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

SAMPLE EXTRACTION DATA

Parameter	Batch	Lab Number	Wt/Vol Extracted	Extract Vol	Date	Analyst	Extraction Method
Polycyclic Aromatic Hydrocarbons by EPA 8270D							
SW846 8270D	11A1728	NUA0996-01	30.26	1.00	01/12/11 09:25	SAS	EPA 3550C
SW846 8270D	11A1728	NUA0996-02	30.43	1.00	01/12/11 09:25	SAS	EPA 3550C
SW846 8270D	11A1728	NUA0996-03	30.21	1.00	01/12/11 09:25	SAS	EPA 3550C
SW846 8270D	11A1728	NUA0996-04	30.67	1.00	01/12/11 09:25	SAS	EPA 3550C
SW846 8270D	11A1728	NUA0996-05	30.70	1.00	01/12/11 09:25	SAS	EPA 3550C
Volatile Organic Compounds by EPA Method 8260B							
SW846 8260B	11A1686	NUA0996-01	4.71	5.00	01/04/11 10:15	CHH	EPA 5035
SW846 8260B	11A1686	NUA0996-02	5.19	5.00	01/04/11 16:00	CHH	EPA 5035
SW846 8260B	11A1686	NUA0996-03	4.46	5.00	01/05/11 11:00	CHH	EPA 5035
SW846 8260B	11A1686	NUA0996-04	4.74	5.00	01/06/11 11:00	CHH	EPA 5035
SW846 8260B	11A1686	NUA0996-05	5.34	5.00	01/06/11 16:00	CHH	EPA 5035
SW846 8260B	11A2821	NUA0996-05RE1	5.63	5.00	01/06/11 16:00	CHH	EPA 5035
SW846 8260B	11A2821	NUA0996-05RE2	5.45	5.00	01/06/11 16:00	CHH	EPA 5035

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

PROJECT QUALITY CONTROL DATA

Blank

Analyte	Blank Value	Q	Units	Q.C. Batch	Lab Number	Analyzed Date/Time
Volatile Organic Compounds by EPA Method 8260B						
1A1686-BLK1						
Benzene	<0.00110		mg/kg wet	11A1686	11A1686-BLK1	01/13/11 12:21
Ethylbenzene	<0.000980		mg/kg wet	11A1686	11A1686-BLK1	01/13/11 12:21
Naphthalene	<0.00170		mg/kg wet	11A1686	11A1686-BLK1	01/13/11 12:21
Toluene	<0.000890		mg/kg wet	11A1686	11A1686-BLK1	01/13/11 12:21
Xylenes, total	<0.00190		mg/kg wet	11A1686	11A1686-BLK1	01/13/11 12:21
Surrogate: 1,2-Dichloroethane-d4	101%			11A1686	11A1686-BLK1	01/13/11 12:21
Surrogate: Dibromofluoromethane	98%			11A1686	11A1686-BLK1	01/13/11 12:21
Surrogate: Toluene-d8	102%			11A1686	11A1686-BLK1	01/13/11 12:21
Surrogate: 4-Bromofluorobenzene	97%			11A1686	11A1686-BLK1	01/13/11 12:21
1A2821-BLK1						
Benzene	<0.00110		mg/kg wet	11A2821	11A2821-BLK1	01/14/11 12:05
Ethylbenzene	<0.000980		mg/kg wet	11A2821	11A2821-BLK1	01/14/11 12:05
Naphthalene	<0.00170		mg/kg wet	11A2821	11A2821-BLK1	01/14/11 12:05
Toluene	<0.000890		mg/kg wet	11A2821	11A2821-BLK1	01/14/11 12:05
Xylenes, total	<0.00190		mg/kg wet	11A2821	11A2821-BLK1	01/14/11 12:05
Surrogate: 1,2-Dichloroethane-d4	104%			11A2821	11A2821-BLK1	01/14/11 12:05
Surrogate: Dibromofluoromethane	101%			11A2821	11A2821-BLK1	01/14/11 12:05
Surrogate: Toluene-d8	103%			11A2821	11A2821-BLK1	01/14/11 12:05
Surrogate: 4-Bromofluorobenzene	96%			11A2821	11A2821-BLK1	01/14/11 12:05
Polycyclic Aromatic Hydrocarbons by EPA 8270D						
1A1728-BLK1						
Acenaphthene	<0.0140		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Acenaphthylene	<0.0200		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Anthracene	<0.00900		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Benzo (a) anthracene	<0.0110		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Benzo (a) pyrene	<0.00800		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Benzo (b) fluoranthene	<0.0380		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Benzo (g,h,i) perylene	<0.00900		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Benzo (k) fluoranthene	<0.0370		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Chrysene	<0.0310		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Dibenz (a,h) anthracene	<0.0150		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Fluoranthene	<0.0110		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Fluorene	<0.0200		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Indeno (1,2,3-cd) pyrene	<0.0310		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Naphthalene	<0.0140		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Phenanthrene	<0.0100		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
Pyrene	<0.0230		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
1-Methylnaphthalene	<0.0120		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54
2-Methylnaphthalene	<0.0210		mg/kg wet	11A1728	11A1728-BLK1	01/13/11 11:54

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

PROJECT QUALITY CONTROL DATA
Blank - Cont.

anlyte	Blank Value	Q	Units	Q.C. Batch	Lab Number	Analyzed Date/Time
Polycyclic Aromatic Hydrocarbons by EPA 8270D						
1A1728-BLK1						
<i> surrogate: Terphenyl-d14</i>	66%			11A1728	11A1728-BLK1	01/13/11 11:54
<i> surrogate: 2-Fluorobiphenyl</i>	64%			11A1728	11A1728-BLK1	01/13/11 11:54
<i> surrogate: Nitrobenzene-d5</i>	65%			11A1728	11A1728-BLK1	01/13/11 11:54

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

PROJECT QUALITY CONTROL DATA

Duplicate

Sample	Orig. Val.	Duplicate	Q	Units	RPD	Limit	Batch	Sample Duplicated	% Rec.	Analyzed Date/Time
General Chemistry Parameters										
1A1852-DUP1										
Dry Solids	88.3	87.7		%	0.8	20	11A1852	NUA0883-12		01/17/11 15:19

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

PROJECT QUALITY CONTROL DATA LCS

Analyste	Known Val.	Analyzed Val	Q	Units	% Rec.	Target Range	Batch	Analyzed Date/Time
Volatile Organic Compounds by EPA Method 8260B								
1A1686-BS1								
Benzene	50.0	45.0		ug/kg	90%	78 - 126	11A1686	01/13/11 10:55
Ethylbenzene	50.0	46.6		ug/kg	93%	79 - 130	11A1686	01/13/11 10:55
1,2,3-Trichlorobenzene	50.0	48.4		ug/kg	97%	72 - 150	11A1686	01/13/11 10:55
Toluene	50.0	48.0		ug/kg	96%	76 - 126	11A1686	01/13/11 10:55
Xylenes, total	150	142		ug/kg	94%	80 - 130	11A1686	01/13/11 10:55
Surrogate: 1,2-Dichloroethane-d4	50.0	50.3			101%	67 - 138	11A1686	01/13/11 10:55
Surrogate: Dibromofluoromethane	50.0	51.2			102%	75 - 125	11A1686	01/13/11 10:55
Surrogate: Toluene-d8	50.0	51.5			103%	76 - 129	11A1686	01/13/11 10:55
Surrogate: 4-Bromofluorobenzene	50.0	49.8			100%	67 - 147	11A1686	01/13/11 10:55
1A2821-BS1								
Benzene	50.0	48.2		ug/kg	96%	78 - 126	11A2821	01/14/11 10:12
Ethylbenzene	50.0	47.0		ug/kg	94%	79 - 130	11A2821	01/14/11 10:12
1,2,3-Trichlorobenzene	50.0	48.8		ug/kg	98%	72 - 150	11A2821	01/14/11 10:12
Toluene	50.0	48.2		ug/kg	96%	76 - 126	11A2821	01/14/11 10:12
Xylenes, total	150	141		ug/kg	94%	80 - 130	11A2821	01/14/11 10:12
Surrogate: 1,2-Dichloroethane-d4	50.0	52.0			104%	67 - 138	11A2821	01/14/11 10:12
Surrogate: Dibromofluoromethane	50.0	53.3			107%	75 - 125	11A2821	01/14/11 10:12
Surrogate: Toluene-d8	50.0	50.7			101%	76 - 129	11A2821	01/14/11 10:12
Surrogate: 4-Bromofluorobenzene	50.0	49.4			99%	67 - 147	11A2821	01/14/11 10:12
Polycyclic Aromatic Hydrocarbons by EPA 8270D								
1A1728-BS1								
Acenaphthene	1.67	1.13		mg/kg wet	68%	49 - 120	11A1728	01/13/11 11:12
Acenaphthylene	1.67	1.20		mg/kg wet	72%	52 - 120	11A1728	01/13/11 11:12
Anthracene	1.67	1.30		mg/kg wet	78%	58 - 120	11A1728	01/13/11 11:12
Benzo (a) anthracene	1.67	1.28		mg/kg wet	77%	57 - 120	11A1728	01/13/11 11:12
Benzo (a) pyrene	1.67	1.30		mg/kg wet	78%	55 - 120	11A1728	01/13/11 11:12
Benzo (b) fluoranthene	1.67	1.21		mg/kg wet	73%	51 - 123	11A1728	01/13/11 11:12
Benzo (g,h,i) perylene	1.67	1.29		mg/kg wet	78%	49 - 121	11A1728	01/13/11 11:12
Benzo (k) fluoranthene	1.67	1.21		mg/kg wet	72%	42 - 129	11A1728	01/13/11 11:12
Benzofluorene	1.67	1.22		mg/kg wet	73%	55 - 120	11A1728	01/13/11 11:12
Benzidene	1.67	1.35		mg/kg wet	81%	50 - 123	11A1728	01/13/11 11:12
Fluoranthene	1.67	1.28		mg/kg wet	77%	58 - 120	11A1728	01/13/11 11:12
Fluorene	1.67	1.22		mg/kg wet	73%	54 - 120	11A1728	01/13/11 11:12
Indeno (1,2,3-cd) pyrene	1.67	1.33		mg/kg wet	80%	50 - 122	11A1728	01/13/11 11:12
1,2,3-Trichlorobenzene	1.67	0.993		mg/kg wet	60%	28 - 120	11A1728	01/13/11 11:12
Phenanthrene	1.67	1.26		mg/kg wet	76%	56 - 120	11A1728	01/13/11 11:12
Pyrene	1.67	1.26		mg/kg wet	75%	56 - 120	11A1728	01/13/11 11:12
1-Methylnaphthalene	1.67	0.927		mg/kg wet	56%	36 - 120	11A1728	01/13/11 11:12
2-Methylnaphthalene	1.67	1.03		mg/kg wet	62%	36 - 120	11A1728	01/13/11 11:12

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

PROJECT QUALITY CONTROL DATA

LCS - Cont.

Analyte	Known Val.	Analyzed Val	Q	Units	% Rec.	Target Range	Batch	Analyzed Date/Time
Polyaromatic Hydrocarbons by EPA 8270D								
11A1728-BS1								
Surrogate: Terphenyl-d14	1.67	1.06			63%	18 - 120	11A1728	01/13/11 11:12
Surrogate: 2-Fluorobiphenyl	1.67	0.959			58%	14 - 120	11A1728	01/13/11 11:12
Surrogate: Nitrobenzene-d5	1.67	0.859			52%	17 - 120	11A1728	01/13/11 11:12

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

PROJECT QUALITY CONTROL DATA Matrix Spike

Analyte	Orig. Val.	MS Val	Q	Units	Spike Conc	% Rec.	Target Range	Batch	Sample Spiked	Analyzed Date/Time
Volatile Organic Compounds by EPA Method 8260B										
1A1686-MS1										
Benzene	ND	0.0727		mg/kg dry	0.0606	120%	42 - 141	11A1686	NUA0996-05	01/13/11 16:47
o-Xylylbenzene	ND	0.0729		mg/kg dry	0.0606	120%	21 - 165	11A1686	NUA0996-05	01/13/11 16:47
o-Xylylbenzene	ND	0.0383		mg/kg dry	0.0606	63%	10 - 160	11A1686	NUA0996-05	01/13/11 16:47
o-Xylylbenzene	ND	0.0782		mg/kg dry	0.0606	129%	45 - 145	11A1686	NUA0996-05	01/13/11 16:47
o-Xylylenes, total	ND	0.217		mg/kg dry	0.182	120%	31 - 159	11A1686	NUA0996-05	01/13/11 16:47
Surrogate: 1,2-Dichloroethane-d4		51.9		ug/kg	50.0	104%	67 - 138	11A1686	NUA0996-05	01/13/11 16:47
Surrogate: Dibromofluoromethane		53.2		ug/kg	50.0	106%	75 - 125	11A1686	NUA0996-05	01/13/11 16:47
Surrogate: Toluene-d8		53.5		ug/kg	50.0	107%	76 - 129	11A1686	NUA0996-05	01/13/11 16:47
Surrogate: 4-Bromofluorobenzene		54.9		ug/kg	50.0	110%	67 - 147	11A1686	NUA0996-05	01/13/11 16:47
1A2821-MS1										
Benzene	ND	0.0562		mg/kg wet	0.0500	112%	42 - 141	11A2821	NUA1463-12	01/17/11 23:03
o-Xylylbenzene	ND	0.0566		mg/kg wet	0.0500	113%	21 - 165	11A2821	NUA1463-12	01/17/11 23:03
o-Xylylbenzene	ND	0.0301		mg/kg wet	0.0500	60%	10 - 160	11A2821	NUA1463-12	01/17/11 23:03
o-Xylylbenzene	ND	0.0598		mg/kg wet	0.0500	120%	45 - 145	11A2821	NUA1463-12	01/17/11 23:03
o-Xylylenes, total	ND	0.170		mg/kg wet	0.150	113%	31 - 159	11A2821	NUA1463-12	01/17/11 23:03
Surrogate: 1,2-Dichloroethane-d4		52.8		ug/kg	50.0	106%	67 - 138	11A2821	NUA1463-12	01/17/11 23:03
Surrogate: Dibromofluoromethane		52.8		ug/kg	50.0	106%	75 - 125	11A2821	NUA1463-12	01/17/11 23:03
Surrogate: Toluene-d8		51.9		ug/kg	50.0	104%	76 - 129	11A2821	NUA1463-12	01/17/11 23:03
Surrogate: 4-Bromofluorobenzene		48.5		ug/kg	50.0	97%	67 - 147	11A2821	NUA1463-12	01/17/11 23:03
Polycyclic Aromatic Hydrocarbons by EPA 8270D										
1A1728-MS1										
Acenaphthene	ND	1.07		mg/kg dry	1.96	55%	42 - 120	11A1728	NUA0952-01	01/13/11 12:27
Acenaphthylene	ND	1.12		mg/kg dry	1.96	57%	32 - 120	11A1728	NUA0952-01	01/13/11 12:27
Anthracene	ND	1.20		mg/kg dry	1.96	61%	10 - 200	11A1728	NUA0952-01	01/13/11 12:27
Benzo (a) anthracene	ND	1.20		mg/kg dry	1.96	61%	41 - 120	11A1728	NUA0952-01	01/13/11 12:27
Benzo (a) pyrene	ND	1.19		mg/kg dry	1.96	61%	33 - 121	11A1728	NUA0952-01	01/13/11 12:27
Benzo (b) fluoranthene	ND	1.34		mg/kg dry	1.96	68%	26 - 137	11A1728	NUA0952-01	01/13/11 12:27
Benzo (g,h,i) perylene	ND	1.18		mg/kg dry	1.96	60%	21 - 124	11A1728	NUA0952-01	01/13/11 12:27
Benzo (k) fluoranthene	ND	0.940		mg/kg dry	1.96	48%	14 - 140	11A1728	NUA0952-01	01/13/11 12:27
Benzofluorene	ND	1.15		mg/kg dry	1.96	59%	28 - 123	11A1728	NUA0952-01	01/13/11 12:27
Benz (a,h) anthracene	ND	1.24		mg/kg dry	1.96	63%	25 - 127	11A1728	NUA0952-01	01/13/11 12:27
Fluoranthene	ND	1.20		mg/kg dry	1.96	61%	38 - 120	11A1728	NUA0952-01	01/13/11 12:27
Fluorene	ND	1.16		mg/kg dry	1.96	59%	41 - 120	11A1728	NUA0952-01	01/13/11 12:27
Indeno (1,2,3-cd) pyrene	ND	1.21		mg/kg dry	1.96	62%	25 - 123	11A1728	NUA0952-01	01/13/11 12:27
Naphthalene	ND	1.01		mg/kg dry	1.96	51%	25 - 120	11A1728	NUA0952-01	01/13/11 12:27
Phenanthrene	ND	1.20		mg/kg dry	1.96	61%	37 - 120	11A1728	NUA0952-01	01/13/11 12:27

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

PROJECT QUALITY CONTROL DATA Matrix Spike - Cont.

Analyte	Orig. Val.	MS Val	Q	Units	Spike Conc	% Rec.	Target Range	Batch	Sample Spiked	Analyzed Date/Time
Polyaromatic Hydrocarbons by EPA 8270D										
1A1728-MS1										
Pyrene	ND	1.20		mg/kg dry	1.96	61%	29 - 125	11A1728	NUA0952-01	01/13/11 12:27
1-Methylnaphthalene	ND	0.898		mg/kg dry	1.96	46%	19 - 120	11A1728	NUA0952-01	01/13/11 12:27
2-Methylnaphthalene	ND	1.00		mg/kg dry	1.96	51%	11 - 120	11A1728	NUA0952-01	01/13/11 12:27
Surrogate: Terphenyl-d14		1.01		mg/kg dry	1.96	51%	18 - 120	11A1728	NUA0952-01	01/13/11 12:27
Surrogate: 2-Fluorobiphenyl		0.925		mg/kg dry	1.96	47%	14 - 120	11A1728	NUA0952-01	01/13/11 12:27
Surrogate: Nitrobenzene-d5		0.851		mg/kg dry	1.96	43%	17 - 120	11A1728	NUA0952-01	01/13/11 12:27

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

PROJECT QUALITY CONTROL DATA

Matrix Spike Dup

Analyte	Orig. Val.	Duplicate	Q	Units	Spike Conc	% Rec.	Target Range	RPD	Limit	Batch	Sample Duplicated	Analyzed Date/Time
Volatile Organic Compounds by EPA Method 8260B												
1A1686-MSD1												
Benzene	ND	0.0687		mg/kg dry	0.0606	113%	42 - 141	6	50	11A1686	NUA0996-05	01/13/11 17:16
Ethylbenzene	ND	0.0678		mg/kg dry	0.0606	112%	21 - 165	7	50	11A1686	NUA0996-05	01/13/11 17:16
Naphthalene	ND	0.0321		mg/kg dry	0.0606	53%	10 - 160	18	50	11A1686	NUA0996-05	01/13/11 17:16
Toluene	ND	0.0723		mg/kg dry	0.0606	119%	45 - 145	8	50	11A1686	NUA0996-05	01/13/11 17:16
Kylenes, total	ND	0.204		mg/kg dry	0.182	112%	31 - 159	6	50	11A1686	NUA0996-05	01/13/11 17:16
Surrogate: 1,2-Dichloroethane-d4		50.9		ug/kg	50.0	102%	67 - 138			11A1686	NUA0996-05	01/13/11 17:16
Surrogate: Dibromofluoromethane		53.6		ug/kg	50.0	107%	75 - 125			11A1686	NUA0996-05	01/13/11 17:16
Surrogate: Toluene-d8		53.1		ug/kg	50.0	106%	76 - 129			11A1686	NUA0996-05	01/13/11 17:16
Surrogate: 4-Bromofluorobenzene		52.7		ug/kg	50.0	105%	67 - 147			11A1686	NUA0996-05	01/13/11 17:16
1A2821-MSD1												
Benzene	ND	0.0802	M1	mg/kg wet	0.0500	160%	42 - 141	35	50	11A2821	NUA1463-12	01/17/11 23:32
Ethylbenzene	ND	0.0789		mg/kg wet	0.0500	158%	21 - 165	33	50	11A2821	NUA1463-12	01/17/11 23:32
Naphthalene	ND	0.0434		mg/kg wet	0.0500	87%	10 - 160	36	50	11A2821	NUA1463-12	01/17/11 23:32
Toluene	ND	0.0823	M1	mg/kg wet	0.0500	165%	45 - 145	32	50	11A2821	NUA1463-12	01/17/11 23:32
Kylenes, total	ND	0.237		mg/kg wet	0.150	158%	31 - 159	33	50	11A2821	NUA1463-12	01/17/11 23:32
Surrogate: 1,2-Dichloroethane-d4		54.4		ug/kg	50.0	109%	67 - 138			11A2821	NUA1463-12	01/17/11 23:32
Surrogate: Dibromofluoromethane		54.2		ug/kg	50.0	108%	75 - 125			11A2821	NUA1463-12	01/17/11 23:32
Surrogate: Toluene-d8		51.1		ug/kg	50.0	102%	76 - 129			11A2821	NUA1463-12	01/17/11 23:32
Surrogate: 4-Bromofluorobenzene		47.2		ug/kg	50.0	94%	67 - 147			11A2821	NUA1463-12	01/17/11 23:32
Polycyclic Aromatic Hydrocarbons by EPA 8270D												
1A1728-MSD1												
Acenaphthene	ND	1.24		mg/kg dry	1.96	64%	42 - 120	15	40	11A1728	NUA0952-01	01/13/11 12:48
Acenaphthylene	ND	1.33		mg/kg dry	1.96	68%	32 - 120	17	30	11A1728	NUA0952-01	01/13/11 12:48
Anthracene	ND	1.44		mg/kg dry	1.96	73%	10 - 200	18	50	11A1728	NUA0952-01	01/13/11 12:48
Benzo (a) anthracene	ND	1.37		mg/kg dry	1.96	70%	41 - 120	13	30	11A1728	NUA0952-01	01/13/11 12:48
Benzo (a) pyrene	ND	1.40		mg/kg dry	1.96	72%	33 - 121	16	33	11A1728	NUA0952-01	01/13/11 12:48
Benzo (b) fluoranthene	ND	1.52		mg/kg dry	1.96	78%	26 - 137	13	42	11A1728	NUA0952-01	01/13/11 12:48
Benzo (g,h,i) perylene	ND	1.37		mg/kg dry	1.96	70%	21 - 124	15	32	11A1728	NUA0952-01	01/13/11 12:48
Benzo (k) fluoranthene	ND	1.16		mg/kg dry	1.96	59%	14 - 140	21	39	11A1728	NUA0952-01	01/13/11 12:48
Chrysene	ND	1.34		mg/kg dry	1.96	68%	28 - 123	15	34	11A1728	NUA0952-01	01/13/11 12:48
Dibenz (a,h) anthracene	ND	1.45		mg/kg dry	1.96	74%	25 - 127	16	31	11A1728	NUA0952-01	01/13/11 12:48
Fluoranthene	ND	1.42		mg/kg dry	1.96	73%	38 - 120	17	35	11A1728	NUA0952-01	01/13/11 12:48
Fluorene	ND	1.34		mg/kg dry	1.96	68%	41 - 120	15	37	11A1728	NUA0952-01	01/13/11 12:48
Indeno (1,2,3-cd) pyrene	ND	1.44		mg/kg dry	1.96	73%	25 - 123	17	32	11A1728	NUA0952-01	01/13/11 12:48
Naphthalene	ND	1.17		mg/kg dry	1.96	60%	25 - 120	15	42	11A1728	NUA0952-01	01/13/11 12:48
Phenanthrene	ND	1.39		mg/kg dry	1.96	71%	37 - 120	15	32	11A1728	NUA0952-01	01/13/11 12:48
Pyrene	ND	1.38		mg/kg dry	1.96	70%	29 - 125	14	40	11A1728	NUA0952-01	01/13/11 12:48
1-Methylnaphthalene	ND	1.06		mg/kg dry	1.96	54%	19 - 120	17	45	11A1728	NUA0952-01	01/13/11 12:48
2-Methylnaphthalene	ND	1.17		mg/kg dry	1.96	60%	11 - 120	15	50	11A1728	NUA0952-01	01/13/11 12:48

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

PROJECT QUALITY CONTROL DATA

Matrix Spike Dup - Cont.

anlyte	Orig. Val.	Duplicate	Q	Units	Spike Conc	% Rec.	Target Range	RPD Limit	Batch	Sample Duplicated	Analyzed Date/Time
Polycyclic Aromatic Hydrocarbons by EPA 8270D											
1A1728-MSD1											
Surrogate: Terphenyl-d14		1.12		mg/kg dry	1.96	57%	18 - 120		11A1728	NUA0952-01	01/13/11 12:48
Surrogate: 2-Fluorobiphenyl		1.09		mg/kg dry	1.96	56%	14 - 120		11A1728	NUA0952-01	01/13/11 12:48
Surrogate: Nitrobenzene-d5		0.992		mg/kg dry	1.96	51%	17 - 120		11A1728	NUA0952-01	01/13/11 12:48

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwec

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

CERTIFICATION SUMMARY

TestAmerica Nashville

Method	Matrix	AIHA	Nelac	South Carolina
SW846 8260B	Soil	N/A	X	X
SW846 8270D	Soil		X	X
SW-846	Soil			

Client EEG - Small Business Group, Inc. (2449)
10179 Highway 78
Ladson, SC 29456
Attn Tom McElwee

Work Order: NUA0996
Project Name: Laurel Bay Housing Project
Project Number: [none]
Received: 01/08/11 08:30

DATA QUALIFIERS AND DEFINITIONS

J Analyte detected at a level less than the Reporting Limit (RL) and greater than or equal to the Method Detection Limit (MDL).
Concentrations within this range are estimated.
MI The MS and/or MSD were above the acceptance limits due to sample matrix interference. See Blank Spike (LCS).
ND Not detected at the reporting limit (or method detection limit if shown)

METHOD MODIFICATION NOTES

THE LEADER IN ENVIRONMENTAL TESTING

**Nashville Division
2960 Foster Creighton
Nashville, TN 37204**

Phone: 615-726-0177
Toll Free: 800-765-0980
Fax: 615-726-3404

To assist us in using the proper analytical methods, is this work being conducted for regulatory purposes?

Client Name/Account #: EEG - SBG # 2449

Address: 10179 Highway 78

City/State/Zip: Ladson, SC 29456

Project Manager: Tom McElwee email: mcelwee@eeginc.net

Telephone Number: 843.412.2097

Fax No.:

Sampler Name: (Print)

Sampler Signature:

Site State: SC

PO#:

TA Quote #:

Project ID: Laurel Bay Housing Project

Project #:

Compliance Monitoring?	Yes	No
------------------------	-----	----

Enforcement Action?	Yes	No
---------------------	-----	----


[illegible]

Special Instructions:

Laboratory Comments:

Temperature Upon Receipt: VOCs Free of Headspace?

1

Method of Shipment:				FEDEX	
Relinquished by: 	Date: 1/7/11	Time: 0900	Received by: 	Date: 1/7/11	Time:
Relinquished by: 	Date:	Time:	Received by TestAmerica: 	Date: 1/8/11	Time: 830

ATTACHMENT A



NON-HAZARDOUS MANIFEST

NON-HAZARDOUS MANIFEST		1. Generator's US EPA ID No.		Manifest Doc No.		2. Page 1 of 1		
3. Generator's Mailing Address: MCAS, BEAUFORT LAUREL BAY HOUSING BEAUFORT, SC 29907		4. Generator's Phone 843-228-6461		Generator's Site Address (if different than mailing):		A. Manifest Number WMNA 00316805		
5. Transporter 1 Company Name EEG, INC.		6. US EPA ID Number		C. State Transporter's ID		D. Transporter's Phone 843-879-0411		
7. Transporter 2 Company Name		8. US EPA ID Number		E. State Transporter's ID		F. Transporter's Phone		
9. Designated Facility Name and Site Address HICKORY HILL LANDFILL 2621 LOW COUNTRY ROAD RIDGELAND, SC 29936		10. US EPA ID Number		G. State Facility ID		H. State Facility Phone 843-987-4643		
11. Description of Waste Materials		12. Containers		13. Total Quantity	14. Unit Wt./Vol.	I. Misc. Comments		
		No.	Type					
		a. HEATING OIL TANKS FILLED WITH SAND WM Profile # 102655SC						
		b.						
		c.						
d.								
J. Additional Descriptions for Materials Listed Above		K. Disposal Location		Cell		Level		
15. Special Handling Instructions and Additional Information 437's from: 2) 910 BARRACUDA 4) 923 ALBACORR 6) 926 ALBACORR 1) 904 BARRACUDA 3) 909 BARRACUDA 5) 924 ALBACORR		Purchase Order #		EMERGENCY CONTACT / PHONE NO.:				
16. GENERATOR'S CERTIFICATE: I hereby certify that the above-described materials are not hazardous wastes as defined by CFR Part 261 or any applicable state law, have been fully and accurately described, classified and packaged and are in proper condition for transportation according to applicable regulations.								
Printed Name Charles H. Herron		Signature "On behalf of" Charles H. Herron		Month 07	Day 28	Year 11		
17. Transporter 1 Acknowledgement of Receipt of Materials		Printed Name James Baldwin		Signature James Baldwin		Month 3	Day 2	Year 11
18. Transporter 2 Acknowledgement of Receipt of Materials		Printed Name		Signature		Month	Day	Year
19. Certificate of Final Treatment/Disposal I certify, on behalf of the above listed treatment facility, that to the best of my knowledge, the above-described waste was managed in compliance with all applicable laws, regulations, permits and licenses on the dates listed above.								
20. Facility Owner or Operator: Certification of receipt of non-hazardous materials covered by this manifest.								
Printed Name Toni Cofield		Signature Toni Cofield		Month 3	Day 2	Year 11		

White- TREATMENT, STORAGE, DISPOSAL FACILITY COPY

Blue- GENERATOR #2 COPY

Yellow- GENERATOR #1 COPY

Pink- FACILITY USE ONLY

Gold- TRANSPORTER #1 COPY

Appendix C

Regulatory Correspondence



Catherine E. Heigel, Director

Promoting and protecting the health of the public and the environment

July 1, 2015

Commanding Officer
Attention: NREAO Mr. William A. Drawdy
United State Marine Corps Air Station
Post Office Box 55001
Beaufort, SC 29904-5001

RE: No Further Action
Laurel Bay Underground Storage Tank Assessment Reports for:
See attached sheet

Dear Mr. Drawdy,

The South Carolina Department of Health and Environmental Control (the Department) received the referenced Underground Storage Tanks (USTs) Assessment Reports for the addresses listed above. The regulatory authority for the investigation and cleanup of releases from these tank systems is the South Carolina Pollution Control Act (S.C. Code Ann. §48-1-10 et seq., as amended).

The Department has reviewed the referenced assessment reports and agrees there is no indication of soil or groundwater contamination on these properties, and therefore no further investigation is required at this time.

Please note that the Department's decision is based on information provided by the Marine Corps Air Station (MCAS) to date. Any information found to be contradictory to this decision may require additional action. Furthermore, the Department retains the right to request further investigation if deemed necessary.

If you have any questions, please contact me at kriegkm@dhec.sc.gov or 803-898-0255.

Sincerely,

Kent Krieg
Department of Defense Corrective Action Section
Bureau of Land and Waste Management
South Carolina Department of Health and Environmental Control

Cc: Russell Berry (via email)
Craig Ehde (via email)
Bryan Beck (via email)



Catherine E. Heigel, Director

Promoting and protecting the health of the public and the environment

Attachment to: Krieg to Drawdy
Subject: NFA
Dated 7/1/2015

Laurel Bay Underground Storage Tank Assessment Reports for: (153 addresses/161 tanks)

111 Birch	363 Aspen
123 Banyan	364 Aspen
131 Banyan	366 Aspen
134 Banyan	369 Aspen
145 Laurel Bay	373 Aspen
150 Laurel Bay	381 Aspen
153 Laurel Bay	401 Elderberry
154 Laurel Bay	402 Elderberry
155 Laurel Bay	404 Elderberry
200 Balsam	410 Elderberry
202 Balsam	420 Elderberry
203 Balsam	424 Elderberry
208 Balsam	435 Elderberry Tank 3
210 Balsam	452 Elderberry
211 Balsam	460 Elderberry
220 Cypress	465 Dogwood
222 Cypress	477 Laurel Bay
223 Cypress	487 Laurel Bay
252 Beech Tank 2	513 Laurel Bay
271 Beech Tank 1	519 Laurel Bay
271 Beech Tank 2	524 Laurel Bay
284 Birch Tank 1	535 Laurel Bay
284 Birch Tank 2	553 Dahlia
308 Ash	590 Aster
311 Ash	591 Aster
312 Ash	610 Dahlia
317 Ash	612 Dahlia
318 Ash	628 Dahlia
337 Ash	636 Dahlia
351 Ash Tank 1	637 Dahlia Tank 1
351 Ash Tank 2	637 Dahlia Tank 2
355 Ash Tank 1	641 Dahlia
355 Ash Tank 2	642 Dahlia Tank 1
360 Aspen	642 Dahlia Tank 2

Laurel Bay Underground Storage Tank Assessment Reports for: (153 addresses/161 tanks) cont.

655 Camellia	920 Albacore
662 Camellia	922 Barracuda Tank 1
683 Camellia	922 Barracuda Tank 2
684 Camellia	924 Albacore
689 Abelia	925 Albacore
694 Abelia	926 Albacore
695 Abelia	930 Albacore
741 Blue Bell	931 Albacore
742 Blue Bell	933 Albacore
755 Althea	936 Albacore
757 Althea	938 Albacore
776 Laurel Bay	939 Albacore
777 Azalea	940 Albacore
779 Laurel Bay	1010 Foxglove
781 Laurel Bay	1066 Gardenia
802 Azalea	1068 Gardenia
816 Azalea	1071 Heather Tank 2
822 Azalea	1100 Iris Tank 2
823 Azalea	1128 Iris
825 Azalea	1178 Bobwhite
828 Azalea	1204 Cardinal
837 Azalea	1208 Cardinal
851 Dolphin	1209 Cardinal
856 Dolphin	1210 Cardinal
857 Dolphin	1215 Cardinal
861 Dolphin	1216 Cardinal
864 Dolphin	1217 Cardinal Tank 1
868 Dolphin	1217 Cardinal Tank 2
872 Dolphin	1233 Dove
879 Cobia	1244 Dove
886 Cobia	1250 Dove
888 Cobia	1252 Dove
889 Cobia	1254 Dove
901 Barracuda	1256 Dove
902 Barracuda	1258 Dove
903 Barracuda	1263 Dove
904 Barracuda	1269 Dove
909 Barracuda	1276 Dove
910 Barracuda	1283 Dove
914 Barracuda	1285 Dove
915 Barracuda	1288 Eagle

Laurel Bay Underground Storage Tank Assessment Reports for: (153 addresses/161 tanks) cont.

1296 Eagle	1330 Albatross
1307 Eagle	1331 Albatross
1321 Albatross	1333 Albatross
1322 Albatross	1334 Albatross
1327 Albatross	1335 Albatross
1328 Albatross	